

Town of Wilbraham, Massachusetts

Illicit Discharge Detection and Elimination Program

NPDES Permit # MAR041025
June 2019

| Section 1 | Introduction | |
|-----------|--|-----|
| 1.1 | Background | 1-1 |
| 1.2 | Plan Applicability | 1-1 |
| 1.3 | Definition of an Illicit Discharge | 1-3 |
| 1.4 | Illicit Discharges and Water Quality | 1-4 |
| 1.5 | Summary of EPA Requirements | 1-4 |
| 1.6 | Purpose of the IDDE Program Plan | 1-6 |
| Section 2 | Sanitary Sewer and Septic Systems | |
| 2.1 | Sanitary Sewer System Management | 2-1 |
| 2.2 | Septic System Management | 2-1 |
| 2.3 | Action Plan | 2-2 |
| Section 3 | Stormwater System Mapping | |
| 3.1 | 2016 Small MS4 General Permit Requirements | 3-1 |
| 3.2 | Wilbraham's MS4 Mapping Status | 3-2 |
| 3.3 | Outfall Inventory | 3-2 |
| 3.4 | Action Plan | 3-3 |
| Section 4 | Non-Stormwater Discharge Bylaw | |
| 4.1 | Stormwater Phase II Comprehensive By-Law | 4-1 |
| 4.2 | Action Plan | 4-1 |
| Section 5 | Statement of IDDE Program Responsibilities | |
| 5.1 | Protocol for IDDE Program Responsibilities | 5-1 |
| 5.2 | Action Plan | 5-2 |
| | Assessment and Priority Ranking of Outfalls and erconnections | |
| 6.1 | Priority Ranking | 6-1 |
| 6.2 | Action Plan | |
| Section 7 | Identification of Illicit Discharges | |
| 7.1 | Dry Weather Outfall and Interconnection Screening and Sampling | 7-1 |
| | 7.1.1 Procedures and Guidance | |
| | 7.1.2 Impaired Waterbodies | 7-2 |
| 7.2 | Catchment Investigation Procedure | |
| | 7.2.1 Review of Mapping and Historic Plans | |
| | 7.2.2 Manhole Inspection Methodology | |
| | 7.2.3 Procedures to Isolate and Confirm Sources | |
| 7 3 | Catchment Investigation Timeline | 7_1 |

Tighe&Bond

| 7.4 | Action Plan7-4 | | | | | |
|----------------------------------|--|--|--|--|--|--|
| Section 8 | Removal and Confirmation | | | | | |
| 8.1 | Removal of Illicit Discharges8-1 | | | | | |
| 8.2 | Compliance Schedule and Reporting to EPA8-1 | | | | | |
| 8.3 | Confirmation Screening8-2 | | | | | |
| 8.4 | Ongoing Screening8-2 | | | | | |
| 8.5 | Action Plan8-3 | | | | | |
| Section 9 | Illicit Discharge Prevention | | | | | |
| 9.1 | Public Education9-1 | | | | | |
| 9.2 | Annual Employee Training9-2 | | | | | |
| 9.3 | Action Plan9-2 | | | | | |
| Section 1 | 0 Evaluation of IDDE Program Progress and Reporting | | | | | |
| 10.1 | Reporting10-1 | | | | | |
| 10.2 | Action Plan | | | | | |
| Appendice | es | | | | | |
| Appendix A | Town of Wilbraham's Stormwater Phase II Comprehensive By-law | | | | | |
| Appendix B | Excerpts from the 2016 Small MS4 General Permit | | | | | |
| Appendix C | SSO Inventory and Reporting | | | | | |
| Appendix D | Outfall and Interconnection Inventory, Initial Ranking, and Initial Catchment Delineations | | | | | |
| Appendix E | IDDE Statement of Responsibility | | | | | |
| Appendix F | Written Procedures and Forms | | | | | |
| Appendix G | Impaired Waters and TMDLs | | | | | |
| Appendix H | Tracking Implementation Goals and Milestones | | | | | |
| Appendix I IDDE Training Program | | | | | | |
| | | | | | | |

J:\W\W1929 Wilbraham\019 MS4 PY1\Report_Evaluation\Written IDDE Plan\Town of Wilbraham IDDE Program_Text.docx

| Commonly Used Abbreviations | Definitions | | | |
|--------------------------------|--|--|--|--|
| CFR | Code of Federal Regulations | | | |
| CMRSWC | Central Massachusetts Regional Stormwater Coalition | | | |
| EPA | Environmental Protection Agency | | | |
| GIS | Geographic Information System | | | |
| GPS | Global Positioning System | | | |
| IDDE | Illicit Discharge Detection and Elimination | | | |
| MassDEP | Massachusetts Department of Environmental Protection | | | |
| MCM | Minimum Control Measure | | | |
| MS4 | Municipal Separate Storm Sewer System | | | |
| NPDES | National Pollutant Discharge Elimination System | | | |
| SOP | Standard Operating Procedure | | | |
| SSO | Sanitary Sewer Overflow | | | |
| SWMP | Stormwater Management Program | | | |
| TMDL | Total Maximum Daily Load | | | |

Section 1 Introduction

1.1 Background

The Environmental Protection Agency (EPA) nationally regulates the discharge of stormwater runoff that is transported into local waterbodies through Municipal Separate Storm Sewer Systems (MS4) that are located in Urbanized Areas (also known as "Regulated Areas"). The Town of Wilbraham meets EPA's regulatory threshold, and therefore is required to obtain coverage under a National Pollutant Discharge Elimination System (NPDES) permit for its stormwater discharges from the MS4 in its Urbanized Area.

In Massachusetts, the EPA Region 1 and the Massachusetts Department of Environmental Protection (MassDEP) jointly administer the municipal stormwater program and authorize Wilbraham to discharge stormwater under the NPDES General Permit for Storm Water Discharges from Small Municipal Separate Storm Sewer Systems, known as the "Small MS4 General Permit." The permit was first issued in 2003 and an updated permit was issued in 2016. Under this program, the Town has developed and implemented a Stormwater Management Program (SWMP) to reduce the contamination of stormwater runoff and prohibit illicit discharges.

The Small MS4 Program contains six elements called *minimum control measures* (MCMs) that, when implemented, should result in a significant reduction in pollutants discharged into receiving waters. The MCMs are:

- 1. Public Education and Outreach
- 2. Public Involvement and Participation
- 3. Illicit Discharge Detection and Elimination (IDDE)
- 4. Construction Site Stormwater Runoff Control
- 5. Post-Construction Stormwater Management
- 6. Good Housekeeping and Pollution Prevention

Once implemented, the IDDE Program described herein will satisfy the requirements under the third MCM and is one part of Wilbraham's overall SWMP for compliance under the Small MS4 General Permit.

1.2 Plan Applicability

This IDDE Plan should be implemented throughout the MS4 in Wilbraham's Regulated Area. Regulated Areas are defined by the latest Urbanized Area delineated in the United States decennial census. Figure 1.1, below, includes EPA's map showing Wilbraham's Regulated Area (in red hatching) based on the 2000 and 2010 censuses.¹

¹ https://www3.epa.gov/region1/npdes/stormwater/ma/ram/wilbraham.pdf

Tighe&Bond





Figure 1.1. Wilbraham's Urbanized Area under the NPDES program based on the 2000 and 2010 censuses.

1.3 Definition of an Illicit Discharge

An "illicit discharge" is defined by 40 CFR 122.26(b)(2) as any discharge to a MS4 that is not composed entirely of stormwater. Exceptions include allowable discharges pursuant to a NPDES permit and discharges that are not anticipated to introduce pollutants into the storm drain system. Under the 2016 Small MS4 General Permit and Wilbraham's Stormwater Phase II Comprehensive By-Law, Part II: Illicit Discharges to the Municipal Storm Drain System, the following discharges are considered exempt provided that the source is not a significant contributor of pollution to the municipal storm drain system:

- Discharge or flow from firefighting activities
- Waterline flushing
- Flow from potable water sources
- Springs
- Natural flow from riparian habitats and wetlands
- Diverted stream flow
- Rising groundwater
- Uncontaminated groundwater infiltrating as defined in 40 CFR 35.2005(20), or uncontaminated pumped groundwater



- Discharge from landscape irrigation or lawn watering
- Water from individual residential car washing
- Discharge from dechlorinated swimming pool water (less than 1 ppm chlorine), provided the water is allowed to stand for one week prior to draining and the pool is drained in such a way as to not cause a nuisance
- Discharge from street sweeping
- Discharge or flow resulting from DPW ice and snow control operations
- Dye testing, provided verbal notification is given to the DPW prior to the time of the test
- Non-stormwater discharge permitted under an NPDES permit, waiver, or waste discharge order administered under the authority of the EPA, provided that the discharge is in full compliance with the requirements of the permit, waiver, or order and applicable laws and regulations
- Discharge for which advanced written approval is received from the DPW as necessary to protect public health, safety, welfare, and the environment



Sump pump discharges may discharge to the MS4 provided the flow is "uncontaminated pumped groundwater."

Tighe&Bond

A copy of the Town's *Stormwater Phase II Comprehensive By-Law* is provided in **Appendix A**.

Illicit discharges can enter the drainage system through direct connections or indirect sources. A direct connection is any non-stormwater pipe connected to the storm drain system, such as pipe from a washing machine or floor drain or a sewer line from a house.

An indirect discharge may come from a wide variety of sources, such as sanitary sewer overflows (SSOs), infiltration into the drainage system from failed septic systems, or hazardous waste spills collected by storm drains. Grass clippings, leaf litter, and other solid material dumped or otherwise deposited in the storm drain system are also considered illicit discharges.



Direct discharge from a straight pipe (from IDDE Guidance Manual, CWP, 2004).

1.4 Illicit Discharges and Water Quality

Illicit discharges contribute elevated levels of pollutants to surface waterbodies and can potentially enter groundwater. These pollutants can include:

- Heavy metals
- Toxics
- · Oil and grease
- Solvents
- Nutrients such as nitrogen and phosphorus
- Pesticides and fertilizers from lawns
- Sediment from construction sites
- Viruses and bacteria

When these pollutants enter waterbodies, they can contaminate drinking water supplies, hinder recreation activities, and harm aquatic and other wildlife habitats.

1.5 Summary of EPA Requirements

As part of the 2003 Small MS4 General Permit, the Town of Wilbraham was required to develop, implement, and enforce a program to detect and eliminate illicit discharges. As required by Part II.B.3 of the 2003 Small MS4 General Permit, this illicit discharge program must contain the following elements:

1. If not already existing, the Town must develop a storm sewer system map. At a minimum, the map must show the location of all outfalls and the names of all waters that receive discharges from those outfalls. Additional elements may be included on the map, such as, location of catch basins, location of manholes, and location of pipes within the system. Initial mapping should be based on all existing information available to the Town including project plans, city records and drainage maps. Field surveys may be necessary to verify existing records and locate all outfalls.

- 2. To the extent allowable under state law, the Town must effectively prohibit, through a **regulatory mechanism** (such as a local bylaw or ordinance), non-stormwater discharges into the system and implement appropriate enforcement procedures and actions. If a regulatory mechanism does not exist, development and adoption of such a mechanism must be included as part of the SWMP.
- 3. The Town must develop and implement a plan to **detect and address non-stormwater discharges**, including illegal dumping, into the system. The illicit discharge plan must contain the following elements:
 - a. Procedures to identify priority areas. This includes areas suspected of having illicit discharges, for example: older areas of the city, areas of high public complaints and areas of high recreational value or high environmental value such as beaches and drinking water sources.
 - b. Procedures for locating illicit discharges (visual screening of outfalls for dry weather discharges, dye or smoke testing).
 - c. Procedures for locating the source of the discharge and procedures for the removal of the source.
 - d. Procedures for documenting actions and evaluating impacts on the storm sewer system subsequent to the removal.
- 4. The Town must **inform users of the system and the general public** of hazards associated with illegal discharges and improper waste disposal. The Town must train field inspectors to recognize illicit discharges.
- 5. The **non-stormwater discharges** listed in Section 1.3 of this IDDE Plan must be addressed if they are identified as being significant contributors of pollutants.

Wilbraham met the IDDE requirements of the 2003 Small MS4 General Permit.

The 2003 Small MS4 General Permit expired in April 2008, but it was administratively continued and remained in force and in effect until July 1, 2018. On April 13, 2016, the U.S. EPA published the final NPDES General Permits for Stormwater Discharges from Small Municipal Separate Storm Sewer Systems in Massachusetts. The 2016 Small MS4 General Permit substantially increases stormwater management requirements relative to the 2003 Small MS4 General Permit, and mandates specific timelines for compliance.

The new IDDE requirements in the 2016 Small MS4 General Permit include the following elements that build on the 2003 Small MS4 General Permit IDDE requirements, as fully described in the 2016 Small MS4 General Permit Section 2.3.4. The elements listed below build on the 2003 IDDE requirements:

- 1. The Town must develop an **inventory of known locations of SSOs** that occurred within the previous five years within 120 days of the effective date of the General Permit, and document and summarize SSOs in the Annual Report. Wilbraham does not currently have a municipal sewer system, and this requirement is therefore currently not applicable.
- 2. An **inventory of all MS4 outfalls and interconnections** must be developed within one year of the effective date of the General Permit.
- 3. The existing **stormwater map** must be built upon by including all outfalls, interconnections with other MS4s, catch basins, manholes, pipes, flow direction, catchment delineations, and public and private BMPs. This additional mapping must be complete within two years of the effective date of the permit.

Additional items must be added for all outfalls within ten years of the effective date of the permit: latitude and longitude for all outfalls, pipes, manholes, catch basins, refined catchment delineations, and municipal sanitary/combined sewer system (if applicable at that time).

- 4. A **written IDDE Plan** must be developed within one year of the effective date of the permit. This document was prepared to meet this requirement.
- 5. The Town must sample during dry weather² at all outfalls where flow is present, and test the flow for signs of illicit discharges within three years of the permit effective date.
- 6. Based on the results of sampling and characteristics of the catchment areas, the Town must rank all MS4 catchments for potential of illicit discharges into the following categories: "Problem", "High Priority", "Low Priority", and "Excluded".
- 7. A **catchment investigation procedure** that includes a systematic investigation of prioritized catchments, screening of key junction manholes, and wet weather outfall screening in catchments with system vulnerability factors must be developed and implemented.
- 8. An **annual training** must be provided for all employees involved in the IDDE Program on how to recognize illicit discharges (and, if applicable, SSOs).
- 9. **Program progress and effectiveness** must be evaluated and reported on yearly in the Annual Report.

Appendix B includes applicable excerpts from the 2016 Small MS4 General Permit.

1.6 Purpose of the IDDE Program Plan

The IDDE Program described herein establishes a proactive, written program to address illicit discharges to the MS4. The IDDE Program includes activities for compliance with the 2016 Small MS4 General Permit, under which the Town of Wilbraham is currently authorized to discharge stormwater.³

² Per section 2.3.4.7 b.ii of the 2016 Small MS4 General Permit, dry weather screening and sampling shall proceed only when no more than 0.1 inches of rainfall has occurred in the previous 24-hour period and no significant snow melt is occurring.

³ The authorization to discharge for NPDES Permit ID # MARO41025, Town of Wilbraham, was received on June 4, 2019: https://www3.epa.gov/region1/npdes/stormwater/ma/tms4noi/wilbraham-auth.pdf

Section 2 Sanitary Sewer and Septic Systems

Sanitary sewage can be linked to significant indirect illicit discharges in the form of sewage infiltration to the storm drain. According to section 2.3.4.4.c of the 2016 Small MS4 General Permit, the Town must provide oral notice of an SSO to EPA within 24 hours upon becoming aware of the SSO occurrence. Additionally, the Town must provide written notice to EPA and MassDEP within five (5) days of becoming aware of the SSO occurrence. The MassDEP SSO Reporting form is included in **Appendix C**.

2.1 Sanitary Sewer System Management

Wilbraham's public sewer system serves 1,000 customers, approximately 7% of the Town's population. All wastewater is collected and send to the Springfield Regional Wastewater Treatment Facility on Bondi's Island in Agawam, a 67 million gallons per day capacity wastewater treatment facility that discharges to the Connecticut River. The Town's collection system includes approximately 24 miles of sewer main, as well as 8 municipal pump stations.⁴

The Town does not have interconnected storm and sanitary sewer infrastructure, and therefore has not experienced any overflows due to storm events. The Town must track future SSOs and update the SSO Inventory included in **Appendix C** and the Town's written Stormwater Management Plan.

2.2 Septic System Management

Incorrectly managed or malfunctioning septic systems have the potential to discharge improperly treated or excess quantities of wastewater to the MS4, either due to infiltration via groundwater or through septic system breakouts over land, resulting in a discharge of sanitary sewage from the MS4 to receiving waters. Typical pollutants found in septic systems are nutrients, pathogens, dissolved metals, detergents, and solvents. However, the Town mitigates this potential pollution source by implementing Title 5 of the State Environmental Code through its Board of Health.

The majority of the Town of Wilbraham's population, approximately 70%, is served by septic systems. Like most New England communities, there are areas with high groundwater and poor soils in Wilbraham, and these factors combined with densely populated neighborhoods and steep hills could increase the likelihood of septic system challenges. In Wilbraham, areas of the Town with shallow bedrock and/or thick till east of Main Street have been identified as having difficulty in providing sufficient subsurface treatment from traditional on-site wastewater systems.⁵

⁴ https://www.wilbraham-ma.gov/192/Wastewater

⁵ https://www.wilbraham-ma.gov/DocumentCenter/View/1534/OSRP-2014-2021

2.3 Action Plan

| | Action Items: Illicit Discharge Bylaw | | | | | |
|----|---------------------------------------|--|--|--|--|--|
| 1. | Track and maintain an SSO inventory. | Create and update the SSO inventory annually as needed, update the SWMP and IDDE Plan, and summarize in Annual Reports. Provide oral notice to EPA within 24 hours of identifying an SSO. Provide written notice to EPA and MassDEP within five days. | | | | |
| 2. | Coordinate with Board of Health | The Board of Health should be trained on the IDDE Program to help identify incidences of illicit discharges, particularly when a septic system has failed. Continue to support the Board of Health programs to promote proper maintenance of septic systems. | | | | |

Section 3 Stormwater System Mapping

3.1 2016 Small MS4 General Permit Requirements

Storm drain system mapping is an essential tool in identifying illicit discharges. Minimum mapping elements required by the 2016 Small MS4 General Permit are broken into two phases:

Phase I (required within two years of the effective date of the permit):

- Outfalls and receiving waters (required by 2003 Small MS4 General Permit)
- Open channel conveyances (swales, ditches, etc.)
- Interconnections with other MS4s and other storm drain systems
- Municipally-owned stormwater treatment structures (e.g., detention and retention basins, infiltration systems, bioretention areas, water quality swales, gross particle separators, oil/water separators, or other proprietary systems)
- Waterbodies identified by name and indication of all use impairments as identified on the most recent EPA approved Massachusetts Integrated List of waters report pursuant to Clean Water Act Section 303(d) and 305(b)
- Initial catchment delineations. A catchment is the area that drains to an individual outfall or interconnection

Phase II (required within ten years of the effective date of the permit):

- Outfall spatial location (latitude and longitude, minimum accuracy of \pm 30 feet)
- Pipes
- Catch basins
- Manholes
- Refined catchment delineations
- Municipal sanitary sewer system (not applicable)
- Municipal combined sewer system (not applicable)

The following mapping elements are not required, but are **recommended**:

- Storm sewer material, size and age
- Sanitary sewer system material, size, and age
- Privately owned stormwater treatment structures
- Properties known or suspected to be served by a septic system, especially in high-density urban areas
- Area where the Town's MS4 has been or could be influenced by septic system discharges (e.g., areas with poor soils, or high ground water elevations unsuitable for conventional subsurface disposal systems)
- Seasonal high groundwater table elevations impacting sanitary alignments

- Topography
- Orthophotography
- Alignments, dates and representation of work completed (with legend) of past illicit discharge investigations (e.g., closed circuit television (CCTV), flow isolation, dye testing)
- Locations of suspected, confirmed and corrected illicit discharges (with dates and flow estimates)

3.2 Wilbraham's MS4 Mapping Status

The Town of Wilbraham has completed initial mapping of the MS4 using existing plans and field work to obtain locations of drainage system elements using Global Positioning System (GPS). A working draft of the drainage system map is included in **Appendix D**. Up-to-date mapping is available from the Wilbraham DPW. As of the date of this report, the following elements are mapped within the urbanized area:

- · Receiving waterbodies
- 241 known outfalls
- Approximately 55 miles of storm drainage pipe
- Initial catchment delineations
- All sub-watersheds

The mapping requirements of the 2003 Small MS4 General Permit have been met, and many of the requirements of the 2016 Small MS4 General Permit have been completed or are underway. The mapping element totals listed above are subject to change as the Town completes ongoing mapping improvement efforts. Additional mapping is needed to confirm the connectivity of the system and number of outfalls, as well as add attribute data to the structures. As the mapping effort progresses, **Appendix D** should be updated to reflect changes and additions to the system mapping and MS4 inventory.

3.3 Outfall Inventory

The Town must develop and maintain an inventory of all of the Town's outfalls and interconnections. This inventory identifies each outfall discharging from the MS4, records its location and condition, and provides a framework for tracking inspections, screenings, and other activities under the Town's IDDE Program. Refer to **Appendix D** for the initial outfall/interconnection inventory and priority ranking, initial catchment delineations, and working copies of associated drainage system maps.

Per Section 2.3.4.7.b.iii of the 2016 Small MS4 General Permit, the outfall/interconnection inventory shall include the following information:

- Unique identifier
- Receiving water
- Date of most recent inspection
- Dimensions

- Shape
- Material (concrete, PVC)
- Spatial location (latitude and longitude with a minimum accuracy of ± 30 feet)
- Physical condition
- Indicators of potential non-stormwater discharges (including presence or evidence of suspect flow and sensory observations such as odor, color, turbidity, floatables, or oil sheen) as of the most recent inspection.

The initial inventory in **Appendix D** was created from the existing GIS data and supplemented with record drawings and field measurements and observations. Tighe & Bond also created an application with ArcGIS online for mobile data collection with the Town's iPad, using the outfall investigation form in **Appendix F**. Location information was collected with a handheld GPS and input into a GIS database. GPS accuracy of a smart phone or tablet is sufficient to meet permit requirements. The Town's Sampling Protocol and relevant SOPs for sampling and analysis are available in **Appendix F**.

3.4 Action Plan

| | Action I tems: Stormwater System Mapping | | | | | |
|----|--|---|--|--|--|--|
| 1. | Maintain Outfall Inventory | The inventory shall be updated annually to include data collected in connection with the dry weather screening and other relevant inspections conducted by the Town or consultants. The inventory shall be included with each Annual Report. | | | | |
| 2. | Continue to Improve Drainage Mapping and Asset Inventory | Phase 1 mapping must be completed within two years of the effective date of the permit. The next priority will be identifying Town-owned BMPs and open channel conveyance systems. Phase 2 mapping will be completed within 10 years of the permit effective date and includes catchment delineations, pipes, manholes, and catch basins. | | | | |
| | | Throughout the permit term, the map will be updated as necessary to reflect newly discovered information, corrections or modifications, significant changes, and progress made. Updated maps may be added to Appendix D annually or kept electronically. When Annual Reports are prepared, the Town should print or save a pdf of the most up-to-date system map to document progress. | | | | |
| 3. | Map Availability and Data Management | The MS4 map is critical for the IDDE Program, outfall monitoring program, MS4 maintenance activities, and spill response and should be made accessible to Town personnel in a usable format (e.g., paper field maps or electronic on handheld device). | | | | |
| | | All personnel should be encouraged to report mapping errors, omissions, or other updates to the DPW. | | | | |

Section 4 Non-Stormwater Discharge Bylaw

4.1 Stormwater Phase II Comprehensive By-Law

The Town of Wilbraham has developed a by-law to regulate non-stormwater discharges to the MS4. The *Stormwater Phase II Comprehensive By-Law* was approved as Section 634 of the General By-Laws of the Town of Wilbraham at the Annual Town Meeting on May 14, 2007. A complete copy of the *Stormwater Phase II Comprehensive By-Law* is included as part of this plan in **Appendix A**. The DPW or its designated agent is designated to administer, implement, and enforce this bylaw, which meets the requirements of the 2016 Small MS4 General Permit.


4.2 Action Plan

| Action Items: Illicit Discharge Bylaw | | | | |
|---------------------------------------|---|--|--|--|
| 1. Implement Bylaw. | The Town's <i>Stormwater Phase II Comprehensive By-Law</i> shall be enforced when necessary for illicit discharges, illegal connections, and illegal dumping. Recommended procedures to require a private property owner to remove an illicit discharge are provided in Appendix E . | | | |

Section 5 Statement of IDDE Program Responsibilities

5.1 Protocol for IDDE Program Responsibilities

The DPW is responsible for overseeing and implementing the IDDE Program, including enforcement of the prohibition of illicit discharges, connections, and obstructions to the MS4. Additional authority for prohibition of illicit discharges and illegal dumping to the MS4 and water bodies in Wilbraham is granted to the Conservation Commission through the Massachusetts Wetlands Protection Act and Regulations.



Establishing procedures to coordinate Town personnel and departments is an important component of the IDDE Program and is required under Section 2.3.4.6.b of the 2016 Small MS4 General Permit. Wilbraham's protocol for IDDE Program responsibilities is provided in **Appendix E**. This statement is written in accordance with the requirements of the 2016 Small MS4 General Permit, and includes an explanation of specific areas of responsibility and a process for coordination and data sharing among various Town departments and personnel.

The following provides additional detail on responsibilities with regard to finding and removing illicit discharges:

- The DPW has the authority to enforce the prohibition of illicit discharges, connections, and obstructions to the MS4, and is designated to administer and implement the IDDE Program. The DPW serves as the lead local agency to manage the Town's IDDE Program and address EPA's permit requirements.
- The **Fire and Police Departments** are generally the first responders to accidents on roadways that would lead to an emergency spill that would affect the Town's storm drain infrastructure. When public utilities are affected, the DPW is notified via a phone call to the DPW Director.

- The **Health Department**, as the Public Health Agent for the Town, is responsible for overseeing Title 5 inspection results. Any septic related problems or complaints are handled by the Board of Selectmen, who notifies the DPW if any action is required on the part of the DPW.
- The **Building Inspector** notifies the Fire Department or the DPW, depending on the size of the spill, with a phone call when any spills are identified in the course of building inspections.

5.2 Action Plan

| | Action Items: Statement of IDDE Program Responsibilities | | | | | | |
|----|---|---|--|--|--|--|--|
| 1. | Update Protocol for IDDE Program Responsibilities as Needed | The DPW, with assistance from other relevant staff, may update or amend the written statement that identifies responsibilities with regard to eliminating illicit discharges. The most up-to-date Protocol for IDDE Program Responsibilities should be maintained in Appendix E . See also Section 8. | | | | | |
| 2. | Employee Training (see Section 9.2) | Train responsible Town personnel on the written IDDE protocol as part of the Annual Employee Trainings. | | | | | |

Section 6 Assessment and Priority Ranking of Outfalls and Interconnections

In assessing the storm drain system for illicit connections and discharges, prioritization helps focus energies on areas of greatest concern or where the greatest impact would be achieved. Since 2003, the Town of Wilbraham has generally prioritized areas discharging to impaired waters, Spectacle Pond and Chicopee River; industrial areas; and recreational areas. Under the 2016 Small MS4 General Permit, EPA requires a more rigorous assessment of illicit discharge potential and related public health significance. Additionally, per the 2016 Small MS4 General Permit, "the ranking will determine the priority order for the screening of outfalls and interconnections pursuant to part 2.3.4.7.b", and the compliance schedule for catchment investigations is based on this ranking.

6.1 Priority Ranking

Outfalls and interconnections, and their associated catchments must be assessed in terms of their potential to have illicit discharges and/or SSOs, and the related public health significance. The illicit discharge potential assessment and priority ranking will determine the order of outfall and interconnection screening and schedule for catchment investigations for evidence of illicit discharges and SSOs. This assessment also provides the basis for determining IDDE program milestones.

Outfalls and their associated catchments were ranked into the following categories based on potential for illicit discharges:

- Excluded Outfalls: this category is limited to roadway drainage in undeveloped areas with no dwellings and no sanitary sewers; drainage for athletic fields, parks or undeveloped green space and associated parking without services; cross-country drainage alignments (that neither cross nor are in proximity to sanitary sewer alignments) through undeveloped land.
- **Problem Outfalls**: outfalls/interconnections with known or suspected contributions of illicit discharges based on existing information are designated as Problem Outfalls, including any outfalls/interconnections where previous screening indicates likely sewer input.
- **High Priority Outfalls**: outfalls/interconnections that have not been classified as Problem Outfalls and that are: 1) discharging to an area of concern to public health due to proximity of public beaches, recreational areas, drinking water supplies or shellfish beds; or 2) determined by the permittee as high priority based on the characteristics listed in the permit or other available information.
- Low Priority Outfalls: outfalls/interconnections determined by the permittee as low priority based on the characteristics listed in the permit or other available information.

The characteristics of each of these categories have been defined by EPA in the 2016 Small MS4 General Permit Section 2.3.4.7.a.ii and iii.

Within each of these four ranking categories, the catchments will also be ranked based on screening factors. Per section 2.3.4.7.a.iii. of the 2016 Small MS4 General Permit, EPA's **minimum screening factors** include:

- Past discharge complaints and reports.
- Poor dry weather receiving water quality the following guidelines are recommended to identify waters as having a high illicit discharge potential:
 - o Exceeding water quality standards for bacteria
 - o Ammonia levels above 0.50 mg/L
 - o Surfactants levels greater than or equal to 0.25 mg/L.
- Density of generating sites Generating sites are those places, including institutional, municipal, commercial, or industrial sites, with a potential to generate pollutants that could contribute to illicit discharges. Examples of these sites include, but are not limited to: car dealers, car washes, gas stations, garden centers, and industrial manufacturing areas.
- Age of surrounding development and infrastructure Industrial areas greater than 40 years old and areas where the sanitary sewer system is more than 40 years old will probably have a high illicit discharge potential. Developments 20 years or younger will probably have a low illicit discharge potential.
- Sewer conversion Catchments that were once serviced by septic systems, but have been converted to sewer connections may have a high illicit discharge potential.
- Density of aging septic systems Septic systems thirty years or older in residential land use areas are prone to have failures and may have a high illicit discharge potential.
- Culverted streams Any river or stream that is culverted for distances greater than a simple roadway crossing may be considered "high."
- Water quality limited waterbodies that receive a discharge from the MS4 or waters with approved TMDLs applicable to the permittee, where illicit discharges have the potential to contain the pollutant identified as the cause of the water quality impairment.

An initial priority ranking of outfall/interconnections and the associated catchment areas using the screening criteria presented above, in addition to Town-specific criteria such as proximity to recreational areas. **Appendix D** contains the ranking methodology and assumptions, a summary table of preliminary outfall ranking, a summary table of preliminary catchment ranking, an initial outfall inventory, and a map of outfalls, preliminary catchment delineations, and preliminary rankings.

6.2 Action Plan

Action Items: Assessment and Priority Ranking of Outfalls/Interconnections

1. Update Illicit Discharge Potential Assessment and Priority Ranking An initial illicit discharge potential assessment and priority ranking based on existing information was completed as part of this Program and is located in $\bf Appendix\ D$.

The Town shall update its assessment and priority ranking continuously based on catchment delineations, the results of screening, and other new relevant information. The updated ranking shall be complete within three years of the effective date of the permit per section 2.3.4.7.c of the 2016 Small MS4 General Permit.

Section 7 Identification of Illicit Discharges

A key component of the IDDE Program is written procedures for screening and sampling outfalls and interconnections from the MS4 in dry and wet weather for evidence of illicit discharges and SSOs. This section summarizes the written procedures that the Town should use to identify illicit discharges and makes recommendations for prioritizing catchment investigations. These procedures heavily rely on the January 2012 Draft EPA New England Bacterial Source Tracking Protocol as well as guidelines from the Center for Watershed Protection.

Note that certain discharges are permitted through the EPA and MassDEP via other NPDES permitting programs, including the Municipal Wastewater and Industrial Wastewater permit programs. Outfalls permitted through these programs are not part of the Town's MS4 because they have different requirements and individual permits and plans. They do not need to be inventoried or monitored as part of the IDDE investigations. In Wilbraham, the following facilities are excluded from Wilbraham's outfall monitoring program:

- Friendly's Ice Cream Plant (Permit No. MAR054037), 1855 Boston Road
- Red Bridge Project Hydropower Station (Permit No. MAG360021), Red Bridge Road

Additional information on these facilities is available on EPA's Enforcement and Compliance History Online (ECHO) website: https://echo.epa.gov/.

7.1 Dry Weather Outfall and Interconnection Screening and Sampling

7.1.1 Procedures and Guidance

The Town will screen and sample outfalls and interconnections in accordance with the requirements in the 2016 Small MS4 General Permit. Per the 2016 Small MS4 General Permit, all outfalls (excluding Problem and Excluded outfalls) are required to be inspected for the presence of dry weather flow (when no more than 0.1 inches of rainfall has occurred within the previous 24-hour period and no significant snow melt is occurring) within three years of the effective permit date.

The following procedures and guidance are included in **Appendix F** and should be referenced during dry weather outfall/interconnection screening and sampling:

- Outfall Field Sheet, Adapted from Center for Watershed Protection's IDDE Manual
- Wilbraham Sampling Protocol and Field Equipment Checklist
- Chapter 11 of the Center for Watershed Protection's IDDE Manual, "Outfall Reconnaissance Inventory"
- Chapter 13 of the Center for Watershed Protection's IDDE Manual, "Tracking Discharges to a Source"
- EPA New England Bacterial Source Tracking Protocol, Draft 2012

7.1.2 Impaired Waterbodies

Some waterbodies within Wilbraham are impaired for various stormwater pollutants, such as bacteria, nutrients, and pathogens. Other impairments, such as Mercury in Fish Tissue, are not related to stormwater pollutants and are not addressed by the Small MS4 Program.

Specific impairments are compiled for Massachusetts's waterbodies in an Integrated List of Waters, which becomes the EPA's 303(d) list once finalized. The most recent 303(d) list is from 2014, which states that the Wilbraham waterbodies with stormwater pollutants include two segments of the Chicopee River (MA36-22, impaired by *Escherichia coli* and Mercury in Fish Tissue, and MA-36-24, impaired by Fecal Coliform) and Spectacle Pond (MA36142, impaired by Nutrient/Eutrophication Biological Indicators and subject to the TMDLs of Phosphorus for Selected Chicopee Basin Lakes.⁶

Where a discharge is directly to an impaired water or water subject to an approved TMDL, the sample should be analyzed for the pollutants identified as the cause of the impairment. These impairments and associated sampling requirements are included in the Dry Weather Sampling Procedure, located in **Appendix F**.

Note that a draft 2016 Integrated List of Waters is available from MassDEP, which adds an *Escherichia coli* impairment to the MA36-24 segment of the Chicopee River. However, the 2016 Integrated List of Waters has not been finalized and is not the official EPA 303(d) list; therefore, the Dry Weather Sampling Procedure has been developed based on the 2014 Integrated List. Excerpts from the final 2014 and draft 2016 Integrated Lists are included in **Appendix G**, with notes about the differences between the Lists.

7.2 Catchment Investigation Procedure

The Town's IDDE Program must include a written, systematic procedure for catchment investigation that includes:

- 1. A review of mapping and historic plans and records for the catchment;
- 2. A manhole inspection methodology; and
- 3. Procedures to isolate and confirm sources of illicit discharges.

Wilbraham will use the following procedure to develop a written procedure to evaluate and investigate each catchment according to section 2.3.4.8 of the 2016 Small MS4 General Permit.

7.2.1 Review of Mapping and Historic Plans

Based on relevant mapping and historic plans and records (to the extent available), the Town must identify and record the presence of any System Vulnerability Factors within each catchment. System Vulnerability Factors, as defined by Section 2.3.4.8.c.i of the 2016 Small MS4 General Permit, include the following situations:

 History of SSOs, including, but not limited to, those resulting from wet weather, high water table, or fat/oil/grease blockages

_

⁶ https://www.mass.gov/files/documents/2016/08/og/chicopee_0.pdf

- Common or twin-invert manholes serving both storm and sanitary sewer alignments
- Common trench construction serving both storm and sanitary sewer alignments
- Crossings of storm and sanitary sewer alignments where the sanitary system is shallower than the storm drain system
- Sanitary sewer alignments known or suspected to have been constructed with an underdrain system
- Inadequate sanitary sewer level of service (LOS) resulting in regular surcharging, customer back-ups, or frequent customer complaints
- Areas formerly served by combined sewer systems
- Sanitary sewer infrastructure defects such as leaking service laterals, cracked, broken, or offset sanitary infrastructure, directly piped connections between storm drain and sanitary sewer infrastructure, or other vulnerability factors identified through Inflow/Infiltration Analyses, Sanitary Sewer Evaluation Surveys, or other infrastructure investigations.

EPA also recommends including the following items as System Vulnerability Factors, although not required:

- Sewer pump/lift stations, siphons, or known sanitary sewer restrictions where power/equipment failures or blockages could readily result in SSOs
- Any sanitary sewer and storm drain infrastructure greater than 40 years old
- Widespread code-required septic system upgrades required at property transfers
- History of multiple Board of Health actions addressing widespread septic system failures

Where one or more of these System Vulnerability Factors are present, the Town must sample and inspect the catchment area during wet weather conditions to determine whether wet weather-induced high flows in sanitary sewers or high groundwater in areas served by septic systems result in the discharge of sanitary flow to the MS4.

7.2.2 Manhole Inspection Methodology

The Town shall systematically and progressively observe, sample, and evaluate all **key junction manholes** to locate evidence of illicit discharges. A **junction manhole** is defined as a manhole or manhole structure with two or more inlets accepting flow from two or more MS4 alignments. **Key junction manholes** are defined as junction manholes that can represent one or more junction manholes without compromising adequate implementation of the illicit discharge program.

The Town will begin at the most downstream key junction manhole (nearest to the outfall) and work upstream. Catchment investigations will be done in dry weather. Outfalls will only be screened during wet weather per Section 2.3.4.8.c.ii.2 where System Vulnerability Factors (see Section 7.2.1) have been identified. For manhole inspections, the Town will rely on in situ water quality screening such that a sample will be collected for laboratory analysis only if in situ field screening indicates a possible illicit discharge. Refer to Wilbraham's Sampling Protocol and Chapter 13 of the Center for Watershed Protection IDDE Manual in **Appendix F** for additional information regarding laboratory analysis parameters for Wilbraham's receiving waters.

Where water quality screening, sampling results, and/or visual and olfactory observations indicate a potential illicit discharge, the upstream area will be flagged for additional investigation and/or isolation and confirmation of sources (see Section 7.2.3).

The schedule to complete catchment investigations depends on the catchment priority ranking as updated after dry weather screening (see Action Item 1 in Section 6). Program milestones are in Section 7.3.

7.2.3 Procedures to Isolate and Confirm Sources

Chapter 13 of the Center for Watershed Protection IDDE Manual, "Tracking Discharges to a Source" is included in **Appendix F**. The Town will use this chapter as a guide for isolating and confirming sources of illicit discharges.

7.3 Catchment Investigation Timeline

According to the 2016 Small MS4 General Permit section 2.3.4.8.a, the following schedule is applicable to the Town of Wilbraham's investigation of catchments by Permit Year (PY).

| Catchment Investigation Requirement | PY 1 | PY 1.5 | PY 2 | PY 3 | PY 4 | PY 5 | PY 6 | PY 7 | PY 8 | PY 9 | PY 10 |
|---|---------|-----------|---------|---------|---------|---------|---------|--------------|---------|---------|-----------|
| Develop written catchment investigation procedure | | | | | | | | | | | |
| Investigations of catchments associated with Problem Outfalls | | | | | | | | >• | | | |
| Investigations of catchments with likely sewer input | | | | | | | | >• | | | |
| Investigations of catchments associated with High and Low Priority Outfalls | | | | - | | | | | | | *• |
| Year investigations required to | begi | in | | | | | | | | | |
| Ongoing investigations | | | | | | | | | | | |
| Year due | | | | | | | | | | | |

7.4 Action Plan

| | Action Items: Identification of Illicit Discharges | | | | | |
|----|---|--|--|--|--|--|
| 1. | Outfall and Interconnection Dry Weather Screening | The Town shall complete dry weather screening and sampling (where flowing) of every MS4 outfall and interconnection no later than three years from the effective date of the permit. Catchments where screening indicates a possible sanitary sewer input shall be ranked as High Priority for catchment investigations (see Section 6). | | | | |

| | Action Items: Identification of Illicit Discharges | | | | | |
|----|--|--|--|--|--|--|
| 2. | Identify Key Junction Manholes | The Town must identify key junction manholes, as defined in the 2016 Small MS4 General Permit, within each catchment area beginning with Problem and High Priority catchments identified according to Section 6. To the extent allowed, the Town should minimize the number of key junction manholes. Key junction manholes should be included in the Catchment Investigation Procedure, due within 18 months of the effective date of the permit. | | | | |
| 3. | Develop and Implement Catchment Investigation Procedure | The Town will develop and implement the Catchment Investigation Procedure described in Section 7.2 according to the schedule in Section 7.3. Documentation that tracks progress towards these goals should be kept in Appendix I ; large reports may be filed separately. | | | | |
| 4. | System Vulnerability Factors and Wet Weather Screening | EPA guidance will be used to determine whether one or more System Vulnerability Factors are present in catchment areas (refer to Section 7.2, Catchment Investigation Procedure, and the Initial Catchment Ranking in Appendix D). System Vulnerability Factors focus on potential for sanitary wastewater to discharge into the MS4 or environment. They must be recorded and reported annually for each catchment. For catchments with one or more System Vulnerability Factors, wet weather screening is required by the 2016 Small MS4 General Permit. | | | | |
| 5. | Ongoing Manhole Investigations and Outfall Monitoring Program | The Town will continue to perform dry and wet weather outfall and interconnection screening required in the 2016 Small MS4 General Permit in conjunction with the Catchment Investigation Procedure, such as confirmatory screenings and follow-up screenings. Documentation of outfall Screening and sampling should be added to Appendix I as it is available. | | | | |

Section 8 Removal and Confirmation

8.1 Removal of Illicit Discharges

Most corrective actions for an illicit discharge, once isolated, will involve some kind of infrastructure modification or repair. Structural repairs can range from simple plumbing projects to excavation and replacement of sewer lines, and can be used to eliminate a wide variety of direct discharges such as sewage, industrial, and commercial cross-connections. Structural repairs may also be necessary for indirect discharges, such as discharges from a failing septic system or washwater discharged outdoors, when the discharge enters an MS4 inlet or flows directly into receiving waters. Most transitory discharges, such as a liquid or oil spill or illegal dumping, are corrected simply with spill containment and clean-up procedures.

Recommended procedures to require a property owner to remove an illicit discharge are provided in **Appendix E**. This section discusses additional requirements and considerations for Wilbraham.⁷

8.2 Compliance Schedule and Reporting to EPA

Per Section 2.3.4.2 of the 2016 Small MS4 General Permit, the Town of Wilbraham must eliminate all illicit discharges to the MS4 or establish a schedule for elimination within 60 days of detection:

2.3.4.2 Elimination of Illicit Discharges

- a. Upon detection of an illicit discharge, the Town shall locate, identify, and eliminate the illicit discharge as expeditiously as possible. Upon identification of the illicit source the Town shall notify all responsible parties for any such discharge and require immediate cessation of improper disposal practices in accordance with the Town bylaw. Where elimination of an illicit discharge within 60 days of its identification as an illicit discharge is not possible, the Town shall establish an expeditious schedule for its elimination and report the dates of identification and schedules for removal in the Town's annual reports. The Town shall immediately commence actions necessary for elimination. The Town shall diligently pursue elimination of all illicit discharges. In the interim, the Town shall take all reasonable and prudent measures to minimize the discharge of pollutants to and from its MS4.
- b. The period between identification and elimination of an illicit discharge is not a grace period. Discharges from an MS4 that are mixed with an illicit discharge are not authorized by the General Permit and remain unlawful until eliminated.

⁷ Section 8.1 text is adapted from the Center for Watershed Protection's 2004 IDDE Manual, available online at https://www3.epa.gov/npdes/pubs/idde_manualwithappendices.pdf.

The Town shall include the following information in the Annual Report for each confirmed source:

- The location of the discharge and its source(s)
- A description of the discharge
- The date and method of discovery
- The date of elimination or planned corrective measures and a schedule for completing the illicit discharge removal
- Mitigation or enforcement action
- An estimate of the volume of flow removed

This information and additional reporting requirements will be used in evaluating IDDE Program progress and is further described in Section 10.

8.3 Confirmation Screening

Within one year of removal of all identified illicit discharge sources, confirmatory outfall or interconnection screening shall be conducted according to the 2016 Small MS4 General Permit requirements. The confirmatory screening shall be conducted in dry weather unless System Vulnerability Factors have been identified in the catchment as described in Section 7.2, in which case both dry weather and wet weather confirmatory screening shall be conducted.

If confirmatory screening indicates evidence of additional illicit discharges, the catchment shall be scheduled for additional investigation. Confirmatory screening is not required in catchments where no illicit discharges or System Vulnerability Factors have been identified and no previous screening indicated suspicious flows. Refer to the Flow Chart for Corrective Action in **Appendix E** for additional information about the process for eliminating an illicit discharge.

8.4 Ongoing Screening

Upon completion of catchment investigation according to the procedures in Section 7.2, and illicit discharge removal and confirmation (if necessary) pursuant to this Section, part 2.3.4.8.a of the 2016 Small MS4 General Permit requires that each outfall or interconnection be reprioritized for screening and scheduled for ongoing screening once every five years. Follow-up screening shall consist of dry weather screening and sampling, and wet weather screening and sampling is also required in catchments where wet weather screening was previously required.

8.5 Action Plan

| | Action Items: Removal and Confirmation | | | | | | |
|----|---|--|--|--|--|--|--|
| 1. | Follow Protocol and Document Actions | If an illicit connection or discharge is discovered, it is critical that the Town carefully adhere to protocol for removal, enforcement, and documentation described in this section and in the 2016 Small MS4 General Permit. If an illicit connection or discharge cannot be removed within 60 days, the Town must establish a schedule for elimination and include the schedule as well as the date the connection or discharge was identified in Annual Reports. | | | | | |
| 2. | Formalize Illicit Discharge Tracking | Formalize the tracking methodology for illicit discharge and connection discoveries, removal, and confirmation. Store data in a common repository so multiple Town departments can access and update as needed. | | | | | |

Section 9 Illicit Discharge Prevention

Elimination and ongoing prevention are the ultimate goals of the IDDE Program. The following Section provides options for the Town of Wilbraham to educate the public about illicit discharges and train municipal employees on the identification and elimination of known illicit discharges.

9.1 Public Education

Education is a useful tool in preventing illicit discharges. The 2003 Small MS4 General Permit required that the Town inform public employees, businesses, and the general public of hazards associated with illegal discharge and improper waste disposal. The 2016 Small MS4 General Permit requirements for Wilbraham public education include the following:

- Over the course of the permit term, Wilbraham must distribute a minimum of two messages to each of four audiences (residential, business/institutions, developers, and industrial).
- As an MS4 located within the Connecticut River watershed and subject to the Long Island Sound Nitrogen TMDL requirements outlined in Appendix F, Section B.1 of the 2016 Small MS4 General Permit, specific timed messages to residents and businesses/institutions/commercial facilities are required:
 - Annual message in the spring (Apr/May) that encourages proper use and disposal of grass clippings and encourages use of slow-release fertilizers
 - Annual message in the summer (Jun/Jul) that encourages proper management of pet waste
 - Annual message in the fall (Aug/Sept/Oct) that encourages proper disposal of leaf litter

Wilbraham may incorporate various educational activities into the Public Education Program with the goal of preventing illicit discharges to the drainage systems.

- Educate the public on illicit discharges and the impacts to the human health and the environment.
- Encourage awareness and promote stewardship of the storm drain system in neighborhoods.
 This may be accomplished through catch basin stencils or markers.
- Educate the public about the IDDE Program, Wilbraham's Stormwater Management Bylaw, and the consequences of violations.
- Post "No Dumping" signs at key locations to discourage illegal dumping by threatening fine or imprisonment.



Providing IDDE training to DPW staff and contractors that clean catch basins is a cost-efficient way to identify and report illicit discharges.

The target audience for education on illicit discharges and illegal dumping should include residents, businesses, institutions, commercial facilities, developers, and industrial facilities. Materials for public outreach can be obtained from the Pioneer Valley Planning Commission's Connecticut Stormwater Committee, the Massachusetts Think Blue website (https://www.thinkbluemassachusetts.org/), EPA Region 1's Stormwater Tools in New England website (https://www.epa.gov/npdes-permits/stormwater-tools-newengland) or other state and regional groups.

9.2 Annual Employee Training

The Town shall, at a minimum, annually provide training to employees involved in the IDDE Program, including how to recognize illicit discharges and procedures to find and eliminate illicit discharges in accordance with this Plan. Town employees, particularly those that spend time doing site visits and drain system inspections, should be trained. Town departments/boards that should receive training include, but are not limited to, the DPW, Conservation Commission, and the Boards of Selectmen, Planning, and Health. The Town shall report on the frequency and type of employee training in the Annual Report. Trainings can be either conducted for Wilbraham staff only or key Town personnel may attend outside training to meet this requirement.

9.3 Action Plan

| | Action Items: Illicit Discharge Prevention Procedures | | | | | |
|----|---|--|--|--|--|--|
| 1. | Develop an IDDE Training Program | The Town of Wilbraham must develop an employee training program, to be conducted annually, as described in section 9.2. The training program outline, presentations and materials, and sign-in sheets should be added to Appendix I . | | | | |
| | | The IDDE training can be periodically combined with other required training topics, such as good housekeeping and pollution prevention. | | | | |
| | | The Town may rely on EPA or MassDEP sponsored training events as well as regional training sponsored by the Pioneer Valley Regional Planning Commission's Connecticut River Stormwater Committee or a similar group. | | | | |
| | | Maintain the training date, topic and attendees in $\mbox{\bf Appendix I}$ for the Annual Report. | | | | |
| 2. | Continue Public Education | The 2003 Small MS4 General Permit requirements have been satisfied. When developing Wilbraham's Stormwater Management Program under the 2016 Small MS4 General Permit, include messaging to all four target audiences about illicit discharges and illegal dumping. | | | | |
| 3. | Follow Spill Prevention and Response Procedures | The Protocol for IDDE Program Responsibilities in Appendix E should be followed. Maintain the Oil Spill Prevention, Control, and Countermeasure (SPCC) Plan at the Fire Department. Coordinate with the Fire Department regarding spills and emergencies per the protocol established in the SPCC Plan. Update mapping and procedures as necessary. | | | | |

Section 10 Evaluation of IDDE Program Progress and Reporting

The Town shall define or describe indicators for tracking program success. At a minimum, indicators shall include measures that demonstrate efforts to locate illicit discharges, the number of illicit discharges identified and removed, the number and percent of total outfall catchments served by the MS4 evaluated using the catchment investigation procedure, all dry and wet weather screening and sampling results and the volume of sewage removed. The Town shall evaluate and report the overall effectiveness of the program based on the tracking indicators in the Annual Report.

Section 2.3.4.9 of the 2016 Small MS4 General Permit includes the minimum indicators for tracking of program success. These indicators are as follows:

- The number of illicit discharges identified and removed
- The number and percent of total outfall catchments served by the MS4 evaluated using the catchment investigation procedure
- All dry weather and wet weather screening and sampling results
- The volume of sewage removed.

In addition to the above measures of success, the Town will decide additional tracking indicators on a case by case basis and include in the SWMP.

Records must be kept for at least five years per Section 4.2.a of the Permit. Records under the IDDE Program include information used in the development of the written (hardcopy or electronic) IDDE Program, any monitoring results, copies of reports, records of screening, follow-up and elimination of illicit discharges; maintenance records; and inspection records.

10.1 Reporting

All outfall results shall be documented and reported on annually in the Annual Reports. Outfall monitoring results shall include the date, outfall or interconnection identifier, location, weather conditions at time of sampling, precipitation in previous 48 hours, field screening parameter results and results of all analyses. Results of any other stormwater or receiving water quality monitoring or studies conducted during the reporting period where that data is being used by the Town to inform permit compliance or program effectiveness shall also be reported on in the Annual Report per Section 4.3 of the GP.

In addition, the Town must report on the activities related to implementation of the IDDE Program in their Annual Reports according to section 4.4.b.iv of the Massachusetts Small MS4 GP. These activities include:

- Status of the map
- Status and results of the illicit discharge potential ranking and assessment
- Identification of Problem Catchments

- Status of all protocols described in part 2.3.4 of the permit (program responsibilities and systematic procedure)
- Number and identifier of catchments evaluated
- Number and identifier of outfalls screened
- Number of illicit discharges located
- Number of illicit discharges removed
- Gallons of flow removed
- Identification of tracking indicators and measures of progress based on those indicators
- Employee training

10.2 Action Plan

| Action Items: Evaluation of IDDE Program | | |
|--|---|---|
| 1. | Track Indicators of Program Success | The Town will track the indicators of IDDE Program Success, as listed above and report on them annually. The Town may include additional tracking indicators to aid in the annual evaluation. |
| 2. | Record Keeping | The Town will keep records of all IDDE activities in the DPW office. The majority of IDDE records will be maintained electronically and in Appendix H to this Plan, though large reports may be filed separately. Record keeping requirements are described in this Plan, and will include: • Outfall Inventory updates: dates, outfall location/ID, field observations. • Outfall Monitoring: dates, outfall location/ID, field observations, in situ and laboratory results, precipitation previous 48 hours. • Location, structure ID, pollutant of concern for suspected illicit discharges. • Log of follow-up activities to confirm and then locate illicit discharge – dates, locations, personnel, actions. • A log of phone calls and complaints received regarding suspected illicit connections and other storm drain issues. Note actions taken and dates. • Employee Training: dates, attendance sheet, and topics (include handouts or visuals if used). • Information used in the development of the Plan. • Inspection and maintenance records. |
| 3. | Annual Evaluation of Program Effectiveness | The Town will annually summarize and evaluate IDDE Program progress based on the EPA's requirements and tracking indicators in the Annual Report to the EPA and MassDEP. |

J:\W\W1929 Wilbraham\019 MS4 PY1\Report_Evaluation\Written IDDE Plan\Town of Wilbraham IDDE Program_Text.docx

Town of Wilbraham IDDE Program Appendix A Stormwater Bylaw

GENERAL BY-LAWS OF THE TOWN OF WILBRAHAM

Revised May 15, 2017



Adopted at the Annual Town Meeting of May 15, 2017 Approved by the Attorney General on August 31, 2017

Amended: May 14, 2018

Section 4: Policy Statement

"It is the policy of the Town, a Right to Farm community, to conserve, protect and encourage the maintenance and improvement of agricultural land for the production of food and other agricultural products, and also for its natural, recreational and ecological value."

The Agricultural Commission shall submit this policy statement as part of its Annual Report to the Town, and shall cause copies of said policy to be posted in various Town offices dealing with land use, including, but not limited to the Board of Assessors, Zoning Board of Appeals, Planning Board, and Conservation Commission.

Section 5: Procedure for Mediation

Any person having a complaint about a farm or farming activity or practice is encouraged to seek an amicable solution, including talking directly with the involved participant. Such person may, pursuit of other available remedies notwithstanding, request assistance from the Board of Selectmen. The Board of Selectmen may appoint a panel of at least three individuals, including a farmer and a member of the Agricultural Commission, to review and facilitate the resolution of the grievance, and to report its recommendations to the Board of Selectmen within an agreed-upon time frame.

Section 6: Severability Clause

If any part of this By-Law is for any reason found to be invalid, such decision shall not affect the remainder of this By-Law.

SECTION 634 STORMWATER PHASE II COMPREHENSIVE BY-LAW

(ATM, 5/14/07, Art. 43)

PART I LOCAL STORMWATER MANAGEMENT

SECTION A. PURPOSE AND AUTHORITY

1. Purpose

- a. The purpose of this By-Law is to better manage land alteration and development in order to protect, maintain, and enhance the public health, safety, and general welfare of the citizens of Wilbraham by establishing minimum requirements and procedures to control the **adverse impacts** associated with **stormwater runoff**. (Bolded words and phrases are defined under the definition section B).
- b. The proper management of stormwater runoff will meet the following objectives:
 - 1. Reduce the adverse water quality impacts of stormwater discharges to rivers, lakes, reservoirs and streams in order to meet federal water quality standards;
 - 2. Prevent the discharge of pollutants, including hazardous chemicals, into stormwater runoff;

- 3. Minimize the volume and rate of storm water, which is discharged to rivers, streams, reservoirs, lakes and storm sewers, that flows from any site during and following development;
- 4. Prevent erosion and sedimentation from land development, and reduce stream channel erosion caused by increased runoff;
- 5. Provide for the non-polluted recharge of groundwater aquifers and maintain the base flow of streams;
- 6. Provide storm water facilities that are attractive, maintain the natural integrity of the environment, and are designed to protect public safety;
- 7. Maintain or reduce pre-development runoff characteristics after development to the extent feasible;
- 8. Minimize damage to public and private property from flooding;
- 9. Ensure that these management controls are properly maintained; and
- 10. Comply with state and federal statutes and regulations relating to storm water discharges.

2. Authority

This By-Law is adopted under the authority granted by the Home Rule Amendment of the Massachusetts Constitution, the Home Rule statutes, and the regulations of the federal Clean Water Act found at Title 33 U.S.C. §§ 1252 1387 and 40 CFR 122.34.

3. Responsibility for Administration

The Town Department of Public Works (Wilbraham DPW) shall be the Permitting Authority/**Authorized Enforcement Agency** and shall administer, implement and enforce this By-Law. Any powers granted to or duties imposed upon the Wilbraham DPW to promulgate such rules and regulations shall not have the effect of suspending or invalidating this By-Law.

SECTION B. DEFINITIONS

1. Definitions

Unless otherwise expressly stated, the following definitions describe the meaning of the terms used in this By-Law:

Applicant - a person with the duty to apply for a permit hereunder

Authorized Enforcement Agency - The Town Department of Public Works (Wilbraham DPW), and its employees or agents designated to enforce this By-Law. Also see permitting authority below.

Adverse Impact - Any deleterious effect on waters or wetlands, including their quality, quantity, surface area, species composition, aesthetics or usefulness for human or natural uses which are or may potentially be harmful or injurious to human health, welfare, safety or property, to biological productivity, diversity, or stability or which unreasonably interfere with the enjoyment of life or property, including outdoor recreation.

Best Management Practices (BMP) - An activity, procedure, restraint, or structural improvement that helps reduces the quantity or improve quality of stormwater runoff. Some examples of BMPs are described in a stormwater design manual, Stormwater Management, Volume Two: Stormwater Technical Handbook (March, 1997, MA Department of Environmental Protection and MA Office of Coastal Zone Management, as updated or amended). Best Management Practices may include:

- Detention basins
- Deep sump catch basins
- Water quality swales
- Oil/sediment separators
- Vortex separators

Certificate of Completion - A written determination by the Wilbraham DPW that work has been completed in accordance with a Local Stormwater Management Permit. For major projects, a Certificate of Completion will be issued only after a Notice of Termination has been submitted to United States Environmental Protection Agency for termination of coverage under **NPDES**.

Construction Activity - The disturbance of the ground by removal of vegetative surface cover or topsoil, grading, excavation, clearing or filling.

Design Storm - A rainfall event of specified size and return frequency that is used to calculate the runoff volume and peak discharge rate.

Detention - The temporary storage of storm runoff which is used to control the Peak Discharge rates, and which provides gravity settling of pollutants.

Disturbance - Any activity which changes the volume or peak flow discharge rate of rainfall runoff from the land surface. This may include the clearing, grading, digging, scraping, or excavating of soil, placement of fill materials, paving, construction, substantial removal of vegetation, or any activity which bares soil or rock or involves the diversion or piping of any natural man-made watercourse.

Drainage Area - That area contributing runoff to a consolidated flow of water as measured in a horizontal plane.

Easement - A grant or reservation by the owner of land for the use of such land by others for a specific purpose or purposes, and which must be included in the conveyance of land affected by such easement.

Impervious Surfaces – Any material or structure on or above the ground that prevents water from infiltrating the underlying soil. Impervious surfaces include roads, pavement, building rooftops, sidewalks, and driveways.

Infiltration - The process of percolating water from the surface into the subsoil.

Local Stormwater Management Permit - A document issued by the Wilbraham DPW, including conditions, which regulates stormwater controls associated with land disturbance.

Operation and Maintenance Plan – A plan setting up the functional, financial and organizational mechanisms for the ongoing operation and maintenance of a stormwater management system to insure that it continues to function as designed.

Nonpoint Source Pollution - The Pollution from any source other than from any discernible, confined, and discrete conveyances, and shall include, but not be limited to, pollutants from agricultural, mining, construction, subsurface disposal and urban runoff sources.

National Pollutant Discharge Elimination System (NPDES) - As authorized by the Clean Water Act, is a permit program governed by the U.S. Environmental Protection Agency (EPA) that controls water pollution by regulating point sources that discharge pollutants into waters of the United States. A Notice of Intent is the mechanism used to "register" for coverage under a general permit. A Notice of Termination is the mechanism used to close out coverage under a general permit after construction completion.

NRCS - The United States Department of Agriculture Natural Resources Conservation Service.

Owners - The person owning the subject property at the time the application for the permit is made and the also subsequent owners and assignees.

Outfall - The terminus of a storm drain or other stormwater structure where the contents are released.

Peak Discharge - The maximum instantaneous rate of flow during a storm, usually in reference to a specific design storm event.

Permeable Soils - Soil materials with a sufficiently rapid infiltration rate so as to greatly reduce or eliminate surface and stormwater runoff. These soils are generally classified as NRCS hydrologic soil types A and B.

Permit - A **Local Stormwater Management** permit (see above)

Permitting Authority - The Wilbraham DPW, to which a person must apply for a permit under this By-Law.

Person - Any individual, group of individuals, association, partnership, corporation, company, business, organization, trust, estate, administrative agency, public or quasi-public corporation or body, the Commonwealth or political subdivision thereof.

Phasing - The disturbance of a parcel of land in distinct phases, with the stabilization of each phase completed before the disturbance of the next.

Recharge - The replenishment of underground water reserves.

Responsible Party - Transferees and assignees of this original owner/applicant

Retention - The holding of runoff in a basin without release except by means of evaporation, infiltration, or emergency bypass.

Stormwater Management Permit - See Local Stormwater Management Permit

Stormwater Runoff - The flow on the surface of the ground, resulting from precipitation.

Stormwater Pollution Prevention Plan (SWPPP) – Plan including minimum information as required for coverage under the EPA NPDES General Permit and with additional information as required by this By-Law.

Swale - A natural depression or wide shallow ditch used to temporarily store, route, or filter runoff.

2. Reference Documents

Stormwater Management Policy (March, 1997, Massachusetts Department of Environmental Protection).

Stormwater Management, Volume One: Stormwater Policy Handbook (March, 1997, Massachusetts Department of Environmental Protection and Massachusetts Office of Coastal Zone Management).

Stormwater Management, Volume Two: Stormwater Technical Handbook (March, 1997, Massachusetts Department of Environmental Protection and Office of Coastal Zone Management).

SECTION C. APPLICABILITY

- 1. Prior to the issuance of any Special Permit, Site Plan Approval, Building Permit for any proposed development listed below, a **Local Stormwater Management Permit**, must be approved by the Wilbraham DPW. No **person** shall, on or after the effective date of the By-Law, initiate any vegetation clearing, land grading, earth moving or development activities without first complying with this By-Law. The following uses and activities shall be regulated under this By-Law:
- a. Minor Projects: any proposed development **disturbing** an area of less than 43,560 square feet (1 Acre)

b. Major Projects:

- (1) Subdivisions and construction activities of any kind **disturbing** an area equal to or greater than 43,560 square feet (1 Acre); and
- (2) Development or redevelopment involving multiple separate activities in discontinuous locations or on different schedules if the activities are part of a larger common plan of development that all together disturbs an area equal to or greater than 43,560 square feet (1Acre).

SECTION D. EXEMPTIONS

- 1. To prevent the adverse impacts of stormwater runoff, the Wilbraham DPW has adopted the MA DEP Stormwater Management Policy as the set of performance standards that must be met at new development sites. These standards apply to construction activities as described under Section C. The following activities are exempt from these stormwater performance standards:
 - a. Any agricultural activity which is consistent with an approved soil conservation plan prepared or approved by the **NRCS**;
 - b. Any logging which is consistent with a timber management plan already approved under the Forest Cutting Practices Act by the Massachusetts Department of Conservation and Recreation;
 - c. Additions or modifications to existing single family structures where there is no proposed change in impervious area;
 - d. Any emergency activity that is immediately necessary for the protection of life, property or the environment, as determined by the Wilbraham DPW; and
 - e. Work undertaken by the Wilbraham DPW.

SECTION E. PERMIT PROCEDURES AND REQUIREMENTS

1. Approval of Local Stormwater Management Permit Required

No landowner shall receive a building, grading, or other land development permits required, or commence land **disturbance** activities, without approval of the Local Stormwater Management Permit and meeting the requirements of this By-Law. Approval by the Wilbraham DPW under this By-Law does not exempt the applicant from meeting the requirements of the federal **National Pollutant Discharge Elimination System (NPDES)** program, which requires a Notice of Intent be filed with the EPA and a **Stormwater Pollution Prevention Plan (SWPPP)** be prepared and maintained on site nor does it supersede compliance with the requirements of the Wilbraham Conservation Commission and the Massachusetts Department of Environmental Protection.

2. Application and SWPPP Requirements

a. Minor Projects

Applicants for a Local Stormwater Management Permit for Minor Projects are required to submit the non-refundable permit review fee with the Local Stormwater Management Permit Application and a site plan depicting the following information.

- 1. Name, address and telephone number of owner, professional engineer (if applicable) and contractor (if applicable)
- 2. Property lines
- 3. Existing zoning and land use at the site
- 4. Proposed land use
- 5. Location(s) of existing and proposed easements
- 6. Location of existing and proposed buildings and impervious surfaces
- 7. Location of existing and proposed Stormwater utilities, including dry wells, rain gardens or **swales** within 100' of the property line
- 8. Proposed driveway location and slope (not to exceed 2% within the first 20 feet measured from the paved road)
- 9. Septic system or sewer location
- 10. Well or water location
- 11. Limits of tree clearing
- 12. Limits of grading
- 13. Proposed erosion controls
- 14. Average slope of disturbed area as a percentage (%)
- 15. Delineation of 100 year flood plain if applicable

Every person disturbing a site with an average slope equal to or greater than 5% must post a bond or other approved means of security in an amount agreeable to Wilbraham DPW until the project is completed. The Wilbraham DPW may promulgate regulations setting forth the elements comprising the amount of and terms and conditions of the bond or other financial security required by this or other sections of this By-Law. Wilbraham DPW may require a SWPPP.

If a project is shown on a plan as part of a larger plan of development that is covered under an existing NPDES (NOI), but is, in actual fact, considered a separate development on a unique lot, as determined by the Wilbraham DPW, then Local Stormwater Management Permit coverage is required for both activities. This may apply to a residential or commercial subdivision, where one person is responsible for roadway construction and a separate person is responsible for building construction on subdivided lots.

b. Major Projects

Applicants for a Local Stormwater Management Permit for Major Projects are required to submit the non-refundable permit review fee along with the Local Stormwater Management Application, a copy of the following information that was sent to EPA:

- 1. NPDES Notice of Intent
- 2. SWPPP, including additional information as described in section E.(3)
- 3. An Operation and Maintenance Plan and Agreement.

All major projects must post a five hundred dollars (\$500) per acre of disturbed area bond.

3. Contents of the SWPPP for Major Projects - Every person applying for a Local Stormwater Management Permit for a major project shall submit a copy of the NPDES (NOI) and the SWPPP that was sent to the EPA. The SWPPP shall include sufficient information to evaluate the environmental characteristics of the affected areas, the potential impacts of the proposed development on water resources, and the effectiveness and acceptability of measures proposed for managing stormwater runoff. The SWPPP shall be designed to meet the Massachusetts Stormwater Management Standards as set forth in the DEP/CZM Stormwater Management Handbook Volumes I and II. The applicant shall certify on the drawings that all clearing, grading, drainage, construction, and development shall be conducted in accordance with the SWPPP.

The SWPPP shall be designed and stamped by a professional engineer. Prior to submission to the Town the SWPPP shall include the following minimum information:

- a. Name, address and telephone number of owner, professional engineer and **person** responsible for implementation of the plan
- b. Locus map
- c. Property lines
- d. Existing zoning and land use at the site
- e. Proposed land use
- f. Location(s) of existing and proposed easements
- g. Location of existing and proposed utilities
- h. Location of all existing and proposed buildings and impervious surfaces
- i. Erosion and sediment control provisions to minimize on-site erosion and prevent offsite sediment transport, including provisions to preserve topsoil and limit disturbance
- j. Design details for adequate access (i.e. easement, gravel roads, gates) for operation and maintenance of the **best management practices (BMPs)**
- k. Site's existing and proposed topography with contours at 2 foot intervals on the MA State Plane Coordinate System
- 1. Existing and proposed vegetation and ground surfaces
- m. Clear and definite delineation of any areas of vegetation or trees. Specify vegetation that is to be removed and vegetation that is to be saved.
- n. Description and delineation of existing stormwater conveyances, impoundments, and wetlands on or adjacent to the site or into which storm water flows or impacts
- o. Delineation of 100-year flood plains, if applicable
- p. Estimated seasonal high groundwater elevation in areas to be used for storm water retention, detention, or infiltration
- q. **Drainage area** map showing pre- and post-construction watershed boundaries and stormwater conveyances.
 - 1. Subcatchment areas for specific design points must include pre- and postdesign drawings, report, and a summary table for 2, 10, 50, 100 year **design storms** based on accepted engineering standards.
- r. A description and drawings of the proposed drainage system including:

- 1. locations, cross sections, and profiles of drainage swales and their method of stabilization
- 2. measures for the detention, retention or infiltration of water
- 3. measures for the protection of water quality
- 4. the structural details for the components of the proposed drainage systems and stormwater management facilities
- 5. notes on drawings specifying materials to be used and construction specifications
- 6. expected hydrology with supporting calculations
- 7. Proposed improvements including location of buildings or other structures, impervious surfaces, and drainage facilities, if applicable
- s. A description of construction and waste materials expected to be stored on-site, and a description of controls to reduce pollutants from these materials including storage practices to minimize exposure of the materials to storm water, and spill prevention and response consistent with those allowed in zoning district
- t. Timing, schedules, **phasing**, and sequence of development including clearing, stripping, rough grading, construction, final grading, and vegetative stabilization
- u. An inspection and maintenance schedule, including but not limited to replacement of compromised hay bales or silt fence, catch basin cleaning, or cleaning of sedimentation basins, for the period of construction, routine updates to the Wilbraham DPW may be required.
- v. Description of how project meets the Standards of the Massachusetts DEP Stormwater Management Policy as updated or amended, including back-up materials such as hydraulic calculations and detailed plans
- w. An **operation and maintenance plan and agreement** for continued operation and maintenance of each component of the stormwater management system, refer to Section H.

4. Additional Information for the SWPPP

The Wilbraham DPW may require any additional information or data deemed appropriate and may impose such conditions as may be deemed necessary to ensure compliance with the provisions of this By-Law, or to protect public health and safety.

5. Application Review Fees

The fee for review of any Local Stormwater Management Permit application shall be based on the amount of land to be disturbed at the site and the fee structure established by the Wilbraham DPW.

SECTION F. STORMWATER MANAGEMENT PERFORMANCE STANDARDS

In addition to other criteria used by the Wilbraham DPW in making permit decisions, for the uses specified in this By-Law, the Wilbraham DPW must also find that the Stormwater Pollution Prevention Plan submitted with the permit application meets the following criteria:

1. Minimum Control Standards

Projects must meet the Standards of the Massachusetts Stormwater Management Policy as updated or amended. These Standards are:

- a. No new stormwater conveyances (e.g. **outfalls**) may discharge untreated stormwater directly to or cause erosion in wetlands or water of the Commonwealth.
- b. Stormwater management systems must be designed so that post-development **peak discharge** rates do not exceed pre-development peak discharge rates.
- c. Loss of annual recharge to groundwater should be minimized through the use of infiltration measures to the maximum extent practicable. The annual recharge from the post-development site should approximate the annual recharge rate from the predevelopment or existing site conditions, based on soil types.
- d. For new development, stormwater management systems must be designed to remove 80% of the average annual load (post-development conditions) of Total Suspended Solids (TSS). It is presumed that this standard is met when:
 - (1) suitable nonstructural practices for source control and pollution prevention are implemented;
 - (2) stormwater management BMPs are sized to capture the prescribed runoff volume; and
 - (3) stormwater management BMPs are maintained as designed.
- e. Stormwater discharges from areas with higher potential pollutant loads require the use of specific stormwater management BMPs (Stormwater Management Volume I: Stormwater Policy Handbook, as updated or amended). The use of infiltration practices without pretreatment is prohibited.
- f. Stormwater discharges to critical areas must utilize certain stormwater management BMPs approved for critical areas (Stormwater Management Volume I: Stormwater Policy Handbook, as updated or amended). Critical areas are Outstanding Resource Waters (ORWs), shellfish beds, swimming beaches, cold water fisheries and recharge areas for public water supplies.
- g. Redevelopment of previously developed sites must meet the Stormwater Management Standards to the maximum extent practicable. However, if it is not practicable to meet all the Standards, new (retrofitted or expanded) stormwater management systems must be designed to improve existing conditions.
- h. Erosion and sediment controls must be implemented to prevent impacts during disturbance and construction activities.
- i. All stormwater management systems must have an operation and maintenance plan to ensure that systems function as designed.

When the proposed discharge may have an impact upon a sensitive receptor, including streams, storm sewers, and/or combined sewers, the Wilbraham DPW may require an increase in these minimum requirements, based on existing stormwater system capacity.

2. Erosion Control Performance Standards

Projects must address the following design requirements for erosion and sediment control.

- a. Minimize total area of disturbance;
- b. Sequence activities to minimize simultaneous areas of disturbance;
- c. Minimize peak rate of runoff in accordance with the MA Stormwater Management Policy;
- d. Minimize soil erosion and control sedimentation during construction; prevention of erosion is preferred over sedimentation control;
- e. Divert uncontaminated water around disturbed areas;
- f. Maximize groundwater recharge;
- g. Install, and maintain all erosion and sediment control measures in accordance with the manufacturer's specifications and good engineering practices;
- h. Prevent off-site transport of sediment;
- i. Protect and manage on and off-site material storage areas (overburden and stockpiles of dirt, borrow areas, or other areas used solely by the permitted project are considered a part of the project);
- j. Comply with all applicable Federal, State and local laws and regulations, including but not limited to, waste disposal, sanitary sewer or septic system regulations, and air quality requirements, including dust control;
- k. Prevent adverse impact from the proposed activities to habitats mapped by the Massachusetts Natural Heritage & Endangered Species Program as Estimated Habitats of Rare Wildlife and Certified Vernal Pools, and Priority Habitats of Rare Species;
- 1. Institute interim and permanent stabilization measures. The stabilization measures shall be instituted on a disturbed area as soon as practicable but no more than 14 days after **construction activity** has temporarily or permanently ceased on that portion of the site;
- m. Properly manage on-site construction and waste materials; and
- n. Prevent off-site vehicle tracking of sediments.

3. Criteria for Review of Local Stormwater Management Permit Applications

The Wilbraham DPW shall review each application to determine its conformance with the provisions of this section. The Wilbraham DPW shall review the permit application and issue a decision within 21 municipal business days after receiving an application. This timeframe may be extended at the sole discretion of the Wilbraham DPW if it requires additional information. Upon completion of the review, the Wilbraham DPW shall issue, in writing:

- 1) The Local Stormwater Management Permit based upon determination that the proposed plan meets the purposes in Section A and the standards in Section F and will adequately protect the water resources of the community and is in compliance with the requirements set forth in this By-Law;
- 2) Approval of the Local Stormwater Management Permit subject to any conditions, modifications or restrictions required by the Wilbraham DPW to meet the purposes in Section A and the standards in Section F to adequately protect water resources, set forth in this By-Law; and
- 3) Disapproval of the Local Stormwater Management Permit based upon a determination that the proposed plan, as submitted, does not meet the purposes in Section A and the standards in Section F or adequately protect water resources, as set forth in this By-Law.

SECTION G. INSPECTIONS

When any new drainage control facility is installed on private property, or when any new connection is made between private property and a public drainage control system or sanitary sewer, the filing of an application shall be deemed as the property owner's permission to the Wilbraham DPW, or their agents for the right to enter the property at reasonable times and in a reasonable manner for the purpose of the inspection. This includes the right to enter a property when the Wilbraham DPW has a reasonable basis to believe that a violation of this By-Law is occurring or has occurred, and to enter when necessary for abatement of a public nuisance or correction of a violation of this By-Law.

The applicant shall notify the Wilbraham DPW within 48 hours prior to the following activities. At its discretion, the Wilbraham DPW may enter the property to observe these activities:

- a) Installation of erosion and sediment control measures;
- b) Site clearing;
- c) Installation of permanent stormwater structures prior to backfilling of any underground drainage
- d) or stormwater conveyance structures; and
- e) Construction completion: Contractor shall notify Wilbraham DPW in writing when all work, including construction of stormwater management facilities and landscaping, has been completed and the site is stabilized. For all major projects, the NPDES Notice of Termination must also be filed with EPA and a copy provided to the Wilbraham DPW prior to final inspection or issuance of **Certificate of Completion**.

The applicant shall submit an "as-built" plan for the stormwater controls after the final construction is completed. The plan must show the final design specifications of all stormwater management controls and Wilbraham DPW may require the plan be prepared by a professional engineer. The as-built plan shall be submitted digitally in accordance with Wilbraham Engineering Department standards, or a conversion fee shall be required. Wilbraham DPW shall issue a Certificate of Completion once all requirements have been met.

The person responsible for implementation of the plan shall make regular inspections of all control measures in accordance with the inspection schedule outlined in the approved SWPPP. The purpose of such inspections shall be to determine the overall effectiveness of the control plan and the need for additional control measures. All inspections shall be documented in written form, maintained on site, and made available at the Wilbraham DPW's request. Such records shall be maintained by the applicant for at least 3 years from the day of final inspection.

SECTION H. MAINTENANCE REQUIREMENTS

1. Operation, Maintenance and Inspection Agreement

- a. binding on all subsequent owners of land served by the private stormwater management facility. The agreement shall be designed to ensure that water quality standards are met in all seasons and throughout the life of the system. Such agreement shall provide for access to the facility at reasonable times for regular inspections by the Wilbraham DPW, or its designated representative, and for regular or special assessments to property owners after costs of operation, maintenance and inspection to ensure that the facility is maintained in proper working condition to meet design standards and any conditions set forth in the permit. The agreement shall include:
 - 1. The name(s) of the owner(s) for all components of the system
 - 2. Maintenance agreements that specify
 - a. the names and addresses of the person(s) responsible for operation and maintenance;
 - b. the person(s) responsible for financing maintenance and emergency repairs;
 - c. a maintenance schedule for all drainage structures, including swales and ponds;
 - d. a list of easements with the purpose and location of each; and
 - e. the signature(s) of the owner(s).
 - 3. Stormwater management easements as necessary for:
 - a. access for facility inspections and maintenance;
 - b. preservation of stormwater runoff conveyance, infiltration, and detention areas and facilities, including flood routes for the 100-year storm event; and
 - c. direct maintenance access by heavy equipment to structures requiring regular cleanout.
 - 4. Stormwater management easement requirements
 - a. The purpose of each easement shall be specified in the maintenance agreement signed by the property owner.
 - b. Stormwater management easements are required for all areas used for off-site stormwater control, unless a waiver is granted by the Town.
 - c. Easements shall be recorded with the Registry of Deeds prior to issuance of a Certificate of Completion.
 - 5. Changes to Operation and Maintenance Plans
 - a. The owner(s) of the stormwater management system must notify the Wilbraham DPW of changes in ownership or assignment of financial responsibility.

- b. The maintenance schedule in the Maintenance Agreement may be amended to achieve the purposes of this By-Law by mutual agreement of the Wilbraham DPW and the Responsible Parties. Amendments must be in writing and signed by all Responsible Parties. Responsible Parties must include owner(s), persons with financial responsibility, and persons with operational responsibility.
- b. The agreement shall also provide that, if satisfactory corrections are not made by the owner(s) within thirty days of notice by the Wilbraham DPW, or designated representative, to correct a violation requiring maintenance work, the Town may perform or contract all necessary work to place the facility in proper working condition. The owner(s) of the facility shall be assessed the cost of the work and any penalties. If the costs are not paid, the Town may place a lien on the property or use available secured funds from bond provided.

2. Maintenance Responsibility

- a) The owner of the property on which work has been done pursuant to this By-Law for private stormwater management facilities, or any other person or agent in control of such property, shall maintain in good condition and promptly repair and restore all grade surfaces, walls, drains, dams and structures, vegetation, erosion and sediment control measures and other protective devices. Such repairs or restoration and maintenance shall be in accordance with approved plans.
- b) A maintenance schedule shall be developed for any stormwater management facility and shall state the maintenance to be completed, the time period for completion, and who shall be legally responsible to perform the maintenance. This maintenance schedule shall be printed on the stormwater management plan.
- c) Records of installation and maintenance shall be maintained by the property owner and shall be made available to Town officials by request. These records shall be stored by the property owner for a minimum of three years.
- d) Failure to maintain any stormwater management facility shall be subject to the enforcement and penalties identified in Section J herein.

SECTION I. PERFORMANCE BOND

The Town or its agents may require from the developer a surety or cash bond or other means of security acceptable to the Town prior to the issuance of any building permit for the construction of a development requiring a stormwater management facility. The bond so required in this section shall include provisions relative to forfeiture for failure to complete work specified in the approved stormwater management plan, compliance with all of the provisions of this By-law and other applicable laws and regulations, and any time limitations. The company providing the performance bond to the developer shall submit a bond of the highest grade as rated by Moody's or Standard and Poor's.

A Certificate of Completion signed by the Town, submission of "as-built" plans, and the Town's final inspection is required prior to full release of the bond.

SECTION J. ENFORCEMENT AND PENALTIES

1. Violations

Any development activity that has commenced or is conducted contrary to this By-Law may be restrained by injunction or otherwise abated in a manner provided by law.

2. Notice of Violation

When the Town determines that an activity is not being carried out in accordance with the requirements of this By-Law, it shall issue a written notice of violation to the owner of the property. Failure to maintain proper maintenance and installation records shall constitute a violation of this By-Law.

The notice of violation shall contain:

- a. the name and address of the owner applicant;
- b. the address when available or the description of the building, structure, or land upon which the violation is occurring;
- c. a statement specifying the nature of the violation;
- d. a description of the remedial measures necessary to bring the development activity into compliance with this By-law and a time schedule for the completion of such remedial action; and
- e. a statement of the penalty or penalties that shall or may be assessed against the person to whom the notice of violation is directed.

3. Stop Work Orders

Persons receiving a notice of violations will be required to halt all construction activities. This "stop work order" will be in effect until the Town confirms that the development activity is in compliance and the violation has been satisfactorily addressed. Failure to address a notice of violation in a timely manner can result in civil, criminal, or monetary penalties in accordance with the enforcement measures authorized in this By-Law.

4. Non-Criminal Disposition

As an alternative to criminal prosecution or civil action, the Town may elect to utilize the non-criminal disposition procedure set forth in the non-criminal disposition procedure in Mass. Gen. Laws, Chapter 40, Section 21D or in the Town General By-laws § 103A. The Wilbraham DPW shall be the enforcing entity. The penalty shall be three hundred (\$300.00) dollars per day. Each day or part thereof that such violation occurs or continues shall constitute a separate offense. If action is not taken by the property owner within seven days, this shall become a civil or criminal penalty.

5. Criminal and Civil Penalties

Notwithstanding anything to the contrary in the foregoing sections of this By-Law any person who violates any provision of this By-Law, valid regulation, or the terms or conditions in any permit or order prescribed or issued thereunder, *shall be subject to a fine for each day* such violation occurs or continues or subject to a civil penalty which may be assessed in an action brought on behalf of the Town in any court of competent jurisdiction.

6. Restoration of Lands

Any violator may be required to restore land to its undisturbed condition. In the event that restoration is not undertaken within a reasonable time after notice, the Town will take necessary corrective action, the cost of which shall become a lien upon the property until paid.

7. Severability

If any provision, paragraph, sentence, or clause, of this By-Law shall be held invalid for any reason, all other provisions shall continue in full force and effect.

STORMWATER PHASE II COMPREHENSIVE BY-LAW PART II ILLICIT DISCHARGES TO THE MUNICIPAL STORM DRAIN SYSTEM

SECTION A. PURPOSE AND AUTHORITY

1. Purpose

The purpose of this By-Law is to eliminate non-stormwater discharges to the Town's Municipal Storm Drain System (storm drain). Non-stormwater discharges contain contaminants and supply additional flows to the Town's Storm Drain System. Non-stormwater discharges are major causes of:

- a. impairment of water quality and flow in lakes, ponds, streams, rivers, wetlands, and groundwater;
- b. contamination of drinking water supplies;
- c. alteration or destruction of aquatic and wildlife habitat; and
- d. flooding.

Regulation of illicit connections and discharges to the storm drain system is necessary for the protection of the Town's natural resources, municipal facilities, general health, safety, welfare, and the environment.

The objectives of this section are:

- a. to prevent pollutants from entering the storm drain;
- b. to prohibit illicit connections and unauthorized discharges to the storm drain;
- c. to remove all such illicit connections:
- d. to comply with state and federal statutes and regulations relating to stormwater discharges; and

e. to establish the legal authority to ensure compliance with the provisions of this section through inspection, monitoring, and enforcement.

2. Authority

This By-Law is adopted under the authority granted by the Home Rule Amendment of the Massachusetts Constitution, the Home Rule statutes, and the regulations of the federal Clean Water Act found at 40 CFR 122.34.

3. Responsibility for Administration

The Town Department of Public Works (DPW) shall administer, implement and enforce this By-Law. Any powers granted to or duties imposed upon the DPW to promulgate such rules and regulations shall not have the effect of suspending or invalidating this By-Law.

SECTION B. DEFINITIONS

1. Definitions

Authorized Enforcement Agency – The Town Department of Public Works (DPW), its employees and agents designated to enforce this By-Law.

Best Management Practice (BMP) – An activity, procedure, restraint, or structural improvement that helps reduces the quantity or improve quality of stormwater runoff.

Clean Water Act – The Federal Water Pollution Control Act (33 U.S.C. section 1251 *et seq.*) and as it is amended from time to time.

Discharge of Pollutants - The addition from any source of any pollutant or combination of pollutants into the storm drain or into waters of the United States of America (United States) or the Commonwealth of Massachusetts (Commonwealth) from any source.

Groundwater - Water beneath the surface of the ground, except where the water under the ground is the result of a perched water table.

Illicit Connection - A surface or subsurface drain or conveyance, which allows an illicit discharge into the storm drain, including without limitation sewage, process wastewater, or gray water and any connections from indoor drains, sinks, or toilets, regardless of whether said connection was previously allowed, permitted, or approved before the effective date of this By-Law.

Illicit Discharge - Direct or indirect discharge to the storm drain that is not composed entirely of stormwater, except as exempted in Section 8. The term does not include a discharge in compliance with an NPDES Storm Water Discharge Permit or resulting from firefighting activities.

Impervious Surface - Any material or structure on or above the ground that prevents water infiltrating the underlying soil. Impervious surface includes without limitation roads, paved parking lots, sidewalks, and rooftops.

Municipal Storm Drain System (storm drain) or Municipal Separate Storm Sewer System (MS4) - The system of conveyances designed or used for collecting or conveying stormwater, including any road with a drainage system, street, gutter, curb, inlet, piped storm drain, pumping facility, retention or detention basin, natural or man-made or altered drainage channel, reservoir, and other drainage structure that together comprise the storm drainage system owned or operated by the Town.

National Pollutant Discharge Elimination System (NPDES) Storm Water Discharge Permit - A permit issued by the United States Environmental Protection Agency or jointly with the State of Massaehusetts that authorizes the discharge of pollutants to waters of the United States or Commonwealth.

Non-Stormwater Discharge - Discharge to the storm drain not comprised entirely of stormwater.

Person - An individual, partnership, association, firm, company, trust, corporation, agency, authority, department or political subdivision of the United States or Commonwealth or, to the extent permitted by law, and any officer, employee, or agent of such person.

Pollutant - Any element or property of sewage, residential, agricultural, industrial, or commercial waste, runoff, leachate, heated effluent, or other matter whether originating at a point or non-point source, that is or may be introduced into any storm drain system, waters of the United States, and/or Commonwealth. Pollutants shall include without limitation:

- a. paints, varnishes, solvents:
- b. oil, grease, antifreeze, other automotive fluids and/or products;
- c. non-hazardous liquid and solid wastes;
- d. refuse, garbage, litter, rubbish, yard wastes, or other discarded or abandoned objects, ordnances, accumulations and floatables;
- e. pesticides, herbicides, and fertilizers;
- f. hazardous materials and wastes;
- g. sewage:
- h. dissolved and particulate metals;
- i. metal objects or materials;
- j. animal wastes;
- k. rock, sand, salt, soils, or other products/materials that mobilize in surface water runoff; and
- 1. construction wastes and/or residues.

Process Wastewater - Water which, during manufacturing or processing, comes into direct contact with or results from the production or use of any material, intermediate product, finished product, or waste product.

Recharge - The process by which groundwater is replenished by precipitation through the percolation of runoff and surface water through the soil.

Stormwater - Runoff from precipitation or snowmelt.

Toxic or Hazardous Material or **Waste -** Any material, which because of its quantity, concentration, chemical, corrosive, flammable, reactive, toxic, infectious or radioactive characteristics, either separately or in combination with any substance or substances, constitutes a present or potential threat to human health, safety, welfare or to the environment. Toxic or hazardous material includes without limitation:

- a. any synthetic organic chemical;
- b. petroleum products;
- c. heavy metals;
- d. radioactive or infectious waste;
- e. acid and alkali substances;
- f. any substance defined as Toxic or Hazardous under Mass. Gen. Laws, Chapter 21C and Chapter 21E, and the regulations at 310 CMR 30.000 and 310 CMR 40.000; and
- g. any substance listed as hazardous under 40 CFR 261.

Watercourse - A natural or man-made channel through which water flows or a stream of water, including a river, brook or underground stream.

Waters of the Commonwealth - All waters within the jurisdiction of the Commonwealth, including, without limitation, rivers, streams, lakes, ponds, springs, impoundments, estuaries, wetlands, coastal waters, and groundwater.

Wastewater - Any sanitary waste, sludge, or septic tank or cesspool overflow, and water that during manufacturing, cleaning or processing, comes into direct contact with or results from the production or use of any raw material, intermediate product, finished product, byproduct or waste product.

SECTION C. APPLICABILITY

1. Applicability

This section shall apply to flows entering the municipally owner storm and/or operated storm drain system, a watercourse, or into waters of the United States and/or Commonwealth.

2. Regulations

The DPW may promulgate rules and regulations to effectuate the purpose of this By-Law. Failure by the DPW to promulgate such rules and regulations shall not have the effect of suspending or invalidating this By-Law.

3. Prohibited Activities

Illicit Discharges – No person shall dump, discharge, cause or allow to be discharged any pollutant or non-stormwater discharge into the storm drain system, into a watercourse, or into waters of the United States and/or Commonwealth.

Illicit Connections – No person shall construct, use, allow, maintain or continue any illicit connection to the municipal storm drain system, regardless of whether the connection was permissible under applicable law, regulation or custom at the time of connection.

Obstruction of the Municipal Storm Drain System – No person shall obstruct or interfere with the normal flow of stormwater into or out of the municipal storm drain system without prior approval from the DPW.

SECTION D. EXEMPTIONS

1. Exemptions

Discharge or flow resulting from firefighting activities and DPW ice and snow control operations shall not constitute illicit discharge within the meaning of this By-Law or pertinent federal, state, or local laws.

The following non-stormwater discharges or flows are considered exempt provided that the source is not a significant contributor of pollution to the municipal storm drain system:

- a. waterline flushing;
- b. flow from potable water sources;
- c. springs;
- d. natural flow from riparian habitats and wetlands;
- e. diverted stream flow;
- f. rising groundwater;
- g. uncontaminated groundwater infiltrating as defined in 40 CFR 35.2005(20), or uncontaminated pumped groundwater;
- h. water from exterior foundation drains, footing drains (not including active groundwater dewatering systems), crawl space pumps, or air conditioning condensation;
- i. discharge from landscape irrigation or lawn watering;
- j. water from individual residential car washing;
- k. discharge from dechlorinated swimming pool water (less than one ppm chlorine) provided the water is allowed to stand for one week prior to draining and the pool is drained in such a way as not to cause a nuisance;
- 1. discharge from street sweeping;
- m. discharge or flow resulting DPW ice and snow control operations
- n. dye testing, provided verbal notification is given to the DPW prior to the time of the test:
- o. discharge or flow resulting from firefighting activities

- p. non-stormwater discharge permitted under an NPDES permit, waiver, or waste discharge order administered under the authority of the United States Environmental Protection Agency, provided that the discharge is in full compliance with the requirements of the permit, waiver, or order and applicable laws and regulations; and
- q. discharge for which advanced written approval is received from the DPW as necessary to protect public health, safety, welfare, and the environment.

SECTION F. ENFORCEMENT AND PENALTIES

1. Emergency Suspension of Storm Drainage System Access

The DPW may suspend municipal storm drain system access to any person or property without prior written notice when such suspension is necessary to stop an actual or threatened discharge of pollutants that presents imminent risk of harm to public health, safety, welfare or the environment. In the event any person fails to comply with an emergency suspension order, the Authorized Enforcement Agency may take all reasonable steps to prevent or minimize harm to the public health, safety, welfare, or the environment.

2. Notification of Spills

Any spills or releases that require notification under local, state or federal law will be the responsibility of the person responsible for a facility or operation, or for an emergency response for a facility or operation (e.g., construction). In the event of a spill or release which may result in a discharge of pollutants or non-stormwater discharge to the municipal storm drain system, waters of the United States, and/or waters of the Commonwealth, the responsible parties, potentially responsible parties, or any person or persons managing a site or facility shall take all necessary steps to ensure containment, and remediate any municipal storm drains that have been impacted. However, if in the opinion of DPW, there is an excessive amount of pollutants in the stormdrain system, the DPW can require remediation by the responsible party regardless of other state or federal regulations. If the discharge of prohibited materials is from a commercial or industrial facility, the facility owner or operator of the facility shall take all necessary steps to ensure containment, clean-up of the release, retain on-site a written record of the discharge, and the actions taken to prevent its recurrence. Such records shall be retained for at least three years.

3. Enforcement

Non-Criminal Disposition

A. As an alternative to criminal prosecution or civil action, the Town may elect to utilize the non-criminal disposition procedure set forth in the non-criminal disposition procedure in Mass. Gen. Laws, Chapter 40, Section 21D or in the Town General Bylaws 103A. The Wilbraham DPW shall be the enforcing entity. The penalty will be three hundred dollars (\$300) per day each day or part thereof that such violation occurs or continues shall constitute a separate offense. If action is not taken by the property owner within seven days, this shall become a civil or criminal penalty.

Criminal and Civil Penalties

- B. Notwithstanding anything to the contrary in the foregoing sections of this By-Law any person who violates any provision of this By-Law, valid regulation, or the terms or conditions in any permit or order prescribed or issued thereunder, shall be subject to a fine for each day such violation occurs or continues or subject to a civil penalty which may be assessed in an action brought on behalf of the Town in any court of competent jurisdiction.
- C. The DPW or an authorized agent of the DPW shall enforce this By-Law, regulations, orders, violation notices, and enforcement orders, and may pursue all civil and criminal remedies for such violations.
 - a. **Civil Relief** If a person violates the provisions of this By-Law, regulations, permit, notice, or order issued thereunder, the DPW may seek injunctive relief in a court of competent jurisdiction restraining the person from activities which would create further violations or compelling the person to perform abatement or remediation of the violation.
 - b. **Orders** The DPW or an authorized agent of the DPW may issue a written order to enforce the provisions of this By-Law or the regulations thereunder, which may include:
- D. elimination of illicit connections or discharges to the MS4;
- E. performance of monitoring, analyses, and reporting;
- F. cessation of unlawful discharges, practices, or operations;
- G. remediation of contamination in connection therewith.
- H. If the authorized enforcement agency determines that abatement or remediation of contamination is required and is the responsibility of the property owner, the order shall set forth a deadline by which such abatement or remediation must be completed. Said order shall further advise that, should the violator or property owner fail to abate or perform remediation within the specified deadline, the Town may, at its option, undertake such work, and expenses, trebled, shall be charged to the violator.

- I. Within thirty (30) days after completing all measures necessary to abate the violation or to perform remediation, the violator and the property owner will be notified of the costs incurred by the Town, including administrative costs. The violator or property owner may file a written protest objecting to the amount or basis of costs with the DPW within thirty (30) days of receipt of the notification of the costs incurred. If the amount due is not received by the expiration of the time in which to file a protest or within thirty (30) days following a decision of the DPW affirming or reducing the costs, or from a final decision of a court of competent jurisdiction, the costs shall become a special assessment against the property owner and shall constitute a lien on the owner's property for the amount of said costs. Interest shall begin to accrue on any unpaid costs at the statutory rate provided in Mass. Gen. Laws, Chapter 59, Section 57 after the thirty-first day at which the costs first become due.
 - a. Entry to Perform Duties under this By-Law To the extent permitted by state law, or if authorized by the owner or other party in control of the property, the Wilbraham DPW, its agents, officers, and employees may enter upon privately owned property for the purpose of performing their duties under this By-Law and may make or cause to be made such examinations, surveys or sampling as the DPW deems reasonably necessary.
 - b. **Appeals** The decision or orders of the Wilbraham DPW shall be final. Further relief shall be to a court of competent jurisdiction.
 - c. **Remedies not Exclusive** The remedies listed in this By-Law are not exclusive of any other remedies available under any applicable federal, state or local law.

4. Severability

If any provision, paragraph, sentence, or clause, of this By-Law shall be held invalid for any reason, all other provisions shall continue in full force and effect.

SECTION 635 LITTER (ATM, 5/16/16, Art. 50)

For the purposes of this section, the following definitions shall be applicable:

Garbage – includes, but is not limited to putrescible animal and vegetable wastes resulting from the handling, preparation, cooking, and consumption of food.

Litter – includes, but is not limited to 'garbage', 'refuse' and 'rubbish' as defined herein and all other waste materials which, if thrown or deposited as prohibited in this article, tends to create a danger to public health, safety, and welfare.

Refuse – includes but is not limited to all putrescible and non-putrescible solid wastes (except bodily wastes) including garbage, rubbish, ashes, street cleanings, dead animals, and solid market and industrial wastes.

Town of Wilbraham IDDE Program

Appendix B

2016 Small MS4 General Permit Excerpts

c. The permittee shall report on the activities undertaken to provide public participation opportunities including compliance with part 2.3.3.a. Public participation opportunities pursuant to part 2.3.3.b may include, but are not limited to, websites; hotlines; clean-up teams; monitoring teams; or an advisory committee.

2.3.4. Illicit Discharge Detection and Elimination (IDDE) Program

Objective: The permittee shall implement an IDDE program to systematically find and eliminate sources of non-stormwater discharges to its municipal separate storm sewer system and implement procedures to prevent such discharges.

- a. <u>Legal Authority</u> The IDDE program shall include adequate legal authority to:: prohibit illicit discharges; investigate suspected illicit discharges; eliminate illicit discharges, including discharges from properties not owned by or controlled by the MS4 that discharge into the MS4 system; and implement appropriate enforcement procedures and actions. Adequate legal authority consists of a currently effective ordinance, by-law, or other regulatory mechanism. For permittees authorized by the MS4-2003 permit, the ordinance, by-law, or other regulatory mechanism was a requirement of the MS4-2003 permit and was required to be effective by May 1, 2008. For new permittees the ordinance, by-law, or other regulatory mechanism shall be in place within 3 years of the permit effective date.
- b. During the development of the new components of the IDDE program required by this permit, permittees authorized by the MS4-2003 permit must continue to implement their existing IDDE program required by the MS4-2003 permit to detect and eliminate illicit discharges to their MS4.

2.3.4.1. Definitions and Prohibitions

The permittee shall prohibit illicit discharges and sanitary sewer overflows (SSOs) to its MS4 and require removal of such discharges consistent with parts 2.3.4.2 and 2.3.4.4 of this permit.

An SSO is a discharge of untreated sanitary wastewater from a municipal sanitary sewer.

An illicit discharge is any discharge to a municipal separate storm sewer that is not composed entirely of stormwater, except discharges pursuant to a NPDES permit (other than the NPDES permit for discharges from the municipal separate storm sewer) and discharges resulting from fire fighting activities.

2.3.4.2. Elimination of Illicit Discharges

- a. Upon detection of an illicit discharge, the permittee shall locate, identify and eliminate the illicit discharge as expeditiously as possible. Upon identification of the illicit source the MS4 notify all responsible parties for any such discharge and require immediate cessation of improper disposal practices in accordance with its legal authorities. Where elimination of an illicit discharge within 60 days of its identification as an illicit discharge is not possible, the permittee shall establish an expeditious schedule for its elimination and report the dates of identification and schedules for removal in the permittee's annual reports. The permittee shall immediately commence actions necessary for elimination. The permittee shall diligently pursue elimination of all illicit discharges. In the interim, the permittee shall take all reasonable and prudent measures to minimize the discharge of pollutants to and from its MS4.
 - b. The period between identification and elimination of an illicit discharge is not a grace period. Discharges from an MS4 that are mixed with an illicit discharge are not authorized by this Permit (part 1.3.a) and remain unlawful until eliminated.

2.3.4.3. Non-Stormwater Discharges

The permittee may presume that the sources of non-stormwater listed in part 1.4 of this permit need not be addressed. However, if the permittee identifies any of these sources as significant contributors of pollutants to the MS4, then the permittee shall implement measures to control these sources so they are no longer significant contributors of pollutants, and/or eliminate them entirely, consistent with part 2.3.4.

2.3.4.4. Sanitary Sewer Overflows

- a. Upon detection of an SSO the permittee shall eliminate it as expeditiously as possible and take interim mitigation measures to minimize the discharge of pollutants to and from its MS4 until elimination is completed.
- b. The permittee shall identify all known locations where SSOs have discharged to the MS4 within the previous five (5) years. This shall include SSOs resulting, during dry or wet weather, from inadequate conveyance capacities, or where interconnectivity of the storm and sanitary sewer infrastructure allows for communication of flow between the systems. Within one (1) year of the effective date of the permit, the permittee shall develop an inventory of all identified SSOs indicating the following information, if available:
 - 1. Location (approximate street crossing/address and receiving water, if any);
 - 2. A clear statement of whether the discharge entered a surface water directly or entered the MS4;
 - 3. Date(s) and time(s) of each known SSO occurrence (i.e., beginning and end of any known discharge);
 - 4. Estimated volume(s) of the occurrence;
 - 5. Description of the occurrence indicating known or suspected cause(s);
 - 6. Mitigation and corrective measures completed with dates implemented; and
 - 7. Mitigation and corrective measures planned with implementation schedules.

The permittee shall maintain the inventory as a part of the SWMP and update the inventory annually, all updates shall include the information in part 2.3.4.4.b.1-7.

- c. In accordance with Paragraph B.12 of Appendix B of this permit, upon becoming aware of an SSO to the MS4, the permittee shall provide oral notice to EPA within 24 hours. Additionally, the permittee shall provide written notice to EPA and MassDEP within five (5) days of becoming aware of the SSO occurrence and shall include the information in the updated inventory. The notice shall contain all of the information listed in part 2.3.4.4.b. Where common notification requirements for SSOs are included in multiple NPDES permits issued to a permittee, a single notification may be made to EPA as directed in the permittee's wastewater or CSO NPDES permit and constitutes compliance with this part.
- d. The permittee shall include and update the SSO inventory in its annual report, including the status of mitigation and corrective measures implemented by the permittee to address each SSO identified pursuant to this part.
- e. The period between detection and elimination of a discharge from the SSO to the MS4 is not a grace period. Discharges from an MS4 that are mixed with an SSO are not authorized by this Permit (part 1.3.a) and remain unlawful until eliminated.

2.3.4.5. System mapping

The permittee shall develop a revised and more detailed map than was required by the MS4-2003 permit. This revised map of the MS4 shall be completed in two phases as outlined below. The mapping shall include a depiction of the permittee's separate storm sewer system in the permit area. The mapping is intended to facilitate the identification of key infrastructure and factors influencing proper system operation, and the potential for illicit sanitary sewer discharges.

- a. Phase I: The system map shall be updated within two (2) years of the permit effective date to include the following information:
 - Outfalls and receiving waters (required by MS4-2003 permit)
 - Open channel conveyances (swales, ditches, etc.)
 - Interconnections with other MS4s and other storm sewer systems
 - Municipally-owned stormwater treatment structures (e.g., detention and retention basins, infiltration systems, bioretention areas, water quality swales, gross particle separators, oil/water separators, or other proprietary systems)
 - Waterbodies identified by name and indication of all use impairments as identified on the most recent EPA approved Massachusetts Integrated List of waters report pursuant to Clean Water Act section 303(d) and 305(b)
 - Initial catchment delineations. Any available system data and topographic information may be used to produce initial catchment delineations. For the purpose of this permit, a catchment is the area that drains to an individual outfall or interconnection.
- b. Phase II: The system map shall be updated annually as the following information becomes available during implementation of catchment investigation procedures in part 2.3.4.8. This information must be included in the map for all outfalls within ten (10) years of the permit effective date:
 - Outfall spatial location (latitude and longitude with a minimum accuracy of +/-30 feet)
 - Pipes
 - Manholes
 - Catch basins
 - Refined catchment delineations. Catchment delineations shall be updated to reflect information collected during catchment investigations
 - Municipal sanitary sewer system (if available)
 - Municipal combined sewer system (if applicable).
- c. Recommended elements to be included in the system map as information becomes available:
 - Storm sewer material, size (pipe diameter) and age
 - Sanitary sewer system material, size (pipe diameter) and age
 - Privately-owned stormwater treatment structures
 - Where a municipal sanitary sewer system exists, properties known or suspected to be served by a septic system, especially in high-density urban areas
 - Area where the permittee's MS4 has received or could receive flow from septic system
 discharges (e.g., areas with poor soils, or high ground water elevations unsuitable for
 conventional subsurface disposal systems)
 - Seasonal high water table elevations impacting sanitary alignments
 - Topography
 - Orthophotography

- Alignments, dates and representation of work completed (with legend) of past illicit discharge investigations (e.g., flow isolation, dye testing, CCTV)
- Locations of suspected, confirmed and corrected illicit discharges (with dates and flow estimates).
- d. The mapping may be produced by hand or through computer-aided methods (e.g. GIS). The required scale and detail of the map shall be appropriate to facilitate a rapid understanding of the system by the permittee, EPA and the state. In addition, the mapping shall serve as a planning tool for the implementation and phasing of the IDDE program and demonstration of the extent of complete and planned investigations and corrections. The permittee shall update the mapping as necessary to reflect newly discovered information and required corrections or modifications.
- e. The permittee shall report on the progress towards the completion of the system map in each annual report.

2.3.4.6. Written Illicit Discharge Detection and Elimination Program

The IDDE program shall be recorded in a written (hardcopy or electronic) document. The IDDE program shall include each of the elements described in parts 2.3.4.7 and part 2.3.4.8, unless the permittee provides a written explanation within the IDDE program as to why a particular element is not applicable to the permittee.

Notwithstanding the permittee's explanation, EPA may at any time determine that a particular element is in fact applicable to the permittee and require the permittee to add it to the IDDE program. The written (hardcopy or electronic) IDDE program shall be completed within one (1) year of the effective date of the permit and updated in accordance with the milestones of this part. The permittee shall implement the IDDE program in accordance with the goals and milestones contained in this part.

- a. The written (hardcopy or electronic) IDDE program shall include a reference or citation of the authority the permittee will use to implement all aspects of the IDDE program.
- b. <u>Statement of IDDE Program Responsibilities</u> The permittee shall establish a written (hardcopy or electronic) statement that clearly identifies responsibilities with regard to eliminating illicit discharges. The statement shall identify the lead municipal agency(ies) or department(s) responsible for implementing the IDDE Program as well as any other agencies or departments that may have responsibilities for aspects of the program (e.g., board of health responsibilities for overseeing septic system construction; sanitary sewer system staff; inspectional services for enforcing plumbing codes; town counsel responsibilities in enforcement actions, etc.). Where multiple departments and agencies have responsibilities with respect to the IDDE program specific areas of responsibility shall be defined and processes for coordination and data sharing shall be established and documented.
- c. <u>Program Procedures</u> The permittee shall include in the written IDDE program all written procedures developed in accordance with the requirements and timelines in parts 2.3.4.7 and 2.3.4.8 below. At a minimum this shall include the written procedures for dry weather outfall screening and sampling and for catchment investigations.

2.3.4.7. Assessment and Priority Ranking of Outfalls/Interconnections

The permittee shall assess and priority rank the outfalls in terms of their potential to have illicit discharges and SSOs and the related public health significance. This ranking will determine the priority order for

screening of outfalls and interconnections pursuant to part 2.3.4.7.b, catchment investigations for evidence of illicit discharges and SSOs pursuant to part 2.3.4.8, and provides the basis for determining permit milestones of this part.

a. Outfall/Interconnection Inventory and Initial Ranking:

An initial outfall and interconnection inventory and priority ranking to assess illicit discharge potential based on existing information shall be completed within one (1) year from the effective date of the permit; an updated inventory and ranking will be provided in each annual report thereafter. The inventory shall be updated annually to include data collected in connection with the dry weather screening and other relevant inspections conducted by the permittee.

- i. The outfall and interconnection inventory will identify each outfall and interconnection discharging from the MS4, record its location and condition, and provide a framework for tracking inspections, screenings and other activities under the permittee's IDDE program.
 - An outfall means a point source as defined by 40 CFR § 122.2 as the point where the municipal separate storm sewer discharges to waters of the United States. An outfall does not include open conveyances connecting two municipal separate storm sewers or pipes, tunnels or other conveyances that connect segments of the same stream or other waters of the United States and that are used to convey waters of the United States. (40 CFR § 122.26(b)(9)). However, it is strongly recommended that a permittee inspect all accessible portions of the system as part of this process. Culverts longer than a simple road crossing shall be included in the inventory unless the permittee can confirm that they are free of any connections and simply convey waters of the United States.
 - An interconnection means the point (excluding sheet flow over impervious surfaces) where the
 permittee's MS4 discharges to another MS4 or other storm sewer system, through which the
 discharge is conveyed to waters of the United States or to another storm sewer system and
 eventually to a water of the United States.
- ii. The permittee shall classify each of the permittee's outfalls and interconnections into one of the following categories:
 - <u>Problem Outfalls:</u> outfalls/interconnections with known or suspected contributions of illicit discharges based on existing information shall be designated as Problem Outfalls. This shall include any outfalls/interconnections where previous screening indicates likely sewer input.⁴ Problem Outfalls need not be screened pursuant to part 2.3.4.7.b.
 - <u>High Priority Outfalls:</u> Outfalls/interconnections that have not been classified as Problem Outfalls and that are:
 - o discharging to an area of concern to public health due to proximity of public beaches, recreational areas, drinking water supplies or shellfish beds;
 - o determined by the permittee as high priority based on the characteristics listed below or other available information;
 - <u>Low Priority Outfalls</u>: Outfalls/interconnections determined by the permittee as low priority based on the characteristics listed below or other available information.

⁴ Likely sewer input indicators are any of the following:

[•] Olfactory or visual evidence of sewage,

Ammonia ≥ 0.5 mg/L, surfactants ≥ 0.25 mg/L, and bacteria levels greater than the water quality criteria applicable to the receiving water, or

[•] Ammoni $a \ge 0.5$ mg/L, surfactants ≥ 0.25 mg/L, and detectable levels of chlorine.

- Excluded outfalls: outfalls/interconnections with no potential for illicit discharges may be
 excluded from the IDDE program. This category is limited to roadway drainage in
 undeveloped areas with no dwellings and no sanitary sewers; drainage for athletic fields, parks
 or undeveloped green space and associated parking without services; cross-country drainage
 alignments (that neither cross nor are in proximity to sanitary sewer alignments) through
 undeveloped land.
- iii. The permittee shall priority rank outfalls into the categories above (except for excluded outfalls), based on the following characteristics of the defined initial catchment area where information is available:
 - Past discharge complaints and reports.
 - Poor receiving water quality- the following guidelines are recommended to identify waters as having a high illicit discharge potential: exceeding water quality standards for bacteria; ammonia levels above 0.5 mg/l; surfactants levels greater than or equal to 0.25 mg/l.
 - Density of generating sites- Generating sites are those places, including institutional, municipal, commercial, or industrial sites, with a potential to generate pollutants that could contribute to illicit discharges. Examples of these sites include, but are not limited to, car dealers; car washes; gas stations; garden centers; and industrial manufacturing areas.
 - Age of development and infrastructure Industrial areas greater than 40 years old and areas where the sanitary sewer system is more than 40 years old will probably have a high illicit discharge potential. Developments 20 years or younger will probably have a low illicit discharge potential.
 - Sewer conversion contributing catchment areas that were once serviced by septic systems, but have been converted to sewer connections may have a high illicit discharge potential.
 - Historic combined sewer systems contributing areas that were once serviced by a combined sewer system, but have been separated may have a high illicit discharge potential.
 - Surrounding density of aging septic systems Septic systems thirty years or older in residential land use areas are prone to have failures and may have a high illicit discharge potential.
 - Culverted streams any river or stream that is culverted for distances greater than a simple roadway crossing may have a high illicit discharge potential.
 - Water quality limited waterbodies that receive a discharge from the MS4 or waters with approved TMDLs applicable to the permittee, where illicit discharges have the potential to contain the pollutant identified as the cause of the water quality impairment.
 - The permittee may also consider additional relevant characteristics, including location-specific characteristics; if so, the permittee shall include the additional characteristics in its written (hardcopy or electronic) IDDE program.

b. Dry Weather Outfall and Interconnection Screening and Sampling

All outfalls/interconnections (excluding Problem and excluded Outfalls) shall be inspected for the presence of dry weather flow within three (3) years of the permit effective date. The permittee shall screen all High and Low Priority Outfalls in accordance with their initial ranking developed at part 2.3.4.7.a.

- i. <u>Written procedure</u>: The permittee shall develop an outfall and interconnection screening and sampling procedure to be included in the IDDE program within one (1) year of the permit effective date. This procedure shall include the following procedures for:
 - sample collection,
 - use of field kits,

- storage and conveyance of samples (including relevant hold times), and
- field data collection and storage.

An example screening and sampling protocol (*EPA New England Bacterial Source Tracking Protocol*) can be found on EPA's website.

- ii. <u>Weather conditions:</u> Dry weather screening and sampling shall proceed only when no more than 0.1 inches of rainfall has occurred in the previous 24-hour period and no significant snow melt is occurring.
- iii. <u>Screening requirements</u>: For each outfall/interconnection:
 - 1. The permittee shall record all of the following information and include it in the outfall/interconnection inventory and priority ranking:
 - unique identifier,
 - receiving water,
 - date of most recent inspection,
 - dimensions,
 - shape,
 - material (concrete, PVC),
 - spatial location (latitude and longitude with a minimum accuracy of +/-30 feet,
 - physical condition,
 - indicators of potential non-stormwater discharges (including presence or evidence of suspect flow and sensory observations such as odor, color, turbidity, floatables, or oil sheen).
 - 2. If an outfall/interconnection is inaccessible or submerged, the permittee shall proceed to the first accessible upstream manhole or structure for the observation and sampling and report the location with the screening results.
 - 3. If no flow is observed, but evidence of illicit flow exists, the permittee shall revisit the outfall during dry weather within one week of the initial observation, if practicable, to perform a second dry weather screening and sample any observed flow (proceed as in iv. below).
 - 4. Where dry weather flow is found at an outfall/interconnection, at least one (1) sample shall be collected, and:
 - a) Samples shall be analyzed at a minimum for:
 - ammonia,
 - chlorine.
 - conductivity,
 - salinity,
 - *E. coli* (freshwater receiving water) or enterococcus (saline or brackish receiving water),
 - surfactants (such as MBAS),
 - temperature, and
 - pollutants of concern⁵
 - b) All analyses with the exception of indicator bacteria and pollutants of concern can be performed with field test kits or field instrumentation and are not subject to 40

⁵ Where the discharge is directly into a water quality limited water or a water subject to an approved TMDL as indicated in Appendix F; the sample shall be analyzed for the pollutant(s) of concern identified as the cause of the impairment as specified in Appendix G

CFR part 136 requirements. Sampling for bacteria and pollutants of concern shall be conducted using the analytical methods found in 40 CFR §136, or alternative methods approved by EPA in accordance with the procedures in 40 CFR §136. Sampling for ammonia and surfactants must use sufficiently sensitive methods to detect those parameters at or below the threshold indicator concentrations of 0.5 mg/L for ammonia and 0.25 mg/L for surfactants. Sampling for residual chlorine must use a method with a detection limit of 0.02 mg/L or 20 ug/L.

- iv. The permittee may rely on screening conducted under the MS4-2003 permit, pursuant to an EPA enforcement action, or by the state or EPA to the extent that it meets the requirements of part 2.3.4.7.b.iii.4. All data shall be reported in each annual report. Permittees that have conducted substantially equivalent monitoring to that required by part 2.3.4.7.b as part of an EPA enforcement action can request an exemption from the requirements of part 2.3.4.7.b by submitting a written request to EPA and retaining exemption approval from EPA as part of the SWMP. Until the permittee receives formal written approval of the exemption from part 2.3.4.7.b from EPA the permittee remains subject to all requirements of part 2.3.4.7.b.
- v. The permittee shall submit all screening data used in compliance with this part in its Annual Report.

c. Follow-up ranking of outfalls and interconnections:

- i. The permittee's outfall and interconnection ranking (2.3.4.7.a) shall be updated to reprioritize outfalls and interconnections based on information gathered during dry weather screening (part 2.3.4.7.b).
- ii. Outfalls/interconnections where relevant information was found indicating sewer input to the MS4 or sampling results indicating sewer input⁶ shall be considered highly likely to contain illicit discharges from sanitary sources, and such outfalls/interconnections shall be ranked at the top of the High Priority Outfalls category for investigation. At this time, permittees may choose to rank other outfalls and interconnections based on any new information from the dry weather screening.
- iii. The ranking can be updated continuously as dry weather screening information becomes available, but shall be completed within three (3) years of the effective date of the permit.

2.3.4.8. Catchment Investigations

The permittee shall develop a systematic procedure to investigate each catchment associated with an outfall or interconnection within their MS4 system.

a. Timelines:

- A written catchment investigation procedure shall be developed within 18 months of the permit effective date in accordance with the requirements of part 2.3.4.8.b below.
- Investigations of catchments associated with Problem Outfalls shall begin no later than two (2)

- Olfactory or visual evidence of sewage,
- Ammonia ≥ 0.5 mg/L, surfactants ≥ 0.25 mg/L, and bacteria levels greater than the water quality criteria applicable to the receiving water, or
- Ammonia \geq 0.5 mg/L, surfactants \geq 0.25 mg/L, and detectable levels of chlorine.

⁶ Likely sewer input indicators are any of the following:

- years from the permit effective date.
- Investigations of catchments associated with High and Low Priority Outfalls shall follow the ranking of outfalls updated in part 2.3.4.7.c.
- Investigations of catchments associated with Problem Outfalls shall be completed with seven (7) years of the permit effective date
- Investigations of catchments where any information gathered on the outfall/interconnection identifies sewer input⁷ shall be completed within seven (7) years of the permit effective date.
- Investigations of catchments associated with all Problem, High- and Low-Priority Outfalls shall be completed within ten (10) years of the permit effective date.

*For the purposes of these milestones, an individual catchment investigation will be considered complete if all relevant procedures in part 2.3.4.8.c. and 2.3.4.8.d. below have been completed.

b. A written catchment investigation procedure shall be developed that:

- i. Identifies maps, historic plans and records, and other sources of data, including but not limited to plans related to the construction of the storm drain and of sanitary sewers, prior work performed on the storm drains or sanitary sewers, board of health or other municipal data on septic system failures or required upgrades, and complaint records related to SSOs, sanitary sewer surcharges, and septic system breakouts. These data sources will be used in identifying system vulnerability factors within each catchment.
- ii. **Includes a manhole inspection methodology** that shall describe a storm drain network investigation that involves systematically and progressively observing, sampling (as required below) and evaluating key junction manholes (see definition in Appendix A) in the MS4 to determine the approximate location of suspected illicit discharges or SSOs. The manhole inspection methodology may either start from the outfall and work up the system or start from the upper parts of the catchment and work down the system or be a combination of both practices. Either method must, at a minimum, include an investigation of each key junction manhole within the MS4, even where no evidence of an illicit discharge is observed at the outfall. The manhole inspection methodology must describe the method the permittee will use. The manhole inspection methodology shall include procedures for dry and wet weather investigations.
- iii. **Establishes procedures to isolate and confirm sources of illicit discharges** where manhole investigations or other physical evidence or screening has identified that MS4 alignments are influenced by illicit discharges or SSOs. These shall include isolation of the drainage area for implementation of more detailed investigations, inspection of additional manholes along the alignment to refine the location of potential contaminant sources, and methods such as sandbagging key junction manhole inlets, targeted internal plumbing inspections, dye testing, video inspections, or smoke testing to isolate and confirm the sources.
- c. Requirements for each catchment investigation associated with an outfall/interconnection:
 - i. For each catchment being investigated, the permittee shall review relevant mapping and historic plans and records gathered in accordance with Part 2.3.4.8.b.i. This review shall be used to identify

⁷ Likely sewer input indicators are any of the following:

[•] Olfactory or visual evidence of sewage,

Ammonia ≥ 0.5 mg/L, surfactants ≥ 0.25 mg/L, and bacteria levels greater than the water quality criteria applicable to the receiving water, or

[•] Ammonia \geq 0.5 mg/L, surfactants \geq 0.25 mg/L, and detectable levels of chlorine.

areas within the catchment with higher potential for illicit connections. The permittee shall identify and record the presence of any of the following specific **System Vulnerability Factors (SVFs)**:

- History of SSOs, including, but not limited to, those resulting from wet weather, high water table, or fat/oil/grease blockages;
- Common or twin-invert manholes serving storm and sanitary sewer alignments;
- Common trench construction serving both storm and sanitary sewer alignments;
- Crossings of storm and sanitary sewer alignments where the sanitary system is shallower than the storm drain system;
- Sanitary sewer alignments known or suspected to have been constructed with an underdrain system;
- Inadequate sanitary sewer level of service (LOS) resulting in regular surcharging, customer back-ups, or frequent customer complaints;
- Areas formerly served by combined sewer systems;
- Sanitary sewer infrastructure defects such as leaking service laterals, cracked, broken, or offset sanitary infrastructure, directly piped connections between storm drain and sanitary sewer infrastructure, or other vulnerability factors identified through Inflow/Infiltration Analyses, Sanitary Sewer Evaluation Surveys, or other infrastructure investigations.

EPA recommends the permittee include the following in their consideration of System Vulnerability Factors:

- Sewer pump/lift stations, siphons, or known sanitary sewer restrictions where power/equipment failures or blockages could readily result in SSOs;
- Any sanitary sewer and storm drain infrastructure greater than 40 years old;
- Widespread code-required septic system upgrades required at property transfers (indicative of inadequate soils, water table separation, or other physical constraints of the area rather that poor owner maintenance);
- History of multiple Board of Health actions addressing widespread septic system failures (indicative of inadequate soils, water table separation, or other physical constraints of the area rather that poor owner maintenance);

The permittee shall document the presence or absence of System Vulnerability Factors for each catchment, retain this documentation as part of its IDDE program, and report this information in Annual Reports. Catchments with a minimum of one (1) System Vulnerability Factor are subject to wet weather sampling requirements of part 2.3.4.8.c.ii.2.

ii. For each catchment, the permittee must inspect key junction manholes and gather catchment information on the locations of MS4 pipes, manholes, and the extent of the contributing catchment.

1. For all catchments

- a) Infrastructure information shall be incorporated into the permittee's mapping required at part 2.3.4.5; the permittee will refine their catchment delineation based on the field investigation where appropriate.
- b) The SVF inventory for the catchment will be updated based on information obtained during the inspection, including common (twin invert) manholes, directly piped connections between storm drains and sanitary sewer infrastructure, common weir walls, sanitary sewer underdrain connections and other structural vulnerabilities where sanitary discharges could enter the storm drain system during wet weather.
 - 1) Where a minimum of one (1) SVF is identified based on previous information

or the investigation, a wet weather investigation must be conducted at the associated outfall (see below).

- c) During dry weather, key junction manholes⁸ shall be opened and inspected systematically for visual and olfactory evidence of illicit connections (e.g., excrement, toilet paper, gray filamentous bacterial growth, or sanitary products present).
 - 1) If flow is observed, the permittee shall sample the flow at a minimum for ammonia, chlorine and surfactants and can use field kits for these analyses.
 - 2) Where sampling results or visual or olfactory evidence indicate potential illicit discharges or SSOs, the area draining to the junction manhole shall be flagged for further upstream investigation.
- d) Key junction and subsequent manhole investigations will proceed until the location of suspected illicit discharges or SSOs can be isolated to a pipe segment between two manholes. If no evidence of an illicit discharge is found, catchment investigations will be considered complete upon completion of key junction manhole sampling.

2. For all catchments with a minimum of one (1) SVF identified

- a) The permittee shall meet the requirements above for dry weather screening
- b) The permittee shall inspect and sample under wet weather conditions to the extent necessary to determine whether wet weather-induced high flows in sanitary sewers or high groundwater in areas served by septic systems result in discharges of sanitary flow to the MS4.
 - 1) The permittee shall conduct at least one wet weather screening and sampling at the outfall that includes the same parameters required during dry weather screening, part 2.3.4.7.b.iii.4.
 - 2) Wet weather sampling and screening shall proceed during or after a storm event of sufficient depth or intensity to produce a stormwater discharge. EPA strongly recommends sampling during the spring (March through June) when groundwater levels are relatively high.
 - 3) The permit does not require a minimum rainfall event prior to wet weather screening. However, permittees may incorporate provisions that assist in targeting such discharges, including avoiding sampling during the initial period of discharge ("first flush") and/or identifying minimum storm event intensities likely to trigger sanitary sewer interconnections.
- c) This sampling can be done upon completion of any dry weather investigation but must be completed before the catchment investigation is marked as complete.
- iii. All data collected as part of the dry and wet weather catchment investigations shall be recorded and reported in each annual report.

d. Identification/Confirmation of illicit source

Where the source of an illicit discharge has been approximated between two manholes in the permittee's MS4, the permittee shall isolate and identify/confirm the source of the illicit discharge using more detailed methods identified in their written procedure (2.3.4.8.b.iii). For outfalls that contained evidence of an illicit discharge, catchment investigations will be considered complete upon

⁸ Where catchments do not contain junction manholes, the dry weather screening and sampling shall be considered as meeting the manhole inspection requirement. In these catchments, dry weather screenings that indicate potential presence of illicit discharges shall be further investigated pursuant to part 2.3.4.8.d. Investigations in these catchments may be considered complete where dry weather screening reveals no flow; no evidence of illicit discharges or SSOs is indicated through sampling results or visual or olfactory means; and no wet weather System Vulnerability Factors are identified.

confirmation of all illicit sources.

e. Illicit discharge removal

When the specific source of an illicit discharge is identified, the permittee shall exercise its authority as necessary to require its removal pursuant to part 2.3.4.2 or 2.3.4.3.

- i. For each confirmed source the permittee shall include in the annual report the following information:
 - the location of the discharge and its source(s);
 - a description of the discharge;
 - the method of discovery;
 - date of discovery;
 - date of elimination, mitigation or enforcement action OR planned corrective measures and a schedule for completing the illicit discharge removal; and
 - estimate of the volume of flow removed.
- ii. Within one year of removal of all identified illicit discharges within a catchment area, confirmatory outfall or interconnection screening shall be conducted. The confirmatory screening shall be conducted in dry weather unless System Vulnerability Factors have been identified, in which case both dry weather and wet weather confirmatory screening shall be conducted. If confirmatory screening indicates evidence of additional illicit discharges, the catchment shall be scheduled for additional investigation.

2.3.4.9. Indicators of IDDE Program Progress

The permittee shall define or describe indicators for tracking program success and evaluate and report on the overall effectiveness of the IDDE program in each annual report. At a minimum the permittee shall document in each annual report:

- the number of SSOs and illicit discharges identified and removed,
- the number and percent of total outfall catchments served by the MS4 evaluated using the catchment investigation procedure,
- all dry weather and wet weather screening and sampling results and
- the volume of sewage removed

2.3.4.10 Ongoing Screening

Upon completion of all catchment investigations pursuant to part 2.3.4.8.c and illicit discharge removal and confirmation (if necessary) pursuant to paragraph 2.3.4.8.e, each outfall or interconnection shall be reprioritized for screening in accordance with part 2.3.4.8.a and scheduled for ongoing screening once every five years. Ongoing screening shall consist of dry weather screening and sampling consistent with part 2.3.4.7.b; wet weather screening and sampling shall also be required at outfalls where wet weather screening was required due to SVFs and shall be conducted in accordance with part 2.3.4.8.c.ii. All sampling results shall be reported in the permittee's annual report.

2.3.4.11 Training

The permittee shall, at a minimum, annually provide training to employees involved in IDDE program about the program, including how to recognize illicit discharges and SSOs. The permittee shall report on the frequency and type of employee training in the annual report.

MA MS4 General Permit Appendix G

Appendix G Massachusetts Small MS4 Permit Monitoring Requirements For Discharges into Impaired Waters – Parameters and Methods

| Pollutant Causing Impairment | Monitoring Parameter | EPA or Approved Method No. |
|--|--|-------------------------------------|
| Aluminum | Aluminum, Total | 200.7; 200.8; 200.9 |
| Ammonia (Un-ionized) | Ammonia – Nitrogen | 350.1 |
| Arsenic | Arsenic, Total | 200.7; 200.8; 200.9 |
| Cadmium | Cadmium, Total | 200.7; 200.8; 200.9 |
| Chlordane | NMR | 608; 625 |
| Chloride | Chloride | 300 |
| Chromium (total) | Chromium, Total | 200.7; 200.8; 200.9 |
| Copper | Copper, Total | 200.7; 200.8; 200.9 |
| DDT | NMR | 608; 625 |
| DEHP (Di-sec-octyl phthalate) | NMR | |
| Dioxin (including 2,3,7,8-TCDD) | NMR | 613; 1613 |
| Dioxin (2,3,7,8-Tetrachlorodibenzo-p-dioxin only) | NMR | 613 |
| Lead | Lead, Total | 200.7; 200.8; 200.9 |
| Mercury in Water Column | NMR unless potentially present such (e.g., salvage yards crushing vehicles with Hg switches) | 200.7; 200.8; 200.9 |
| Nitrogen (Total) | Nitrogen, Total | 351.1/351.2 + 353.2 |
| Pentachlorophenol (PCP) | NMR | |
| Petroleum Hydrocarbons | Oil and Grease | 1664 |
| Phosphorus (Total) | Phosphorus, Total | 365.1; 365.2; 365.3; SM 4500-P-E |
| Polychlorinated biphenyls | NMR | |
| Polycyclic Aromatic Hydrocarbons (PAHs) (Aquatic Ecosystems) | PAHs | 610; 1625 |
| Sulfide-Hydrogen Sulfide | NMR | |
| Mercury in Fish Tissue | NMR | |
| PCB in Fish Tissue | NMR | |
| Total Dissolved Solids | Total Dissolved Solids | 160.1 |
| Total Suspended Solids (TSS) | Total Suspended Solids | 160.2, 180.1 |
| Turbidity | Total Suspended Solids and Turbidity | 160.2, 180.1 |
| Secchi disk transparency | Total Suspended Solids | 160.2 |
| Sediment Screening Value (Exceedence) | Total Suspended Solids | 160.2 |

MA MS4 General Permit Appendix G

| Sedimentation/Siltation | Total Suspended Solids | 160.2 |
|---|--|---|
| Bottom Deposits | Total Suspended Solids | 160.2 |
| Color | NMR | |
| pH, High | pН | 150.2 |
| pH, Low | pН | 150.2 |
| Taste and Odor | NMR | |
| Temperature, water | NMR | |
| Salinity | Specific Conductance | 120.1 |
| Enterococcus | Enterococcus | 1106.1; 1600; Enterolert® 12 22. |
| Escherichia coli | E. coli | 1103.1; 1603; Colilert® 12 16, Colilert-18® 12 15 16.; mColiBlue- 24®17. |
| Fecal Coliform | Fecal Coliform | 1680; 1681 |
| Organic Enrichment (Sewage) Biological Indicators | Enterococcus (marine waters) or E. coli (freshwater) | 1106.1; 1600 |
| Debris/Floatables/Trash | NMR | or |
| Foam/Flocs/Scum/Oil Slicks | Contact MassDEP | 1103.1; 1603 |
| Oil and Grease | Oil and Grease | |
| Chlorophyll-a | Total Phosphorus (freshwater) | |
| Сшогориун-а | Total Nitrogen (marine waters) | 1664 |
| Nutrient/Eutrophication Biological Indicators | Total Phosphorus (freshwater) | 365.1; 365.2; 365.3 |
| Nutren/Eutrophication Biological Indicators | Total Nitrogen (marine waters) | 351.1/351.2 + 353.2 |
| | Dissolved Oxygen | 365.1; 365.2; 365.3 |
| | Temperature | 351.1/351.2 + 353.2 |
| Dissolved oxygen saturation / Oxygen, Dissolved | BOD ₅ | 360.1; 360.2 |
| Dissolved oxygen saturation / Oxygen, Dissolved | Total Phosphorus (freshwater) | SM-2550 |
| | Total Nitrogen (marine waters) | SM-5210 |
| Excess Algal Growth | Total Phosphorus (freshwater) | 365.1; 365.2; 365.3 |
| Lacess Aigai Giowiii | Total Nitrogen (marine waters) | 351.1/351.2 + 353.2 |
| Aquatic Plants (Macrophytes) | NMR | |

MA MS4 General Permit Appendix G


| Abnormal Fish deformities, erosions, lesions, tumors (DELTS) | NMR | |
|--|-----------------|--|
| Abnormal Fish Histology (Lesions) | NMR | |
| Estuarine Bioassessments | Contact MassDEP | |
| Fishes Bioassessments | Contact MassDEP | |
| Aquatic Macroinvertebrate Bioassessments | Contact MassDEP | |
| Combined Biota/Habitat Bioassessments | Contact MassDEP | |
| Habitat Assessment (Streams) | Contact MassDEP | |
| Lack of a coldwater assemblage | Contact MassDEP | |
| Fish Kills | Contact MassDEP | |
| Whole Effluent Toxicity (WET) | Contact MassDEP | |
| Ambient Bioassays Chronic Aquatic Toxicity | Contact MassDEP | |
| Sediment Bioassays Acute Toxicity Freshwater | Contact MassDEP | |
| Sediment Bioassays Chronic Toxicity Freshwater | Contact MassDEP | |
| Fish-Passage Barrier | NMR | |
| Alteration in stream-side or littoral vegetative covers | NMR | |
| Low flow alterations | NMR | |
| Other flow regime alterations | NMR | |
| Physical substrate habitat alterations | NMR | |
| Other anthropogenic substrate alterations | NMR | |
| Non-Native Aquatic Plants | NMR | |
| Eurasian Water Milfoil, Myriophyllum spicatum | NMR | |
| Zebra mussel, Dreissena polymorph | NMR | |
| Other | Contact MassDEP | |

Notes:

NMR" indicates no monitoring required

"Total Phosphorus (freshwater)" indicates monitoring required for total phosphorus where stormwater discharges to a water body that is freshwater

"Total Nitrogen (marine water)" indicates monitoring required for total nitrogen where stormwater discharges to a water body that is a marine or estuarine water



Town of Wilbraham IDDE Program Appendix C MassDEP SSO Reporting Instructions and Form



Massachusetts Department of Environmental Protection

Bureau of Water Resources

Wastewater Management Program

Sanitary Sewer Overflow(SSO)/Bypass Notification Form

Who must notify DEP about an overflow or bypass, and when?

Any owner or operator of the following facilities:

- Municipal, state, federal, regional, industrial or other private wastewater collection system;
- Wastewater utility;
- Wastewater treatment works;
- Facility with a groundwater discharge permit;
- Facility with a surface water discharge permit.

This requirement includes any owner or operator of a satellite municipal collection system or other collection system that is part of a larger POTW not under the same ownership and control.

The following situations require notification to DEP and submittal of the SSO Report Form:

- An un-permitted overflow or bypass;
- Backup of wastewater into public or private property when the event is caused by a condition of the system owned and operated by the sewer authority
- In a combined sewer system, an overflow or bypass during dry weather conditions or at a location not covered by a NPDES permit, or from a portion of the system that has a separate sanitary sewer.

Backups of wastewater into a property which are not caused by conditions in the system owned and operated by the sewer system are not required to be reported. These incidents normally occur due to blockages in service connections to a property or blockages in the internal plumbing system.

What are the procedures for reporting?

Step One:

Immediate Telephone and/or email notification to MassDEP, EPA, and other parties:

Notification to MassDEP and other regulatory authorities is a critical element of the SSO response plan. Notification must be made as soon as possible, and no later than 24 hours after discovery of the event. The agency notifications should include all responsible officials whose duties include management of resources which may be affected by the SSO discharge. A list of agencies, contact staff, phone numbers, and emails should be kept by the Sewer Authority and posted for easy access to responsible staff. A list of some relevant agencies follows:

| Agency: | Contact | Requirements |
|---------|------------------------|-----------------|
| MassDEP | During business hours: | Report all SSO |
| | | events to |
| | Northeast Region: | relevant |
| | (978) 694-3215 | regional office |
| | | Report SSO's to |
| | Central Region: | emergency line |
| | (508) 792-7650 | during non- |
| | | business hours |
| | Southeast Region: | |
| | (508) 946-2750 | |



Massachusetts Department of Environmental Protection Bureau of Water Resources – Wastewater Management Program

Sanitary Sewer Overflow(SSO)/Bypass Notification Form Instructions

| | | 1 |
|--|---|---|
| | Western Region: (413) 784-1100 24-hour Emergency Line: 1-888-304-1133 | |
| | If you are not sure which Massachusetts DEP Regional Office oversees your facility, go to http://www.mass.gov/eea/agencies/massdep/about/contacts/ . | |
| EPA | EPA New England: (617) 918-1510 | Report all SSO events |
| | OR | |
| | Southeast Region: David Turin, (617) 918-1598 | |
| | Northeast, Central and Western Regions: Douglas Koopman, (617) 918-1747 | |
| Local Board of Health | List of local BOH contact information available at | Report all SSO events to local |
| | http://www.mhoa.com/boh-roster/ | BOH(s) where impacts may occur |
| Department of Conservation and Recreation | State House Ranger Base 617-722-1188 | Where DCR beaches or parks affected |
| MA Division of Marine | Boston/Northeast: 617-727-3336 x 165 | Where shellfish resources may |
| Fisheries | Southeast: 508-563-1779 x 122 | be affected |
| Drinking Water Resource | List of Drinking Water Supply contacts available at | Where Drinking Water |
| Managers | http://www.mass.gov/eea/docs/dep/about/organization/pwscont.pdf | Resources may be affected |

Hazardous Material Releases: If you believe an overflow, bypass, or any other discharge may have resulted in an oil or hazardous material release, report it to DEP at any time, 24 hours a day, at this toll free number: 1-888-304-1133.

MassDEP may require, on a case-by-case basis, more extensive reporting of the SSO event where determined necessary to protect users of resources affected by SSO discharges.

Step Two:

Submit a written report to DEP within five (5) calendar days of the time you become aware of the overflow, bypass or backup. DEP requires the use of the MassDEP Sanitary Sewer Overflow (SSO)/Bypass notification form, unless an alternative reporting form is authorized by MassDEP in writing.



Massachusetts Department of Environmental Protection Bureau of Water Resources – Wastewater Management Program

Sanitary Sewer Overflow(SSO)/Bypass Notification Form Instructions

The Notification form should be fully completed, and shall include a clear description of the overflow, or bypass and its causes, including the best approximation of the dates and times, and if the situation has not been corrected, the amount of time the overflow/bypass is expected to continue, and a description of the measures to be implemented to stop the discharge. The Form or attachments must also include steps taken or planned to reduce, eliminate, and prevent recurrence.

If you have a discharge permit, check the Monitoring and Reporting Section of your permit to determine if your *Notification Form* should be sent to the attention of DEP's regional Bureau of Waste Prevention (industrial facilities) or the regional Bureau of Water Resources (nonindustrial facilities). All municipal facilities shall submit their reports to the Bureau of Water Resources.

Fax the *Notification Form* to the attention of the Bureau of Water Resources in your DEP regional office and to the appropriate EPA personnel depending on your DEP region:

- Massachusetts Department of Environmental Protection, Northeast Regional Office, 205B Lowell Street, Wilmington, MA 01887. Fax: 978-694-3499.
- Massachusetts Department of Environmental Protection, Central Regional Office, 8 New Bond Street, Worcester, MA 01606. Fax: 508-792-7621.
- Massachusetts Department of Environmental Protection, Southeast Regional Office, 20 Riverside Drive, Lakeville, MA 02347. Fax: 508-947-6557.
- Massachusetts Department of Environmental Protection, Western Regional Office, 436 Dwight Street, Springfield, MA 01103. Fax: 413-784-1149.
- U.S. Environmental Protection Agency, Water Technical Unit (OES 04-4), 5 Post Office Square –
 Suite 100, Boston, MA 02109-3912
 - Southeast Region: David Turin, Fax 617-918-0598
 - Northeast, Central and Western Regions: Douglas Koopman, Fax (617) 918-0747

What should I do if I'm not sure of the information I am providing?

For required items such as time of occurrence, causes of incident, volume of overflow, etc., PROVIDE YOUR BEST ESTIMATE OR ASSESSMENT AT THE TIME OF THIS REPORT. You can submit any additions or corrections later.

What is the best way to report the exact location of the overflow, or bypass?

Include with your *Notification Form* a copy of a map indicating its location. Please use 8 ½ " by 11" paper at an appropriate scale between 1:5000 to 1:25000. Specifying the geographic location will help DEP determine the public health and water quality impacts associated with overflows and bypasses.

Why do I need to report backups into buildings?

DEP wants to ensure that sewage backups into buildings as a result of problems in the sewer system are properly repaired and measures are put in place to reduce the likelihood of recurrence. Owner/operators of sewer systems that caused a backup may need to repair, rehabilitate, or upgrade the hydraulic capacity of their system, or change their operations and maintenance procedures.

Are there some overflows or Bypass that are not subject to these reporting requirements?

DO NOT use the Sanitary Sewer Overflow(SSO)/Bypass Notification Form in the following situations:



Massachusetts Department of Environmental Protection Bureau of Water Resources – Wastewater Management Program

Sanitary Sewer Overflow(SSO)/Bypass Notification Form Instructions

- The overflow is from a properly permitted Combined Sewer Overflow structure. Follow the reporting requirements in your NPDES Permit.
- You are reporting an overflow or bypass of sewage for a collection system or treatment works that is not under your ownership and control. However, please assist DEP by immediately reporting to the appropriate DEP Regional Office by phone or fax any overflows or bypass incidences for facilities other than your own which involve a discharge of wastewater to the environment.

What are the state regulations that apply to this notification? Where can I get copies?

These regulations include, but are not limited to:

- Surface Water Discharge Regulations, 314 CMR 3.00
- Groundwater Discharge Regulations, 314 CMR 5.00
- Sewer Connection Regulations, 314 CMR 7.00
- Operation and Maintenance Regulations, 314 CMR 12.00

Official copies of the regulations may be purchased at:

State Bookstore State House, Room 116 Boston, MA 02133 617-727-2834 State Bookstore 436 Dwight Street Springfield, MA 01103 413-784-1376



Massachusetts Department of Environmental Protection

Bureau of Resource Protection - Wastewater Management Program

Sanitary Sewer Overflow(SSO)/Bypass Notification Form

Instructions

Who must notify DEP about an overflow or bypass, and when?

Any owner or operator of the following facilities:

- Municipal, state, federal, regional, industrial or other private wastewater collection system;
- Wastewater utility;
- Wastewater treatment works;
- Facility with a groundwater discharge permit;
- Facility with a surface water discharge permit.

This requirement includes any owner or operator of a satellite municipal collection system or other collection system that is part of a larger POTW not under the same ownership and control.

The following situations require notification to DEP and submittal of the SSO Report Form:

- An un-permitted overflow or bypass;
- Backup of wastewater into public or private property when the event is caused by a condition of the system owned and operated by the sewer authority
- In a combined sewer system, an overflow or bypass during dry weather conditions or at a location not covered by a NPDES permit, or from a portion of the system that has a separate sanitary sewer.

Backups of wastewater into a property which are not caused by conditions in the system owned and operated by the sewer system are not required to be reported. These incidents normally occur due to blockages in service connections to a property or blockages in the internal plumbing system.

What are the procedures for reporting?

Step One:

Immediate Telephone and/or email notification to MassDEP, EPA, and other parties:

Notification to MassDEP and other regulatory authorities is a critical element of the SSO response plan. Notification must be made as soon as possible, and no later than 24 hours after discovery of the event. The agency notifications should include all responsible officials whose duties include management of resources which may be affected by the SSO discharge. A list of agencies, contact staff, phone numbers, and emails should be kept by the Sewer Authority and posted for easy access to responsible staff. A list of some relevant agencies follows:

| Agency: | Contact | Requirements |
|---------|------------------------|-----------------|
| MassDEP | During business hours: | Report all SSO |
| | | events to |
| | Northeast Region: | relevant |
| | (978) 694-3215 | regional office |
| | | Report SSO's to |
| | Central Region: | emergency line |
| | (508) 792-7650 | during non- |
| | | business hours |
| | Southeast Region: | |



Sanitary Sewer Overflow(SSO)/Bypass Notification Form Instructions

| | (508) 946-2750 | |
|----------------------------|---|--------------------------------|
| | Western Region: | |
| | (413) 784-1100 | |
| | 24-hour Emergency Line: | |
| | 1-888-304-1133 | |
| | If you are not ours which Massachusetta DED Regional Office | |
| | If you are not sure which Massachusetts DEP Regional Office oversees your facility, go to | |
| | http://www.mass.gov/eea/agencies/massdep/about/contacts/. | |
| EPA | EPA New England: | Report all SSO |
| | (617) 918-1870 | events |
| Local Board of | List of level POH contact information available at | Deport all CCO |
| Local Board of Health | List of local BOH contact information available at | Report all SSO events to local |
| | http://www.mhoa.com/boh-roster/ | BOH(s) where |
| | | impacts may |
| Department of | Chata Hayea Dangar Dana | occur Where DCR |
| Department of Conservation | State House Ranger Base 617-722-1188 | beaches or |
| and | 017-722-1100 | |
| Recreation | | parks affected |
| MA Division of | Boston/Northeast: | Where shellfish |
| Marine | 617-727-3336 x 165 | resources may |
| Fisheries | Southeast: | be affected |
| | 508-563-1779 x 122 | |
| Drinking Water | List of Drinking Water Supply contacts available at | Where Drinking |
| Resource | 3 | Water |
| Managers | http://www.mass.gov/eea/docs/dep/about/organization/pwscont.pdf | Resources may |
| | | be affected |

Hazardous Material Releases: If you believe an overflow, bypass, or any other discharge may have resulted in an oil or hazardous material release, report it to DEP at any time, 24 hours a day, at this toll free number: 1-888-304-1133.

MassDEP may require, on a case-by-case basis, more extensive reporting of the SSO event where determined necessary to protect users of resources affected by SSO discharges.

Step Two:

Submit a written report to DEP within five (5) calendar days of the time you become aware of the overflow, bypass or backup. DEP requires the use of the MassDEP Sanitary Sewer Overflow (SSO)/Bypass notification form, unless an alternative reporting form is authorized by MassDEP in writing.

The Notification form should be fully completed, and shall include a clear description of the overflow, or bypass and its causes, including the best approximation of the dates and times, and if the situation has not been corrected, the amount of time the overflow/bypass is expected to continue, and a description of the measures to be implemented to stop the discharge. The Form or attachments must also include steps taken or planned to reduce, eliminate, and prevent recurrence.



Sanitary Sewer Overflow(SSO)/Bypass Notification Form Instructions

If you have a discharge permit, check the Monitoring and Reporting Section of your permit to determine if your *Notification Form* should be sent to the attention of DEP's regional Bureau of Waste Prevention (industrial facilities) or the regional Bureau of Resource Protection (nonindustrial facilities). All municipal facilities shall submit their reports to the Bureau of Resource Protection.

Fax the *Notification Form* to the attention of the Bureau of Resource Protection in your DEP regional office:

- Massachusetts Department of Environmental Protection, Northeast Regional Office, 205B Lowell Street, Wilmington, MA 01887. Fax: 978-694-3499.
- Massachusetts Department of Environmental Protection, Central Regional Office, 8
 New Bond Street, Worcester, MA 01606. Fax: 508-792-7621.
- Massachusetts Department of Environmental Protection, Southeast Regional Office, 20 Riverside Drive, Lakeville, MA 02347. Fax: 508-947-6557.
- Massachusetts Department of Environmental Protection, Western Regional Office, 436 Dwight Street, Springfield, MA 01103. Fax: 413-784-1149.
- U.S. Environmental Protection Agency, Water Technical Unit (OES 04-4), 5 Post Office Square –
 Suite 100, Boston, MA 02109-3912 Fax: 617-918-0870

What should I do if I'm not sure of the information I am providing?

For required items such as time of occurrence, causes of incident, volume of overflow, etc., PROVIDE YOUR BEST ESTIMATE OR ASSESSMENT AT THE TIME OF THIS REPORT. You can submit any additions or corrections later.

What is the best way to report the exact location of the overflow, or bypass?

Include with your *Notification Form* a copy of a map indicating its location. Please use 8 ½ " by 11" paper at an appropriate scale between 1:5000 to 1:25000. Specifying the geographic location will help DEP determine the public health and water quality impacts associated with overflows and bypasses.

Why do I need to report backups into buildings?

DEP wants to ensure that sewage backups into buildings as a result of problems in the sewer system are properly repaired and measures are put in place to reduce the likelihood of recurrence. Owner/operators of sewer systems that caused a backup may need to repair, rehabilitate, or upgrade the hydraulic capacity of their system, or change their operations and maintenance procedures.

Are there some overflows or Bypass that are not subject to these reporting requirements? DO NOT use the Sanitary Sewer Overflow(SSO)/Bypass Notification Form in the following situations:

- The overflow is from a properly permitted Combined Sewer Overflow structure. Follow the reporting requirements in your NPDES Permit.
- You are reporting an overflow or bypass of sewage for a collection system or treatment works that is not under your ownership and control. However, please assist DEP by immediately reporting to the appropriate DEP Regional Office by phone or fax any overflows or bypass incidences for facilities other than your own which involve a discharge of wastewater to the environment.



Sanitary Sewer Overflow(SSO)/Bypass Notification Form Instructions

What are the state regulations that apply to this notification? Where can I get copies?

These regulations include, but are not limited to:

- Surface Water Discharge Regulations, 314 CMR 3.00
- Groundwater Discharge Regulations, 314 CMR 5.00
- Sewer Connection Regulations, 314 CMR 7.00
- Operation and Maintenance Regulations, 314 CMR 12.00

Official copies of the regulations may be purchased at:

State Bookstore State House, Room 116 Boston, MA 02133 617-727-2834 State Bookstore 436 Dwight Street Springfield, MA 01103 413-784-1376



Massachusetts Department of Environmental Protection Bureau of Resource Protection – Watershed Permitting Program Sanitary Sewer Overflow (SSO)/Rypass

Sanitary Sewer Overflow (SSO)/Bypass Notification Form

FOR DEP USE ONLY

Tax Identification Number

Important: When filling out forms on the computer, use only the tab key to move your cursor - do not use the return key.





See DEP Regional Office telephone and fax numbers at the end of this form.

| Α. | Reporting Facility | | | | | |
|----|------------------------------------|---------------------|--------------|--------------------|------------|----|
| 1. | Facility Information | | | | | |
| | Reporting Sewer Authority | | | Per | rmit # | |
| 2. | Authorized Representative Tra | nsmitting Form: | | | | |
| | First Name | Last Name | | Talanhana Na | | |
| | riist Name | Last Name | | Telephone No | | |
| | Title Dhone Notifications | | E-mail Add | ress | | |
| В. | Phone Notifications: | | | | | |
| 1. | MassDEP staff contacted: | first name | | last name | | |
| | Date/Time contacted: | Date | | Time | am | pm |
| 2. | EPA staff contacted: | first name | | last name | | |
| | Date/Time EPA contacted: | Date | | Time | am | pm |
| 3. | Board of Health contacted: | First Name | | Last Name | | |
| | Date/Time contacted: | Date | | Time | am | pm |
| 4. | Others notified (select all that a | apply); | ☐ Conserva | tion Commission | | |
| | ☐ Harbormaster ☐ She | ellfish Warden | Division o | f Marine Fisheries | | |
| | ☐ Downstream Drinking Water | er Supplier 🔲 V | Vatershed A | ssociation | | |
| | ☐ Beach Resource Manager | Other: | (specify) | | | |
| C. | SSO Information | | (| | | |
| 1. | SSO Discovered: | Date | | Time | — <u> </u> | pm |
| | Ву: | | | | | |
| 2. | SSO Stopped: | Date | | Time | am | pm |
| 3. | SSO Discharge from: Sa | nitary Sewer Manh | nole 🗌 F | Pump Station | | |
| | ☐ Backup into Property ☐ | Other: | (specify) | | | |
| 4. | SSO Discharge to: Groun | d Surface (no relea | se to surfac | e water) | | |
| | ☐ Direct to Receiving Water | | (surface wa | ater) | | |
| | ☐ Catch basin to Receiving V | Vater | (surface wa | ater) | | |
| | ☐ Backup into Property Base | ment | | | | |



Massachusetts Department of Environmental Protection Bureau of Resource Protection – Watershed Permitting Program Sanitary Sower Overflow (SSO)/Bypass

Sanitary Sewer Overflow (SSO)/Bypass Notification Form

FOR DEP USE ONLY

Tax Identification Number

| C. | SSO Information (cont.) |
|----|---|
| | Location: (Description of discharge site or closest address) |
| 5. | Estimated SSO Volume at time of this Report: |
| | Method of Estimating Volume: |
| 6. | Cause of SSO Event: |
| | ☐ Rain Event ☐ Pump Station Failure ☐ Insufficient Capacity in System |
| | ☐ Treatment Unit failure |
| | ☐ Sewer System Blockage: ☐ Pipe Collapse ☐ Root Intrusion ☐ Grease Blockage |
| | Other: (Specify) |
| 7. | Corrective Actions Taken: |
| | |
| | |
| | |
| | |
| | Impact Area cleaned and/or disinfected: |
| | |
| | |
| | Corrective Actions Completed: |
| | |
| | |
| D. | Comments/Attachments/Follow-up |
| | I wish to provide (select all that apply): |
| | ☐ Attachment ☐ Additional comments below: ☐ No additional comments or attachments |
| | Additional comments and planned actions: |
| | |
| | |
| | |



Massachusetts Department of Environmental Protection Bureau of Resource Protection – Watershed Permitting Program

Sanitary Sewer Overflow (SSO)/Bypass Notification Form

FOR DEP USE ONLY

Tax Identification Number

E. Certification Statement

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Signature of Authorized Representative

Date Signed

Please keep a copy of this report for your records. When submitting additional information, include the MassDEP Incident Number from this report.

MassDEP Regional Office and EPA Telephone and Fax Numbers:

Northeast Region Phone: 978-694-3215 Fax: 978-694-3499

Southeast Region Phone: 508-946-2750 Fax: 508-947-6557

Central Region Phone: 508-792-7650 Fax: 508-792-7621

Western Region Phone: 413-784-1100 Fax: 413-784-1149

EPA Contact Phone: 617-918-1870 Fax: 617-918-0870

DEP 24-hour emergency

Phone: 888-304-1133

Town of Wilbraham IDDE Program Appendix D

Preliminary Outfall Inventory, Outfall and Catchment Ranking, and Map

Town of Wilbraham MS4 Outfall and Interconnection Inventory, Initial Ranking, and Initial Catchment Delineations

To: Tonya Basch, P.E., Assistant Town Engineer

FROM: Tracy J. Adamski, AICP, Tighe & Bond

DATE: June 27, 2019

Tighe & Bond has completed the **Town of Wilbraham's** initial outfall and interconnection inventory and ranking in accordance with Part 2.3.4.5 and 2.3.4.7 of the U.S. Environmental EPA's National Pollutant Discharge Elimination System (NPDES) General Permits for Stormwater Discharges from Small Municipal Separate Storm Sewer Systems (MS4s) in Massachusetts, effective July 1, 2018 (Small MS4 General Permit). The initial inventory and ranking determine the priority screening order for all outfalls and interconnections in accordance with Part 2.3.4.7.b of the Small MS4 General Permit and catchment investigations for evidence of illicit discharges and SSOs in accordance with Part 2.3.4.8 of the Small MS4 General Permit.

This memorandum and associated summary tables and map satisfy EPA's requirement to include initial catchment delineations on the Phase I system map (due within two years of the permit effective date) and to priority rank each outfall based on illicit discharge potential (due within one year of the permit effective date). The inventory and delineations will be updated as the Illicit Discharge Detection and Elimination (IDDE) Program is implemented and updates will be included in subsequent Annual Reports.

1. Outfall Inventory and Priority Ranking

Tighe & Bond followed EPA's ranking process outlined in Part 2.3.4.7.a of the Small MS4 General Permit for each of the known outfalls and interconnections in town. Based on the outfall ranking category definitions in Part 2.3.4.7.a.ii, outfalls were ranked into one of the four categories: Problem, High Priority, Low Priority, and Excluded outfalls. Descriptions of these categories can be found in Section 6 of the Town's IDDE Plan. At this time, there are no known interconnections. As of June 2019, the Town's stormwater GIS indicates that there are **351 outfalls** within the Town boundary and **241 outfalls** that fall inside the MS4 urbanized area and are regulated by the 2016 Small MS4 General Permit.

During the initial desktop screening, Tighe & Bond concluded that none of the known outfalls should be ranked as a Problem outfall because no known historic illicit connection or discharge problem areas existed within the Town. Additionally, none of the outfalls were classified as Excluded outfalls since all outfalls, at this time, have the *potential* for an illicit discharge. For this reason, each outfall was assigned either a Low or High Priority during the initial ranking.

The following criteria were used to classify the Town's MS4-regulated outfalls as High or Low Priority. Outfalls were classified as High Priority if they exhibited one or more of the determination factors described below. Outfalls that did not exhibit any of the determination factors were categorized as Low Priority. Several outfalls exhibited more than one criterion and are listed under multiple categories below. The attached Preliminary Outfall Inventory and Catchments Map illustrates where these areas of concern are within Wilbraham's regulated area and in relation to each outfall.

TECHNICAL MEMORANDUM Tighe&Bond

Proximity to Dense Development

Based on discussion with the Town, outfalls discharging in areas of dense residential development, particularly near water bodies, were ranked as High Priority for the greater potential to create illicit discharges. Within Wilbraham, the Pines neighborhood was identified in the Town of Wilbraham's Open Space and Recreation Plan as a relatively dense development adjacent to the Chicopee River, and the associated 7 outfalls were therefore considered as High Priority.

Industrial/Commercial Development

Outfalls discharging in areas of dense industrial/commercial development were also ranked as High Priority based on the greater potential to create illicit discharges. Within Wilbraham, the Route 20/Boston Road corridor was identified as an area with concentrated industrial/commercial development, and the associated 19 outfalls were therefore considered as High Priority.

Proximity to Floodplain

Outfalls located within the 100-year floodplain of a waterbody within the Town of Wilbraham were considered to be High Priority based on the potential for on-site wastewater disposal system functionality problems related to flooding and for pollution prevention. Based on MassGIS data, 51 outfalls within the 100-year floodplain are considered to be High Priority.

Poor Subsurface Conditions for On-Site Wastewater Treatment

Additionally, soils data was reviewed for trends of general areas with poor subsurface conditions (such as shallow bedrock or thick till) that could lead to untreated wastewater being introduced into groundwater or nearby streams and water bodies. Individual failures were not assessed, since failures may occur anywhere due to lapses in the regularly required inspection and maintenance. In Wilbraham, areas of shallow bedrock/abundant outcrops and/or thick till are primarily located east of Main Street per MassGIS, leading to ranking of 23 outfalls as a high priority.

Proximity to Public Beach/Recreational Areas

The Nine Mile Pond and Spectacle Pond area of Town has a public beach and recreational area. The 3 outfalls within this area are designated as High Priority outfalls due to pollution prevention concerns.

Proximity to Impaired Waters

All outfalls within 500 feet of an impaired waterbody listed as a Category 4A or Category 5 water in the Massachusetts 2014 Integrated List of Waters with a pollutant of concern associated with stormwater were considered high priority. Based on this criterion, 10 outfalls within 500 feet of the Chicopee River or 500 feet of Spectacle Pond were considered High Priority.

Summary

Based on the screening procedure described in Section 1 of this memorandum, the Town of Wilbraham's initial outfall and interconnection inventory includes 83 High Priority outfalls and 158 Low Priority outfalls.

TECHNICAL MEMORANDUM Tighe&Bond

2. Initial Catchment Delineation

Initial catchment delineations and rankings were completed based on the Metropolitan Area Planning Council's GIS-Based Catchment Delineation and Ranking Methodology available through the Neponset Stormwater Partnership. Slight modifications to MAPC's delineation process were made to account for lack of connectivity in the entire stormwater system. These modifications included burning in polygon water features at -2.0 meters, polyline water features at -1.0 meters, right-of-way polylines at -1.0 meters and only class 1-4 road centerlines at 0.5 meters. Catch basins were snapped at 15 feet instead of the default 5 feet. Tighe & Bond was not able to delineate each of the outfalls where Wilbraham's stormwater GIS lacked connectivity because using topography alone may not represent the drainage area contributing to an outfall. This delineation produced **194 initial catchment delineations**. As Wilbraham's stormwater mapping and connectivity is updated during implementation of the IDDE Program, the catchments can be further refined.

A priority ranking was assigned to each delineated catchment based on the ranking of the associated outfall. For example, if an outfall was considered a High Priority because of proximity to the Chicopee River, the associated catchment would also be ranked as a High Priority catchment. For catchments with multiple outfalls, the catchment was ranked based on the outfall with the highest rank (i.e., if one outfall was ranked Low Priority and one outfall was ranked High Priority, the catchment was assigned a rank of High Priority). The initial catchment delineations and rankings are shown on the Preliminary Outfall Catchment map.

Summary

Based on the screening procedure described in Section 2 of this memorandum, the Town of Wilbraham's initial catchment inventory includes **66 High Priority catchments** and **128 Low Priority catchments**. 47 outfalls do not have a separate associated catchment area delineated as of the date of this memorandum and will need to be further refined as stormwater mapping is improved.

Attachments

Outfall and Interconnection Inventory and Initial Ranking Table

Preliminary Outfall Inventory and Catchments Map

J:\H\H1436 Wilbraham\011 - MS4 Year 1 NOI & GIS\Report_Evaluation\Written IDDE Plan\App E Catchment Map & Priority Ranking\Draft Wilbraham Outfall Prioritization Memo.docx

¹ MAPC. February 2015. *Neponset Outfall Catchment Analysis*. https://github.com/MAPC/stormwater-toolkit

| | | | | Town of Wilbraham Outfall Inventory | | |
|----------------------|-----------------------------|-----------|--------------------------------------|--|-------------------------|--|
| Town Outfall ID | Pipe Size (inches) Material | Condition | | Notes | Date of Last Inspection | |
| 1 | 10 | | 10 MAYNARD RD | | 2018 | Chicopee River (MA36-23) |
| 2 | | | 222 MAYNARD RD | | | Outside Receiving Waterbody |
| 4 | | | 22 WARREN RD | | 2018 | Wetland/Tributary to Calkins Brook |
| 5 | | | 6 CIRCLE DR | | 2018 | Outside Receiving Waterbody |
| 6 | | | 2480 BOSTON RD | | 2017 | Chicopee River (MA36-24) |
| 7 | 24 CMP | | 15 HEMINGWAY RD | | 2018 | Outside Receiving Waterbody |
| 8 | 10 CONCRETE | | 8 LONGFELLOW DR | | | Outside Receiving Waterbody |
| 9 | 24 | | 21V CIRCLE DR | 24 inch outfall to ditch | 2018 | Wetland/Tributary to Calkins Brook |
| 10 | 24 RCP | | 12 DOLLAR AV | 24 inch RCP outfall to 6-18 inch stone | 2010 | Wetland/Tributary to Chicopee River (MA36-23) |
| 11 | 15 | | 4 POPLAR DR | 24 men ken dahan to d 10 men stone | 2017 | Outside Receiving Waterbody |
| 19 | 15 | | 6 LINWOOD DR | | 2017 | Wetland/Tributary to Chicopee River (MA36-24) |
| | | | 8 OXFORD DR | | | |
| 20 | | | | | 2017 | Wetland/Tributary to Chicopee River (MA36-24) |
| 21 | | | 33 LINWOOD DR | | 2017 | Wetland/Tributary to Chicopee River (MA36-24) |
| 22 | 12 | | 56 RIVER RD A | | | Chicopee River (MA36-24) |
| 25 | 12 | | 2540V BOSTON RD A | | 2017 | Outside Receiving Waterbody |
| 26 | | | 2720 BOSTON RD | | | Outside Receiving Waterbody |
| 27 | | | 2780 BOSTON RD | | | Outside Receiving Waterbody |
| 28 | | | 3I COTTAGE AV | | 2017 | Wetland/Tributary to Chicopee River (MA36-23) |
| 29 | | | 2830 BOSTON RD C | | | Outside Receiving Waterbody |
| 30 | | | 2830 BOSTON RD B | | | Outside Receiving Waterbody |
| 31 | | | 2830 BOSTON RD A | | | Chicopee River (MA36-23) |
| 32 | | | Across From 2835 BOSTON RD C | | | Chicopee River (MA36-23) |
| 33 | | | Across From 2835 BOSTON RD B | | | Chicopee River (MA36-23) |
| 34 | | | Across From 2835 BOSTON RD B | | | Chicopee River (MA36-23) |
| 3 4 35 | | | Across From 2960 BOSTON RD A | | | Chicopee River (MA36-23) Chicopee River (MA36-23) |
| | | | | | 2010 | |
| 36 | 4.5 | | 2V MAYNARD RD | | 2018 | Chicopee River (MA36-23) |
| 37 | 15 | | 115 MAIN ST | | | Wetland/Tributary to Nine Mile Pond |
| 38 | 12 | | 3VR MAPLEWOOD DR C | | 2017 | Isolated Wetland Dipping Hole Road |
| 39 | 12 | | 3VR MAPLEWOOD DR A | | 2017 | Outside Receiving Waterbody |
| 40 | 12 | | 3VR MAPLEWOOD DR B | | 2017 | Outside Receiving Waterbody |
| 41 | 12 | | 3 SURREY LN | | 2017 | Outside Receiving Waterbody |
| 42 | 12 | | 449V DIPPING HOLE RD A | | 2017 | Outside Receiving Waterbody |
| 43 | 12 | | 17V PRIMROSE LN | | 2017 | Isolated Wetland Dipping Hole Road |
| 44 | 24 | | 4V FOX HILL DR | | 2017 | Outside Receiving Waterbody |
| 45 | 36 | | 318 MAIN ST C | | 2017 | Wetland/Tributary to Nine Mile Pond |
| 46 | 6 | | 318 MAIN ST A | | 2017 | Wetland/Tributary to Nine Mile Pond |
| 47 | | | | | | |
| | 12 | | 318 MAIN ST B | | 2017 | Wetland/Tributary to Nine Mile Pond |
| 48 | 24 | | 26V STIRLING DR A | | 2017 | Outside Receiving Waterbody |
| 49 | 12 | | 39 BLACKSMITH RD | | | Isolated Wetland Dipping Hole Road |
| 50 | 12 | | 21 BITTERSWEET LN | | 2017 | Wetland/Tributary to North Branch Mill River |
| 51 | 12 | | 9V BITTERSWEET LN | | | Wetland/Tributary to North Branch Mill River |
| 52 | 12 | | 7 BITTERSWEET LN | | | Outside Receiving Waterbody |
| 53 | | | 21V MCINTOSH DR | | 2017 | Wetland/Tributary to Bennett Pond |
| 54 | 18 | | 3 BELLOWS RD | | 2018 | Outside Receiving Waterbody |
| 55 | 12 | | 13A-V OLDWOOD RD B | | 2018 | Wetland/Tributary to South Branch Mill River |
| 57 | 12 | | 4V SOUTHWOOD DR B | | 2017 | Wetland/Tributary to South Branch Mill River |
| 58 | 12 | | 13A-V OLDWOOD RD A | | 2017 | Wetland/Tributary to South Branch Mill River |
| 59 | 12 | | 37V SHIRLEY ST | | 2017 | North Branch Mill River |
| 60 | 12 | | 9 PARK DR | | 2017 | Wetland/Tributary to Bennett Pond |
| | | | | | | |
| 61 63 | 12 | | 21 WESTERN VIEW DR 18 WOODSLEY RD | | 2017 2017 | Wetland/Tributary to Bennett Pond |
| 63 | 12 | | | | 2017 | Outside Receiving Waterbody |
| 64 | 12 | | 6 PHEASANT FARM RD | | 2017 | Wetland/Tributary to South Branch Mill River |
| 65 | 18 | | 3 WARREN RD A | | 2018 | Outside Receiving Waterbody |
| 66 | 24 | | 6 CHRISTOPHER CR | | 2018 | Wetland/Tributary to Bennett Pond |
| 67 | 12 | | 6 JUDITH DR | | 2017 | Wetland/Tributary to Bennett Pond |
| 68 | 12 | | 6 CATHERINE CR | | 2017 | Wetland/Tributary to Bennett Pond |
| 69 | 21 | | 20V WRIGHT PL | | | Wetland/Tributary to North Branch Mill River |
| 70 | 12 | | 2 WRIGHT PL | | 2017 | Wetland/Tributary to North Branch Mill River |
| 71 | | | 10 MCINTOSH DR | | 2017 | Wetland/Tributary to Bennett Pond |
| 72 | 12 | | 9 PEARL DR | | 2017 | Wetland/Tributary to South Branch Mill River |
| 73 | | FAIR | 1228 STONY HILL RD | | 2017 | Wetland/Tributary to South Branch Mill River |
| 73 74 | | I UTI/ | 12 BONAIR DR | | 2018 | Wetland/Tributary to South Branch Mill River |
| | | | | | | |
| 75 76 | | | 9 DEEPWOOD DR | | 2017 | Wetland/Tributary to South Branch Mill River |
| 76 77 | 2.4 | | 257V SOULE RD | | 2017 | Wetland/Tributary to South Branch Mill River |
| 77 | 24 | | 1 HEMLOCK CR | | 2017 | Outside Receiving Waterbody |
| 78 | | | 43 PLEASANT VIEW RD A | | | South Branch Mill River |
| 79 | | | 43 PLEASANT VIEW RD B | | 2018 | South Branch Mill River |
| 82 | 24 RCP | | 7 TALL TIMBER DR | RCP FE with paved swale | 2017 | Outside Receiving Waterbody |
| 85 | 24 RCP | FAIR | 794V STONY HILL RD | 24 RCP FE | 2017 | Outside Receiving Waterbody |
| 86 | | | 14 WEST COLONIAL RD | | 2018 | Outside Receiving Waterbody |
| 87 | | | 4 MEMORY LN | | 2017 | Outside Receiving Waterbody |
| 88 | | | 22V OAKLAND ST | | 201, | Outside Receiving Waterbody |
| 89 | 12 | DAMAGED | 14 MEADOW VIEW RD | rusted pipe | 2018 | Outside Receiving Waterbody Outside Receiving Waterbody |
| 90 | 24 | GOOD | 4 MIRICK LN | i usicu pipe | 2018 | Wetland/Tributary to Bennett Pond |
| | | | 4 MIRICK LIN 11 SYLVAN DR | | | |
| 92 | 12 | GOOD | | | 2017 | Wetland/Tributary to South Branch Mill River |
| 93 | 12 | GOOD | 4 MEADOW VIEW RD | | 2017 | Outside Receiving Waterbody |
| | | | | | | |

| Town Outfall ID | Pipe Size (inches) | Material | Condition | Location | Town of Wilbraham Outfall Inventory | Notes | Date of Last Inspection | Receiving Water |
|-----------------|--------------------|----------|-----------|---|-------------------------------------|-------|-------------------------|--|
| 94 | | | | 14 WESTERN VIEW DR | | | 2017 | Wetland/Tributary to Bennett Pond |
| 95 | | | | 1 OAKLAND ST | | | 2017 | Outside Receiving Waterbody |
| 96 | | | | 1004 MAIN ST | | | 2018 | Wetland/Tributary to Bennett Pond |
| 97 | | | | 200 SOULE RD | | | 2018 | Outside Receiving Waterbody |
| 99 100 | 15 | | FAIR | 28 LONGVIEW DR 22 LONGVIEW DR | cmn | | 2018 2017 | Wetland/Tributary to Bennett Pond Wetland/Tributary to Bennett Pond |
| 100 | 15 | | FAIK | 9V KATIE ST A | cmp | | 2017 | Outside Receiving Waterbody |
| 102 | | | | 5 JEFFREY LN | | | 2017 | Wetland/Tributary to Bennett Pond |
| 103 | | | | 35 MOUNTAINBROOK RD | | | 2017 | Outside Receiving Waterbody |
| 104 | | | | 29V BRENTWOOD DR A | | | 2018 | Wetland/Tributary to Bennett Pond |
| 105 | | | | 29V BRENTWOOD DR B | | | 2018 | Wetland/Tributary to Bennett Pond |
| 106 | | | | 1 SAWMILL DR | | | | Outside Receiving Waterbody |
| 107 | | | | 651 MAIN ST | | | | Wetland/Tributary to North Branch Mill River |
| 108 | | | | 875V TINKHAM RD A | | | 2017 | Wetland/Tributary to North Branch Mill River |
| 109 110 | | | | 11 OLD CARRIAGE DR 676V TINKHAM RD | | | 2018 2018 | Outside Receiving Waterbody Wetland/Tributary to North Branch Mill River |
| 111 | | | | 19 BROOKSIDE CR | | | 2017 | North Branch Mill River |
| 112 | | | | 34 BROOKSIDE DR | | | 2017 | North Branch Mill River |
| 113 | | | | 6 WESTWOOD DR | | | 2017 | North Branch Mill River |
| 114 | | | | 14V INWOOD DR A | | | | Outside Receiving Waterbody |
| 115 | | | | 10 COOLEY DR | | | 2017 | Outside Receiving Waterbody |
| 116 | | | | 359 SPRINGFIELD ST | | | 2017 | Wetland/Tributary to North Branch Mill River |
| 117 | | | | 649V STONY HILL RD A | | | | Outside Receiving Waterbody |
| 118 119 | 12 | | | 649V STONY HILL RD 2 AMY LN | | | | Outside Receiving Waterbody Outside Receiving Waterbody |
| 120 | 18 | | | 16 BRIAR CLIFF DR | | | | Outside Receiving Waterbody Outside Receiving Waterbody |
| 121 | 10 | | | 29 BRIAR CLIFF DR | | | 2017 | Outside Receiving Waterbody |
| 122 | | | | 28 BRIAR CLIFF DR | | | | Outside Receiving Waterbody |
| 123 | | | | 46V BROOKLAWN RD | | | 2018 | Outside Receiving Waterbody |
| 124 | | | | 451 DIPPING HOLE RD | | | 2018 | Outside Receiving Waterbody |
| 125 | 10 | CMP | | 5 MELIKIAN DR | | | 2018 | Outside Receiving Waterbody |
| 126 | | | | 10 MARK RD | | | 2017 | Outside Receiving Waterbody |
| 127 128 | | | | 26 SUNNYSIDE TR 5 RED BRIDGE RD D | | | 2017 2017 | Outside Receiving Waterbody Chicopee River (MA36-24) |
| 129 | 8 | | | 8 STONY HILL RD | | | 2017 | Outside Receiving Waterbody |
| 130 | 12 | | | 5 RED BRIDGE RD C | | | 2020 | Chicopee River (MA36-24) |
| 131 | 12 | | | 5 RED BRIDGE RD B | | | | Chicopee River (MA36-24) |
| 132 | 12 | | | 5 RED BRIDGE RD A | | | | Chicopee River (MA36-24) |
| 133 | | | | 56 RIVER RD B | | | 2018 | Chicopee River (MA36-24) |
| 134 | | | | 73-75 OLD BOSTON RD | | | 2018 | Outside Receiving Waterbody |
| 135 137 | | | | 2343 BOSTON RD 50 BRAINARD RD | | | | Outside Receiving Waterbody Outside Receiving Waterbody |
| 139 | | | | 13 OLD FARM RD | | | 2017 | Outside Receiving Waterbody Outside Receiving Waterbody |
| 140 | | | | 2208 BOSTON RD B | | | 2017 | Outside Receiving Waterbody |
| 141 | | | | 2208 BOSTON RD A | | | | Outside Receiving Waterbody |
| 142 | | | | 2339 BOSTON RD | | | | Outside Receiving Waterbody |
| 143 | | | | 225 MAIN ST | | | | Outside Receiving Waterbody |
| 144 | 12 | | | 28 MAPLE ST | | | 2017 | Outside Receiving Waterbody |
| 145 146 | 15 | | | 10 BRIDLE PATH RD 188V STONY HILL RD | | | 2017 | Wetland/Tributary to South Branch Mill River Wetland/Tributary to North Branch Mill River |
| 147 | 24 | | | 1241 STONY HILL RD B | | | 2018 | South Branch Mill River |
| 148 | 2. | | | 766 MAIN ST | | | 2017 | Wetland/Tributary to Bennett Pond |
| 149 | | | | 728 MAIN ST | | | 2017 | Outside Receiving Waterbody |
| 156 | | | | 21 WANDERING MEADOWS LN | | | | Outside Receiving Waterbody |
| 157 | = . | | | 21 WANDERING MEADOWS LN | | | | Outside Receiving Waterbody |
| 158 | 24 | | | 4 DRUMLIN CR | | | | Outside Receiving Waterbody |
| 159 160 | 24 | | | 6 DRUMLIN CR 4V SOUTHWOOD DR A | | | 2017 | Outside Receiving Waterbody Wetland/Tributary to South Branch Mill River |
| 161 | | | | 479 STONY HILL RD | | | 2017 | Outside Receiving Waterbody |
| 162 | | | | 176 COTTAGE AV | | | 2010 | Wetland/Tributary to Chicopee River (MA36-23) |
| 163 | | | | Contract 2 Main Street | | | | Outside Receiving Waterbody |
| 164 | 10 | | | 26V STIRLING DR B | | | 2017 | Outside Receiving Waterbody |
| 165 | 15 | | | 9 VICTORIA LN | | | 2018 | Outside Receiving Waterbody |
| 166 | | | | 9V HITCHCOCK RD | | | 2017 | Outside Receiving Waterbody |
| 167 168 | 24 | | | 12 OVERLOOK DR 198 MAIN ST | | | 2018 2017 | Outside Receiving Waterbody |
| 169 | 24 12 | | | 2372 BOSTON RD | | | 2017 | Outside Receiving Waterbody Outside Receiving Waterbody |
| 174 | 24 | | | 2 LODGE LN | | | | Outside Receiving Waterbody Outside Receiving Waterbody |
| 175 | | FES | DAMAGED | 42V RED BRIDGE RD | NEEDS CLEANING | | 2018 | Outside Receiving Waterbody |
| 176 | 24 | FES | GOOD | 18 RED BRIDGE RD | FES to swale | | | Outside Receiving Waterbody |
| 177 | 18 | | GOOD | 30V RED BRIDGE RD | | | 2018 | Outside Receiving Waterbody |
| 178 | 12 | | | 299 THREE RIVERS RD | | | 2018 | Outside Receiving Waterbody |
| 179 | | | | 127 THREE RIVERS RD | | | 2018 | Wetland/Tributary to Chicopee River (MA36-23) |
| 180 181 | | | | 80 MAYNARD RD 42V MAYNARD RD | | | 2018 | Chicopee River (MA36-23) Outside Receiving Waterbody |
| 194 | | | | 404 MAIN ST | | | 2017 | Outside Receiving Waterbody Outside Receiving Waterbody |
| · | | | | - | | | — | J |

| | | | Town of | Wilbraham Outfall Inventory | | |
|-----------------|-----------------------------|-----------|------------------------|--|-------------------------|--|
| Town Outfall ID | Pipe Size (inches) Material | Condition | Location | Notes | Date of Last Inspection | Receiving Water |
| 197 | 12 | | 449V DIPPING HOLE RD B | | 2017 | Outside Receiving Waterbody |
| 201 | | | 12V PEARL DR | | 2018 | Wetland/Tributary to South Branch Mill River |
| 202 | 12 CMP | GOOD | 1241 STONY HILL RD A | | 2017 | Wetland/Tributary to South Branch Mill River |
| 204 | 12 CMF | GOOD | 480 MAIN ST | | 2017 | · · · · · · · · · · · · · · · · · · · |
| | | | | | | Outside Receiving Waterbody |
| 205 | | | 621 MAIN ST A | | | Wetland/Tributary to North Branch Mill River |
| 206 | | | 621 MAIN ST B | | 2018 | Wetland/Tributary to North Branch Mill River |
| 207 | 18 | | 621 MAIN ST C | | 2018 | Wetland/Tributary to North Branch Mill River |
| 208 | 18 | | 621 MAIN ST D | | 2018 | Wetland/Tributary to North Branch Mill River |
| 209 | 30 | | 535V MAIN ST | | 2018 | Wetland/Tributary to North Branch Mill River |
| 210 | | | 2 HUNTING LN | | 2018 | Wetland/Tributary to North Branch Mill River |
| 211 | 12 | | 2 MILES MORGAN CT | | 2017 | Wetland/Tributary to North Branch Mill River |
| | 12 | | | | | |
| 212 | | | 4 RAYMOND DR | | 2017 | Outside Receiving Waterbody |
| 213 | | | 24 RUTH DR | | 2017 | Wetland/Tributary to Bennett Pond |
| 214 | | | 16 OAKLAND ST | | 2017 | Outside Receiving Waterbody |
| 216 | | | 59 SOULE RD | | 2017 | Wetland/Tributary to Bennett Pond |
| 217 | | | 1 GARY DR | | 2017 | Outside Receiving Waterbody |
| 218 | | | 5 BURLEIGH RD B | | 2018 | Outside Receiving Waterbody |
| 220 | | | 19V MCINTOSH DR | | 2017 | Wetland/Tributary to Bennett Pond |
| 221 | | | 14 MOUNTAINBROOK RD | | 2017 | |
| | | | | | | Wetland/Tributary to Bennett Pond |
| 222 | | | 180 SOULE RD | | 2017 | Wetland/Tributary to Bennett Pond |
| 223 | | | 17 MILL BROOK DR | | 2017 | Wetland/Tributary to South Branch Mill River |
| 224 | | | 9 MILL BROOK DR | | 2018 | Wetland/Tributary to South Branch Mill River |
| 225 | | | 9V KATIE ST B | | | Outside Receiving Waterbody |
| 226 | | | 9V KATIE ST C | | | Outside Receiving Waterbody |
| 227 | | | 7 LEE LN | | 2017 | Outside Receiving Waterbody |
| 228 | | | 1069 TINKHAM RD | | 2017 | Outside Receiving Waterbody Outside Receiving Waterbody |
| | | | | | 201/ | |
| 229 | | | 1059 TINKHAM RD | | | Wetland/Tributary to Bennett Pond |
| 230 | | | 32 EASTWOOD DR | | 2017 | Outside Receiving Waterbody |
| 231 | | | 14V INWOOD DR A | | 2017 | North Branch Mill River |
| 232 | | | 20 VICTORIA LN | | | Outside Receiving Waterbody |
| 233 | | | 30 VICTORIA LN | | 2017 | Outside Receiving Waterbody |
| 234 | | | 2 BRUUER RD | | | Outside Receiving Waterbody |
| 235 | | | 423-451 MAIN ST | | 2018 | Isolated Wetland Wilbraham & Monson Academy |
| 233 | | | | | | |
| 236 | | | 50 DECORIE DR | | 2017 | Cedar Swamp |
| 237 | | | 2 CEDAR OAK DR | | | Cedar Swamp |
| 238 | | | 34 DECORIE DR | | 2017 | Cedar Swamp |
| 239 | | | 28 DECORIE DR | | | Cedar Swamp |
| 240 | | | 47 DECORIE DR | | 2017 | Cedar Swamp |
| 241 | | | 21 HORSESHOE LN | | 2017 | Outside Receiving Waterbody |
| 247 | | | 25 THREE RIVERS RD | | 2018 | Outside Receiving Waterbody Outside Receiving Waterbody |
| | | | | | 2016 | |
| 252 | | | 2 OLD ORCHARD RD | | | Wetland/Tributary to Nine Mile Pond |
| 253 | | | 4 ARBOR LN | | | Outside Receiving Waterbody |
| 257 | | | 376 THREE RIVERS RD | | 2018 | Outside Receiving Waterbody |
| 260 | | | 307 MOUNTAIN RD | | 2018 | Wetland/Tributary to Spear Brook |
| 265 | | | 335V MAYNARD RD | | 2018 | Wetland/Tributary to Chicopee River (MA36-23) |
| 266 | | | 5 RED BRIDGE RD | | 2018 | Wetland/Tributary to Chicopee River (MA36-22) |
| 267 | | | 757 MAIN ST | | 2017 | Wetland/Tributary to Bennett Pond |
| | | | | | 2017 | |
| 268 | | | 779 MAIN ST A | | 2017 | Outside Receiving Waterbody |
| 269 | | | 779 MAIN ST B | | 2017 | Wetland/Tributary to Bennett Pond |
| 271 | | | 7 APPLE HILL RD | | 2017 | Wetland/Tributary to Bennett Pond |
| 274 | | | 9V CEDAR OAK DR | | | Cedar Swamp |
| 275 | | | 138 MOUNTAIN RD | | 2017 | Outside Receiving Waterbody |
| 277 | | | 459 MOUNTAIN RD B | | | Outside Receiving Waterbody |
| 278 | | | 459 MOUNTAIN RD A | | 2017 | Outside Receiving Waterbody |
| 279 | | | 12 BROOKLAWN RD | | 2017 | North Branch Mill River |
| 280 | | | 20 WESTWOOD DR | | 2017 | Outside Receiving Waterbody |
| 200 | | | | | | |
| 281 | | | 24 SUNNYSIDE TR | | 2018 | Outside Receiving Waterbody |
| 282 | | | 7 COOLEY DR | | 2017 | Outside Receiving Waterbody |
| 283 | UNK | | 624 SPRINGFIELD ST | | | Outside Receiving Waterbody |
| 284 | | | 16 BROOKSIDE DR | Could not find because a fence cut off part of the stream bank | | North Branch Mill River |
| 285 | | GOOD | 8 COLONIAL RD | · | 2018 | Isolated Wetland Springfield Street |
| 286 | | 0002 | 360 MAIN ST | | 2018 | Wetland/Tributary to Nine Mile Pond |
| 287 | | | 9 RUSSELL RD | | 2017 | Outside Receiving Waterbody |
| | | | | | 2017 | |
| 289 | | | 19 WINTERBERRY DR | | | Outside Receiving Waterbody |
| 290 | | | 14 BIRCH ST | | 2017 | Outside Receiving Waterbody |
| 291 | | | 2350 BOSTON RD A | | | Outside Receiving Waterbody |
| 292 | 24 | | 2350 BOSTON RD B | | | Wetland/Tributary to Chicopee River (MA36-24) |
| 293 | | | 2350 BOSTON RD C | | | Outside Receiving Waterbody |
| 294 | 15 | | 269 STONY HILL RD A | | 2018 | Wetland/Tributary to North Branch Mill River |
| 295 | 18 | | 269 STONY HILL RD B | | 2018 | Wetland/Tributary to North Branch Mill River |
| | 10 | | | | | Nine Mile Pond |
| 296 | | | 11 LAKE DR | | 2017 | |
| 297 | | | 7V NORTH HILLS LN | | 2018 | Outside Receiving Waterbody |
| 299 | | | 2048 BOSTON RD | | | Isolated Wetland Boston Street |
| 300 | 20 | FAIR | 3 WARREN RD B | Poor, vegetative growth | 2017 | Outside Receiving Waterbody |
| 301 | | | 84 THREE RIVERS RD | | 2018 | Wetland/Tributary to Chicopee River (MA36-23) |
| 302 | | FAIR | 141 MANCHONIS RD | Clogged with debris | 2017 | Wetland/Tributary to Chicopee River (MA36-24) |
| | | | | 55 | | , , , , , , |

| | | | | | and an education of | | |
|-----------------|--------------------|----------|-----------|----------------------|---------------------|-------------------------|--|
| Town Outfall ID | Pipe Size (inches) | Material | Condition | Location | Notes | Date of Last Inspection | Receiving Water |
| 303 | | | GOOD | 75 POST OFFICE PK | | 2017 | Outside Receiving Waterbody |
| 304 | | | GOOD | 2540V BOSTON RD B | | 2017 | Spectacle Pond |
| 305 | | | | 445V DIPPING HOLE RD | | 2017 | Outside Receiving Waterbody |
| 307 | | | | 18 KENSINGTON DR | | 2018 | Outside Receiving Waterbody |
| 309 | | | | 635 STONY HILL RD | | 2017 | Outside Receiving Waterbody |
| 311 | | | | 717 MAIN ST | | 2018 | Outside Receiving Waterbody |
| 319 | 12 CI | MP | FAIR | 6 HUNTING LN | | 2018 | Wetland/Tributary to North Branch Mill River |
| 320 | | | | 388V THREE RIVERS RD | | | Outside Receiving Waterbody |
| 321 | | | | 42V MAYNARD RD | | | Outside Receiving Waterbody |
| 322 | | | | 10 MAYNARD RD | | 2018 | Chicopee River (MA36-23) |
| 323 | | | | 42V MAYNARD RD | | 20110408 | Outside Receiving Waterbody |
| 328 | | | | 23V RED BRIDGE RD | | 2018 | Outside Receiving Waterbody |
| 329 | | | | 14 HERRICK PL | | 2018 | Outside Receiving Waterbody |

Town of Wilbraham Preliminary Outfall Ranking

| Outfall ID | Initial Ranking | Proximity to Dense | Proximity to Industrial / | Located in 100 Year Floodplain | Vilbraham Prelimir Proximity to Beach / Public Recreational | Proximity to Impaired | Located in Area with Poor Conditions for | Receiving Water |
|---------------|-----------------|-----------------------|------------------------------|-----------------------------------|---|-----------------------|---|---|
| | | Development | Commerical Area | - | Area | Waters | Subsurface Wastewater Disposal | (1125.00) |
| 2 | High Low | | | Yes | | | | Chicopee River (MA36-23) Outside Receiving Waterbody |
| 4 | Low | | | | | | | Wetland/Tributary to Calkins Brook |
| 5 | Low | | | | | V | | Outside Receiving Waterbody |
| <u>6</u> 7 | High Low | | | | | Yes | | Chicopee River (MA36-24) Outside Receiving Waterbody |
| 8 | Low | | | | | | | Outside Receiving Waterbody |
| 9 | Low High | | | Vos | | | | Wetland/Tributary to Calkins Brook Wetland/Tributary to Chicopee River (MA36-23) |
| 11 | High | | | Yes | | | Yes | Outside Receiving Waterbody |
| 19 | High | | | Yes | | | | Wetland/Tributary to Chicopee River (MA36-24) |
| 20 21 | Low Low | | | | | | | Wetland/Tributary to Chicopee River (MA36-24) Wetland/Tributary to Chicopee River (MA36-24) |
| 22 | High | Yes | | Yes | | Yes | | Chicopee River (MA36-24) |
| 25 26 | High High | | Yes Yes | | Yes | Yes | | Outside Receiving Waterbody Outside Receiving Waterbody |
| 27 | High | | Yes | | | | | Outside Receiving Waterbody Outside Receiving Waterbody |
| 28 | High | | | Yes | | | | Wetland/Tributary to Chicopee River (MA36-23) |
| 29 30 | High High | | Yes Yes | Yes Yes | | | | Outside Receiving Waterbody Outside Receiving Waterbody |
| 31 | High | | Yes | Yes | | | | Chicopee River (MA36-23) |
| 32 | High | | Yes | Yes | | | Yes | Chicopee River (MA36-23) |
| 33 34 | High High | | Yes Yes | Yes Yes | | | | Chicopee River (MA36-23) Chicopee River (MA36-23) |
| 35 | High | | Yes | Yes | | | | Chicopee River (MA36-23) |
| 36 37 | High Low | | Yes | Yes | | | | Chicopee River (MA36-23) Wetland/Tributary to Nine Mile Pond |
| 38 | Low | | | | | | | Isolated Wetland Dipping Hole Road |
| 39 | Low | | | | | | | Outside Receiving Waterbody |
| 40 | Low | | | | | | | Outside Receiving Waterbody Outside Receiving Waterbody |
| 42 | Low | | | | | | | Outside Receiving Waterbody |
| 43 44 | Low | | | | | | | Isolated Wetland Dipping Hole Road |
| 45 | Low | | | | | | | Outside Receiving Waterbody Wetland/Tributary to Nine Mile Pond |
| 46 | Low | | | | | | | Wetland/Tributary to Nine Mile Pond |
| 47 48 | Low High | | | | | | Yes | Wetland/Tributary to Nine Mile Pond Outside Receiving Waterbody |
| 49 | Low | | | | | | 163 | Isolated Wetland Dipping Hole Road |
| 50 | Low | | | | | | | Wetland/Tributary to North Branch Mill River |
| 51 52 | Low | | | | | | | Wetland/Tributary to North Branch Mill River Outside Receiving Waterbody |
| 53 | High | | | | | | Yes | Wetland/Tributary to Bennett Pond |
| 54 55 | Low | | | | | | | Outside Receiving Waterbody Wetland/Tributary to South Branch Mill River |
| 57 | Low | | | | | | | Wetland/Tributary to South Branch Mill River |
| 58 | Low | | | | | | | Wetland/Tributary to South Branch Mill River |
| 59 60 | High Low | | | Yes | | | | North Branch Mill River Wetland/Tributary to Bennett Pond |
| 61 | Low | | | | | | | Wetland/Tributary to Bennett Pond |
| 63 64 | Low | | | | | | | Outside Receiving Waterbody Wetland/Tributary to South Branch Mill River |
| 65 | Low | | | | | | | Outside Receiving Waterbody |
| 66 | Low | | | Vaa | | | | Wetland/Tributary to Bennett Pond |
| 67 68 | High Low | | | Yes | | | | Wetland/Tributary to Bennett Pond Wetland/Tributary to Bennett Pond |
| 69 | High | | | Yes | | | | Wetland/Tributary to North Branch Mill River |
| 70 71 | High Low | | | Yes | | | | Wetland/Tributary to North Branch Mill River Wetland/Tributary to Bennett Pond |
| 72 | Low | | | | | | | Wetland/Tributary to South Branch Mill River |
| 73 | Low | | | | | | | Wetland/Tributary to South Branch Mill River |
| 74 75 | Low High | | | Yes | | | | Wetland/Tributary to South Branch Mill River Wetland/Tributary to South Branch Mill River |
| 76 | Low | | | | | | | Wetland/Tributary to South Branch Mill River |
| 77 78 | Low High | | | Yes | | | | Outside Receiving Waterbody South Branch Mill River |
| 79 | High | | | Yes | | | | South Branch Mill River |
| 82 85 | Low | | | | | | | Outside Receiving Waterbody Outside Receiving Waterbody |
| 86 | Low | | | | | | | Outside Receiving Waterbody Outside Receiving Waterbody |
| 87 | Low | | | | | | | Outside Receiving Waterbody |
| 88 89 | Low | | | | | | | Outside Receiving Waterbody Outside Receiving Waterbody |
| 90 | Low | | | | | | | Wetland/Tributary to Bennett Pond |
| 92 | Low | | | | | | | Wetland/Tributary to South Branch Mill River |
| 93 94 | Low Low | | | | | | | Outside Receiving Waterbody Wetland/Tributary to Bennett Pond |
| 95 | Low | | | | | | | Outside Receiving Waterbody |
| 96 97 | Low Low | | | | | | | Wetland/Tributary to Bennett Pond Outside Receiving Waterbody |
| 99 | Low | | | | | | | Wetland/Tributary to Bennett Pond |
| 100 | Low | | | | | | | Wetland/Tributary to Bennett Pond |
| 101 102 | Low High | | | Yes | | | | Outside Receiving Waterbody Wetland/Tributary to Bennett Pond |
| 103 | Low | | | 163 | | | | Outside Receiving Waterbody |
| 104 | Low | | | | | | | Wetland/Tributary to Bennett Pond |
| 105 106 | Low Low | | | | | | | Wetland/Tributary to Bennett Pond Outside Receiving Waterbody |
| 107 | Low | | | | | | | Wetland/Tributary to North Branch Mill River |
| 108 109 | Low | | | | | | | Wetland/Tributary to North Branch Mill River Outside Receiving Waterbody |
| 110 | Low | | | | | | | Wetland/Tributary to North Branch Mill River |
| | | | | | | | | |

| | | | | Town of V | Vilbraham Prelimin | ary Outfall Ranki | ng | |
|------------|-----------------|--------------------------------------|--|-----------------------------------|--|------------------------------------|---|---|
| Outfall ID | Initial Ranking | Proximity to Dense Development | Proximity to Industrial / Commerical | Located in 100 Year Floodplain | Proximity to Beach / Public Recreational | Proximity to Impaired Waters | Located in Area with Poor Conditions for Subsurface | Receiving Water |
| 111 | High | 2 croiopinione | Area | Yes | Area | | Wastewater Disposal | North Branch Mill River |
| 112 | High | | | Yes | | | | North Branch Mill River |
| 113 | High | | | Yes | | | | North Branch Mill River |
| 114 | Low | | | 100 | | | | Outside Receiving Waterbody |
| 115 | Low | | | | | | | Outside Receiving Waterbody |
| 116 | Low | | | | | | | Wetland/Tributary to North Branch Mill River |
| 117 | Low | | | | | | | Outside Receiving Waterbody |
| 118 | Low | | | | | | | Outside Receiving Waterbody |
| 119 | Low | | | | | | | Outside Receiving Waterbody |
| 120 | High | | | | | | Yes | Outside Receiving Waterbody |
| 121 122 | High High | | | | | | Yes Yes | Outside Receiving Waterbody Outside Receiving Waterbody |
| 123 | Low | | | | | | 163 | Outside Receiving Waterbody Outside Receiving Waterbody |
| 124 | Low | | | | | | | Outside Receiving Waterbody |
| 125 | Low | | | | | | | Outside Receiving Waterbody |
| 126 | Low | | | | | | | Outside Receiving Waterbody |
| 127 | Low | | | | | | | Outside Receiving Waterbody |
| 128 | High | Yes | | Yes | | Yes | Yes | Chicopee River (MA36-24) |
| 129 | High | Yes | | | | Yes | | Outside Receiving Waterbody |
| 130 | High | Yes | | Yes | | Yes | Yes | Chicopee River (MA36-24) |
| 131 | High High | Yes | | Yes | | Yes | Yes | Chicopee River (MA36-24) Chicopee River (MA36-24) |
| 133 | High | Yes Yes | | Yes Yes | | Yes Yes | Yes | Chicopee River (MA36-24) Chicopee River (MA36-24) |
| 134 | Low | 163 | | 165 | | 103 | | Outside Receiving Waterbody |
| 135 | Low | | | | | | | Outside Receiving Waterbody |
| 137 | Low | | | | | | | Outside Receiving Waterbody |
| 139 | Low | | | | | | | Outside Receiving Waterbody |
| 140 | High | | Yes | | | | | Outside Receiving Waterbody |
| 141 | High | | Yes | | | | | Outside Receiving Waterbody |
| 142 143 | High Low | | Yes | | | | | Outside Receiving Waterbody Outside Receiving Waterbody |
| 143 | Low | | | | | | | Outside Receiving Waterbody Outside Receiving Waterbody |
| 145 | Low | | | | | | | Wetland/Tributary to South Branch Mill River |
| 146 | Low | | | | | | | Wetland/Tributary to South Branch Mill River |
| 147 | High | | | Yes | | | | South Branch Mill River |
| 148 | Low | | | | | | | Wetland/Tributary to Bennett Pond |
| 149 | Low | | | | | | | Outside Receiving Waterbody |
| 156 | Low | | | | | | | Outside Receiving Waterbody |
| 157 | Low | | | | | | | Outside Receiving Waterbody |
| 158 | Low | | | | | | | Outside Receiving Waterbody |
| 159 160 | Low Low | | | | | | | Outside Receiving Waterbody Wetland/Tributary to South Branch Mill River |
| 161 | High | | | | | | Yes | Outside Receiving Waterbody |
| 162 | High | | | Yes | | | | Wetland/Tributary to Chicopee River (MA36-23) |
| 163 | Low | | | | | | | Outside Receiving Waterbody |
| 164 | High | | | | | | Yes | Outside Receiving Waterbody |
| 165 | High | | | | | | Yes | Outside Receiving Waterbody |
| 166 | Low | | | | | | | Outside Receiving Waterbody |
| 167 168 | Low Low | | | | | | | Outside Receiving Waterbody Outside Receiving Waterbody |
| 169 | High | | Yes | | | | | Outside Receiving Waterbody Outside Receiving Waterbody |
| 174 | High | | 1.00 | | | | Yes | Outside Receiving Waterbody |
| 175 | High | | | Yes | | | | Outside Receiving Waterbody |
| 176 | Low | | | | | | | Outside Receiving Waterbody |
| 177 | Low | | | | | | | Outside Receiving Waterbody |
| 178 | Low | | | | | | | Outside Receiving Waterbody Wetland/Tributary to Chicopee River (MA36-23) |
| 179 180 | Low High | | | Yes | | | | Chicopee River (MA36-23) |
| 181 | High | | | Yes | | | | Outside Receiving Waterbody |
| 194 | High | | | | | | Yes | Outside Receiving Waterbody Outside Receiving Waterbody |
| 197 | Low | | | | | | | Outside Receiving Waterbody |
| 201 | Low | | | | | | | Wetland/Tributary to South Branch Mill River |
| 202 | Low | | | | | | | Wetland/Tributary to South Branch Mill River |
| 204 | Low | | | Voc | | | | Outside Receiving Waterbody Wetland/Tributary to North Branch Mill River |
| 205 206 | High High | | | Yes Yes | | | | Wetland/Tributary to North Branch Mill River Wetland/Tributary to North Branch Mill River |
| 207 | High | | | Yes | | | | Wetland/Tributary to North Branch Mill River |
| 208 | Low | | | | | | | Wetland/Tributary to North Branch Mill River |
| 209 | High | | | Yes | | | | Wetland/Tributary to North Branch Mill River |
| 210 | High | | | Yes | | | | Wetland/Tributary to North Branch Mill River |
| 211 | High | | | Yes | | | | Wetland/Tributary to North Branch Mill River |
| 212 | Low | | | | | | | Outside Receiving Waterbody |
| 213 214 | Low | | | | | | | Wetland/Tributary to Bennett Pond |
| 214 | Low Low | | | | | | | Outside Receiving Waterbody Wetland/Tributary to Bennett Pond |
| 217 | Low | | | | | | | Outside Receiving Waterbody |
| 218 | Low | | | | | | | Outside Receiving Waterbody |
| 220 | High | | | | | | Yes | Wetland/Tributary to Bennett Pond |
| 221 | Low | | | | | | | Wetland/Tributary to Bennett Pond |
| 222 | High | | | Yes | | | | Wetland/Tributary to Bennett Pond |
| 223 | Low | | | V | | | | Wetland/Tributary to South Branch Mill River |
| 224 | High | | | Yes | | | | Wetland/Tributary to South Branch Mill River |
| 225 | Low Low | | | | | | | Outside Receiving Waterbody Outside Receiving Waterbody |
| 227 | Low | | | | | | | Outside Receiving Waterbody Outside Receiving Waterbody |
| 228 | Low | | | | | | | Outside Receiving Waterbody Outside Receiving Waterbody |
| 229 | Low | | | | | | | Wetland/Tributary to Bennett Pond |
| 230 | High | | | | | | Yes | Outside Receiving Waterbody |
| 231 | High | | | Yes | | | | North Branch Mill River |
| 232 | Low | | | | | | | Outside Receiving Waterbody |
| 233 | High | | | | | | Yes | Outside Receiving Waterbody |
| 234 | Low | | | | | | | Outside Receiving Waterbody |

Town of Wilbraham Preliminary Outfall Ranking


| Outfall ID | Initial Ranking | Proximity to Dense | Proximity to Industrial / Commerical | Located in 100 Year Floodplain | Proximity to Beach / Public Recreational | Proximity to Impaired Waters | Located in Area with Poor Conditions for Subsurface | Receiving Water |
|------------|-----------------|-----------------------|--|-----------------------------------|--|------------------------------------|---|--|
| | | Development | Area | • | Area | waters | Wastewater Disposal | |
| 235 | Low | | | | | | | Isolated Wetland Wilbraham & Monson Academy |
| 236 | Low | | | | | | | Cedar Swamp |
| 237 | Low | | | | | | | Cedar Swamp |
| 238 | Low | | | | | | | Cedar Swamp |
| 239 240 | Low | | | | | | | Cedar Swamp |
| 240 | High | | | | | | Yes | Cedar Swamp |
| 241 | Low | | | | | | res | Outside Receiving Waterbody Outside Receiving Waterbody |
| 252 | Low | | | | | | | Wetland/Tributary to Nine Mile Pond |
| 253 | Low | | | | | | | Outside Receiving Waterbody |
| 257 | Low | | | | | | | Outside Receiving Waterbody Outside Receiving Waterbody |
| 260 | Low | | | | | | | Wetland/Tributary to Spear Brook |
| 265 | Low | | | | | | | Wetland/Tributary to Chicopee River (MA36-23) |
| 266 | High | | | Yes | | | | Wetland/Tributary to Chicopee River (MA36-22) |
| 267 | Low | | | 165 | | | | Wetland/Tributary to Bennett Pond |
| 268 | Low | | | | | | | Outside Receiving Waterbody |
| 269 | Low | | | | | | | Wetland/Tributary to Bennett Pond |
| 271 | High | | | | | | Yes | Wetland/Tributary to Bennett Pond |
| 274 | Low | | | | | | 1.65 | Cedar Swamp |
| 275 | Low | | | | | | | Outside Receiving Waterbody |
| 277 | High | | | | | | Yes | Outside Receiving Waterbody Outside Receiving Waterbody |
| 278 | High | | | | | | Yes | Outside Receiving Waterbody Outside Receiving Waterbody |
| 279 | High | | | Yes | | | 163 | North Branch Mill River |
| 280 | Low | | | 165 | | | | Outside Receiving Waterbody |
| 281 | Low | | | | | | | Outside Receiving Waterbody |
| 282 | Low | | | | | | | Outside Receiving Waterbody Outside Receiving Waterbody |
| 283 | Low | | | | | | | Outside Receiving Waterbody Outside Receiving Waterbody |
| 284 | High | | | Yes | | | | North Branch Mill River |
| 285 | Low | | | 165 | | | | Isolated Wetland Springfield Street |
| 286 | Low | | | | | | | Wetland/Tributary to Nine Mile Pond |
| 287 | Low | | | | | | | Outside Receiving Waterbody |
| 289 | Low | | | | | | | Outside Receiving Waterbody |
| 290 | Low | | | | | | | Outside Receiving Waterbody |
| 291 | High | | Yes | | | | | Outside Receiving Waterbody |
| 292 | High | | Yes | | | | | Wetland/Tributary to Chicopee River (MA36-24) |
| 293 | Low | | | | | | | Outside Receiving Waterbody |
| 294 | Low | | | | | | | Wetland/Tributary to North Branch Mill River |
| 295 | Low | | | | | | | Wetland/Tributary to North Branch Mill River |
| 296 | High | | | Yes | Yes | | | Nine Mile Pond |
| 297 | High | | Yes | | | | | Outside Receiving Waterbody |
| 299 | High | | Yes | | | | | Isolated Wetland Boston Street |
| 300 | Low | | | | | | | Outside Receiving Waterbody |
| 301 | Low | | | | | | | Wetland/Tributary to Chicopee River (MA36-23) |
| 302 | Low | | | | | | | Wetland/Tributary to Chicopee River (MA36-24) |
| 303 | Low | | | | | | | Outside Receiving Waterbody |
| 304 | High | | | | Yes | Yes | | Spectacle Pond |
| 305 | Low | | | | | | | Outside Receiving Waterbody |
| 307 | Low | | | | | | | Outside Receiving Waterbody |
| 309 | Low | | | | | | | Outside Receiving Waterbody |
| 311 | Low | | | | | | | Outside Receiving Waterbody |
| 319 | High | | | Yes | | | | Wetland/Tributary to North Branch Mill River |
| 320 | Low | | | | | | | Outside Receiving Waterbody |
| 321 | High | | | Yes | | | | Outside Receiving Waterbody |
| 322 | High | | | Yes | | | | Chicopee River (MA36-23) |
| 323 | High | | | Yes | | | | Outside Receiving Waterbody |
| 328 | Low | | | | | | | Outside Receiving Waterbody |
| 329 | Low | | | | | | | Outside Receiving Waterbody |

| | 100 | | Preliminary Catchment Ranking |
|--------------|----------|----------------------------------|--|
| Catchment ID | Town ID | Preliminary Catchment Rank | Receiving Waterbody |
| 1 | 1 | High | Chicopee River (MA36-23) |
| 2 | 2 | Low | Outside Receiving Waterbody |
| 4 | 4 | Low | Wetland/Tributary to Calkins Brook |
| 5 | 5 | Low | Outside Receiving Waterbody |
| 6 | 6 | High | Chicopee River (MA36-24) |
| 7 | 7 | Low | Outside Receiving Waterbody |
| 8 | 8 | Low | Outside Receiving Waterbody |
| 9 | 9 | Low | Wetland/Tributary to Calkins Brook |
| 11 | 11 | High | Outside Receiving Waterbody |
| 19 20 | 19 | High | Wetland/Tributary to Chicopee River (MA36-24) |
| 21 | 20 21 | Low | Wetland/Tributary to Chicopee River (MA36-24) |
| 22 | 22 | Low | Wetland/Tributary to Chicopee River (MA36-24) |
| 25 | 25 | High | Chicopee River (MA36-24) |
| 26 | 26 | High | Outside Receiving Waterbody |
| 27 | 27 | High | Outside Receiving Waterbody Outside Receiving Waterbody |
| 28 | 28 | High | |
| 36 | 36 | High High | Wetland/Tributary to Chicopee River (MA36-23) |
| 37 | 37 | High Low | Chicopee River (MA36-23) Westland / Tributary to Nine Mile Bond |
| 38 | 38 | Low | Wetland/Tributary to Nine Mile Pond Isolated Wetland Dipping Hole Road |
| 39 | 39 | Low Low | Outside Receiving Waterbody |
| 40 | 40 | _ | Outside Receiving Waterbody Outside Receiving Waterbody |
| 41 | 41 | Low Low | Outside Receiving Waterbody Outside Receiving Waterbody |
| 42 | 42 | Low | Outside Receiving Waterbody Outside Receiving Waterbody |
| 43 | 43 | Low | Isolated Wetland Dipping Hole Road |
| 44 | 44 | Low | Outside Receiving Waterbody |
| 46 | 46 | Low | Wetland/Tributary to Nine Mile Pond |
| 48 | 48 | High | Outside Receiving Waterbody |
| 49 | 49 | Low | Isolated Wetland Dipping Hole Road |
| 50 | 50 | Low | Wetland/Tributary to North Branch Mill River |
| 51 | 51 | Low | Wetland/Tributary to North Branch Mill River |
| 52 | 52 | Low | Outside Receiving Waterbody |
| 53 | 53 | High | Wetland/Tributary to Bennett Pond |
| 54 | 54 | Low | Outside Receiving Waterbody |
| 55 | 55 | Low | Wetland/Tributary to South Branch Mill River |
| 57 | 57 | Low | Wetland/Tributary to South Branch Mill River |
| 58 | 58 | Low | Wetland/Tributary to South Branch Mill River |
| 59 | 59 | High | North Branch Mill River |
| 60 | 60 | Low | Wetland/Tributary to Bennett Pond |
| 61 | 61 | Low | Wetland/Tributary to Bennett Pond |
| 63 | 63 | Low | Outside Receiving Waterbody |
| 64 | 64 | Low | Wetland/Tributary to South Branch Mill River |
| 65 | 65 | Low | Outside Receiving Waterbody |
| 66 | 66 | Low | Wetland/Tributary to Bennett Pond |
| 67 | 67 | High | Wetland/Tributary to Bennett Pond |
| 68 | 68 | Low | Wetland/Tributary to Bennett Pond |
| 69 | 69 | High | Wetland/Tributary to North Branch Mill River |
| 70 | 70 | High | Wetland/Tributary to North Branch Mill River |
| 71 | 71 | Low | Wetland/Tributary to Bennett Pond |
| 72 | 72 | Low | Wetland/Tributary to South Branch Mill River |
| 73 | 73 | Low | Wetland/Tributary to South Branch Mill River |
| 74 | 74 | Low | Wetland/Tributary to South Branch Mill River |
| 75 | 75 | High | Wetland/Tributary to South Branch Mill River |
| 76 | 76 | Low | Wetland/Tributary to South Branch Mill River |
| 77 | 77 | Low | Outside Receiving Waterbody |
| 78 | 78 | High | South Branch Mill River |
| 79 | 79 | High | South Branch Mill River |
| 82 | 82 | Low | Outside Receiving Waterbody |

| | IOW | | Preliminary Catchment Ranking |
|--------------|---------|----------------------------------|---|
| Catchment ID | Town ID | Preliminary Catchment Rank | Receiving Waterbody |
| 85 | 85 | Low | Outside Receiving Waterbody |
| 86 | 86 | Low | Outside Receiving Waterbody |
| 87 | 87 | Low | Outside Receiving Waterbody |
| 88 | 88 | Low | Outside Receiving Waterbody |
| 89 | 89 | Low | Outside Receiving Waterbody |
| 90 | 90 | Low | Wetland/Tributary to Bennett Pond |
| 92 | 92 | Low | Wetland/Tributary to South Branch Mill River |
| 93 | 93 | Low | Outside Receiving Waterbody |
| 94 | 94 | Low | Wetland/Tributary to Bennett Pond |
| 95 | 95 | Low | Outside Receiving Waterbody |
| 97 | 97 | Low | Outside Receiving Waterbody |
| 99 | 99 | Low | Wetland/Tributary to Bennett Pond |
| 100 | 100 | Low | Wetland/Tributary to Bennett Pond |
| 102 | 102 | High | Wetland/Tributary to Bennett Pond |
| 103 | 103 | Low | Outside Receiving Waterbody |
| 104 | 104 | Low | Wetland/Tributary to Bennett Pond |
| 105 | 105 | Low | Wetland/Tributary to Bennett Pond |
| 106 | 106 | Low | Outside Receiving Waterbody |
| 108 | 108 | Low | Wetland/Tributary to North Branch Mill River |
| 109 | 109 | Low | Outside Receiving Waterbody |
| 110 | 110 | Low | Wetland/Tributary to North Branch Mill River |
| 111 | 111 | High | North Branch Mill River |
| 112 | 112 | High | North Branch Mill River |
| 113 | 113 | High | North Branch Mill River |
| 114 | 114 | Low | Outside Receiving Waterbody |
| 115 | 115 | Low | Outside Receiving Waterbody |
| 116 | 116 | Low | Wetland/Tributary to North Branch Mill River |
| 119 | 119 | Low | Outside Receiving Waterbody |
| 121 | 121 | High | Outside Receiving Waterbody |
| 124 | 124 | Low | Outside Receiving Waterbody |
| 125 | 125 | Low | Outside Receiving Waterbody |
| 126 | 126 | Low | Outside Receiving Waterbody |
| 127 | 127 | Low | Outside Receiving Waterbody |
| 128 | 128 | High | Chicopee River (MA36-24) |
| 129 | 129 | High | Outside Receiving Waterbody |
| 130 | 130 | High | Chicopee River (MA36-24) |
| 131 | 131 | High | Chicopee River (MA36-24) |
| 132 | 132 | High | Chicopee River (MA36-24) |
| 133 | 133 | High | Chicopee River (MA36-24) |
| 134 | 134 | Low | Outside Receiving Waterbody |
| 137 | 137 | Low | Outside Receiving Waterbody |
| 139 | 139 | Low | Outside Receiving Waterbody |
| 140 | 140 | High | Outside Receiving Waterbody |
| 142 | 142 | High | Outside Receiving Waterbody |
| 143 | 143 | Low | Outside Receiving Waterbody |
| 145 | 145 | Low | Wetland/Tributary to South Branch Mill River |
| 147 | 147 | High | South Branch Mill River |
| 148 | 148 | Low | Wetland/Tributary to Bennett Pond |
| 149 | 149 | Low | Outside Receiving Waterbody |
| 156 | 156 | Low | Outside Receiving Waterbody |
| 158 | 158 | Low | Outside Receiving Waterbody |
| 160 | 160 | Low | Wetland/Tributary to South Branch Mill River |
| 161 | 161 | High | Outside Receiving Waterbody |
| 162 | 162 | High | Wetland/Tributary to Chicopee River (MA36-23) |
| 163 | 163 | | Outside Receiving Waterbody |
| 164 | 164 | Low | 5 ' |
| 165 | 165 | High High | Outside Receiving Waterbody |
| 166 | 166 | High Low | Outside Receiving Waterbody |
| 100 | 100 | Low | Outside Receiving Waterbody |

| | | | Preliminary Catchment Ranking | | |
|--------------|---------|----------------------------------|---|--|--|
| Catchment ID | Town ID | Preliminary Catchment Rank | Receiving Waterbody | | |
| 167 | 167 | Low | Outside Receiving Waterbody | | |
| 168 | 168 | Low | Outside Receiving Waterbody | | |
| 169 | 169 | High | Outside Receiving Waterbody | | |
| 174 | 174 | High | Outside Receiving Waterbody | | |
| 175 | 175 | High | Outside Receiving Waterbody | | |
| 176 | 176 | Low | Outside Receiving Waterbody | | |
| 177 | 177 | Low | Outside Receiving Waterbody | | |
| 178 | 178 | Low | Outside Receiving Waterbody | | |
| 179 | 179 | Low | Wetland/Tributary to Chicopee River (MA36-23) | | |
| 180 | 180 | High | Chicopee River (MA36-23) | | |
| 181 | 181 | High | Outside Receiving Waterbody | | |
| 194 | 194 | High | Outside Receiving Waterbody | | |
| 197 | 197 | Low | Outside Receiving Waterbody | | |
| 201 | 201 | Low | Wetland/Tributary to South Branch Mill River | | |
| 202 | 202 | Low | Wetland/Tributary to South Branch Mill River | | |
| 205 | 205 | High | Wetland/Tributary to North Branch Mill River | | |
| 206 | 206 | High | Wetland/Tributary to North Branch Mill River | | |
| 208 | 208 | Low | Wetland/Tributary to North Branch Mill River | | |
| 209 | 209 | High | Wetland/Tributary to North Branch Mill River | | |
| 210 | 210 | High | Wetland/Tributary to North Branch Mill River | | |
| 211 | 211 | High | Wetland/Tributary to North Branch Mill River | | |
| 212 | 212 | Low | Outside Receiving Waterbody | | |
| 214 | 214 | Low | Outside Receiving Waterbody | | |
| 217 | 217 | Low | Outside Receiving Waterbody | | |
| 218 | 218 | Low | Outside Receiving Waterbody | | |
| 220 | 220 | High | Wetland/Tributary to Bennett Pond | | |
| 221 | 221 | Low | Wetland/Tributary to Bennett Pond | | |
| 222 | 222 | High | Wetland/Tributary to Bennett Pond | | |
| 223 | 223 | Low | Wetland/Tributary to South Branch Mill River | | |
| 224 | 224 | High | Wetland/Tributary to South Branch Mill River | | |
| 228 | 228 | Low | Outside Receiving Waterbody | | |
| 230 | 230 | High | Outside Receiving Waterbody | | |
| 232 | 232 | Low | Outside Receiving Waterbody | | |
| 234 | 234 | Low | Outside Receiving Waterbody | | |
| 236 | 236 | Low | Cedar Swamp | | |
| 237 | 237 | Low | Cedar Swamp | | |
| 238 | 238 | Low | Cedar Swamp | | |
| 239 | 239 | Low | Cedar Swamp | | |
| 240 | 240 | Low | Cedar Swamp | | |
| 241 | 241 | High | Outside Receiving Waterbody | | |
| 247 | 247 | Low | Outside Receiving Waterbody | | |
| 252 | 252 | Low | Wetland/Tributary to Nine Mile Pond | | |
| 253 | 253 | Low | Outside Receiving Waterbody | | |
| 257 | 257 | Low | Outside Receiving Waterbody | | |
| 260 | 260 | Low | Wetland/Tributary to Spear Brook | | |
| 265 | 265 | Low | Wetland/Tributary to Chicopee River (MA36-23) | | |
| 266 | 266 | High | Wetland/Tributary to Chicopee River (MA36-22) | | |
| 267 | 267 | Low | Wetland/Tributary to Bennett Pond | | |
| 268 | 268 | Low | Outside Receiving Waterbody | | |
| 271 | 271 | High | Wetland/Tributary to Bennett Pond | | |
| 274 | 274 | Low | Cedar Swamp | | |
| 277 | 277 | High | Outside Receiving Waterbody | | |
| 278 | 278 | High | Outside Receiving Waterbody | | |
| 279 | 279 | High | North Branch Mill River | | |
| 280 | 280 | Low | Outside Receiving Waterbody | | |
| 283 | 283 | Low | Outside Receiving Waterbody | | |
| 284 | 284 | High | North Branch Mill River | | |
| 285 | 285 | Low | Isolated Wetland Springfield Street | | |
| | • | • | | | |

| Catchment ID | Town ID | Preliminary Catchment Rank | Receiving Waterbody |
|--------------|---------|----------------------------------|--|
| 286 | 286 | Low | Wetland/Tributary to Nine Mile Pond |
| 287 | 287 | Low | Outside Receiving Waterbody |
| 291 | 291 | High | Outside Receiving Waterbody Outside Receiving Waterbody |
| 292 | 292 | High | Wetland/Tributary to Chicopee River (MA36-24) |
| 294 | 294 | Low | Wetland/Tributary to North Branch Mill River |
| 295 | 295 | Low | Wetland/Tributary to North Branch Mill River |
| 296 | 296 | High | Nine Mile Pond |
| 297 | 297 | High | Outside Receiving Waterbody |
| 299 | 299 | High | Isolated Wetland Boston Street |
| 300 | 300 | Low | Outside Receiving Waterbody |
| 301 | 301 | Low | Wetland/Tributary to Chicopee River (MA36-23) |
| 303 | 303 | Low | Outside Receiving Waterbody |
| 305 | 305 | Low | Outside Receiving Waterbody |
| 307 | 307 | Low | Outside Receiving Waterbody |
| 311 | 311 | Low | Outside Receiving Waterbody |
| 319 | 319 | High | Wetland/Tributary to North Branch Mill River |
| 320 | 320 | Low | Outside Receiving Waterbody |
| 321 | 321 | High | Outside Receiving Waterbody |
| 328 | 328 | Low | Outside Receiving Waterbody |
| 329 | 329 | Low | Outside Receiving Waterbody |



Town of Wilbraham IDDE Program Appendix E Protocol for IDDE Program Responsibilities



This document establishes a written protocol that clearly identifies responsibilities with regard to eliminating illicit discharges, including:

- 1. Identification of a suspected illicit discharge to Wilbraham's MS4
- 1. Contact information to report suspected illicit discharges
- 2. Responsibility for elimination of identified illicit discharges
- 3. Standard operating procedures for enforcement
- 4. Appropriate methods for elimination of the illicit connection or identified problem
- 5. Process for documentation and verification of illicit connection or discharge removal

1. IDENTIFICATION OF A SUSPECTED ILLICIT DISCHARGE TO THE MS4

There are a variety of ways that an illicit discharge to Wilbraham's MS4 might be discovered and reported to the Town.

- Residents and Businesses of Wilbraham. Through the Town's public education and outreach efforts, residents and businesses of Wilbraham are becoming more aware that the municipal storm drain is different than the sanitary sewer and it drains directly into Wilbraham's waterbodies. The public may report illicit connections or illegal dumping by email or by phone to the Fire Department, DPW, Board of Selectmen (the local Public Health Authority) or Conservation Commission.
- Maintenance Field Crews. Both municipal staff and contractors that conduct Wilbraham's drainage and roadway operation and maintenance activities are some of the observers available to the Town to detect illicit discharges and illegal dumping activities.
- **Inspectors.** Both municipal staff and private inspectors may conduct inspections of construction sites, buildings, and other operations and maintenance on public or private properties and detect illicit discharges and illegal dumping activities.
- Personnel Conducting Outfall and Stream Monitoring. Through the Town's outfall monitoring program as well as in-stream monitoring conducted by the Town, pollutant concentrations may indicate the presence of an illicit discharge. In this case, a follow up investigation may be necessary to identify the source of the contamination.

As part of public education and outreach and employee training programs, people involved in these activities should be encouraged to report any signs of illegal dumping or a suspected illicit discharge. It is important that the information observed in the field is communicated to the appropriate staff for follow up and outreach.

2. CONTACT INFORMATION TO REPORT SUSPECTED ILLICIT DISCHARGES

The following contact information should be advertised on any educational materials regarding illicit discharges and illegal dumping, as well as on the Town website.

- For Imminent Emergency Situations where there is an immediate risk to public health and safety: Call 911.
- For **Urgent Situations**, where public health, safety, and/or the environment are at risk and there are possibly hazardous chemicals, call the Fire Department's non-emergency line at **413-596-3122**.



- For **Non-Emergency Situations**, call the Department of Public Works (DPW) at **413-596-2800 extension 208**.
- When in doubt, call 911.

3. RESPONSIBILITY FOR ELIMINATION OF IDENTIFIED ILLICIT DISCHARGES

This section defines the actions to take when an illicit discharge is identified and parties responsible for eliminating reported illicit discharges under three scenarios.

Imminent Emergency Situations

Take **immediate action** in the event of encountering one of the following situations:

- Individuals actively in the process of introducing possible illegal substances or materials into the MS4
- Presence of fumes or smoke emanating from the MS4
- Visible significant stream of a controlled chemical or petroleum product flowing in the storm drain system or in downstream waters
- Large chemical plume in stream or river downstream of a Town outfall
- Any condition that poses or could pose an immediate threat to property, human health or safety, or aquatic life

If one of the above situations is encountered, take the following steps:

- 1. Ensure the safety of municipal employees and/or the public by instructing people to stay away from the area.
- 2. Call 911 to report active illegal dumping, a potential fire, or a significant chemical incident that has the potential to be hazardous to public health or the environment. 911 will receive the call and dispatch the Fire Department and/or Police Department. Fire and Police may coordinate with other Town Departments and Boards as necessary, such as the DPW, Planning Board, or Conservation Commission.
- 3. Be prepared to provide the following information to the Fire Department or other Emergency Responders:
 - Where is the emergency or spill?
 - What is the emergency or what spilled?
 - How much spilled?
 - Who spilled the material?
 - Is anyone cleaning up the material?
 - Are there resource damages (such as dead fish or oily birds)?
 - Who is reporting the emergency and/or spill?
 - Your contact information
- 4. Take detailed notes and photos for subsequent investigation by the Town or other agencies.

911 will receive the call and dispatch the Fire and/or Police Department. Fire and Police may coordinate with other Town Departments and Boards such as the DPW, Planning Board, or Conservation Commission, as necessary.



Urgent Situations

Take **immediate action** in the event of encountering one of the following situations:

- Very strong chemical odor emanating from the MS4
- Suspicion of hazardous chemicals in the MS4
- · Public health and safety or the environment may be urgently at risk

If one of the above situations is encountered, take the following steps:

- 1. Notify your Foreman or call the Wilbraham Fire Department's non-emergency line: 413-596-3122.
- 2. Be prepared tell the Fire Department or other Emergency Responders what the situation is, where the illicit discharge is, and any other relevant information. Take notes and photographs for subsequent investigation by the Town or other agencies.


The Foreman will call the Fire Department's non-emergency line (413-596-3122), and may coordinate as necessary with other applicable Boards and Departments.

The Fire Department will respond to the situation and follow its Emergency Response Procedures and its Spill Response Procedures, including providing spill resources (i.e., booms, pads, storm drain covers, etc.) as needed. The Fire Department may coordinate as necessary with other Town Boards and Departments. Records of illicit discharges should be forwarded to the DPW.

Non-Emergency Situations

If a non-emergency situation is encountered, notify your Foreman or call the DPW (413-596-2800 ext. 208). The Foreman will report the situation to the DPW, if not already notified, and may coordinate with other applicable Town Departments and Boards as needed, such as the Planning Board, Conservation Commission, or Board of Health.

Once the report is received, Town staff may follow the Flow Chart for Non-Emergency Corrective Actions presented below.





4. STANDARD OPERATING PROCEDURES FOR ENFORCEMENT

The following Standard Operating Procedure (SOP) has been developed from requirements of Section 634 of the General By-Laws of the Town of Wilbraham, Part II (*Stormwater Phase II Comprehensive By-Law, Illicit Discharges to the Municipal Storm Drain System*).

When the DPW is notified of or discovers an illicit discharge, illicit connection, or obstruction of the municipal drain system, as listed as Prohibited Activities in Section C.3. of the By-Law, that are not explicitly exempt under Section D.1., it should use the following SOP to conduct enforcement action with adjustments as appropriate for the specific circumstances of each enforcement action. For simplicity, this SOP assumes that the property owner is the violator; make the necessary adjustments if they are different people or entities.

- 1. Start a file (hard copy or electronic) in which all relevant information regarding the enforcement action will be maintained. Log all communications with the property owner.
- 2. Compile existing information regarding the violation, such as:
 - Location and apparent source of the discharge
 - Description of the discharge
 - Date and method of discovery
 - Observations made by Town staff or contractors (when, where, and by whom)
 - Property address and owner
 - Log of physical evidence (e.g., photos, samples)
- 3. Contact the property owner in person or by telephone to discuss the situation and attempt to get voluntary compliance. If the property owner agrees to fix the situation, follow up with a letter memorializing the conversation and noting that failure to address the violation will result in enforcement action.
- 4. If the property owner cannot be contacted or if voluntary compliance is not obtained, send a "Notice of Violation and Order for Correction" letter detailing the apparent violation and asking the property owner to contact the DPW to discuss addressing the violation.
 - The order shall include the name and address of the alleged violator, the address at which the violation is occurring or has occurred, a statement specifying the nature of the violation, a description of the actions needed to resolve the violation and come into compliance, the deadline within which such actions must be completed, and a statement that, if the violator fails to come into compliance by the specified deadline, the Town may do the work necessary to resolve the violation at the expense of the violator.
 - The order may require, without limitation:
 - i. Elimination of illicit connections or discharges to the MS4
 - ii. Performance of monitoring, analyses, and reporting
 - iii. Cessation of unlawful discharges, practices, or operations
 - iv. Remediation of contamination caused by the illicit connection or discharge.
 - The decisions or orders of the DPW shall be final. Any further relief shall be to a court of competent jurisdiction.



- 5. If the Enforcement Order is not complied with, non-compliance fines will accrue per Wilbraham's *Stormwater Phase II Comprehensive By-Law*, and each day or part thereof that the violation occurs or continues will be considered a separate offense. If action is not taken by the property owner within seven days, the penalty shall become a civil or criminal penalty.
- 6. All hard copy written correspondence to the property owner should be sent both by first class mail and certified mail with return receipt requested. Certified mail provides proof of mailing; first class mail is a backup to ensure that the correspondence is received even if the property owner refuses the certified mail delivery. All such correspondence should be copied to the Board of Health, Town Administrator, and Town Counsel.
- 7. Consult Town Counsel if civil or criminal court action is required.

As an alternative to criminal prosecution or civil action, the DPW may elect to utilize the non-criminal disposition procedure set forth in Massachusetts General Laws Chapter 40, Section 21D or the Town General By-Laws 103A.

5. APPROPRIATE METHODS FOR ELIMINATION OF THE ILLICIT DISCHARGE

| Type of Discharge | Source | Elimination Actions by Town |
|--------------------------------|---|--|
| Sewage | Pipe break within right of way Commercial or industrial direct connection Residential direct connection Infrequent/transient discharge (e.g., RV dumping) Septic Pet waste | Repair Enforcement Enforcement Enforcement, spill response Enforcement, incentive, or aid Warning, education, enforcement |
| Wash Water | Commercial or industrial direct connection Residential direct connection Commercial car wash Household maintenance related activities | EnforcementEnforcementEnforcementWarning and education |
| Liquid Wastes | Professional oil change / car maintenance Heating oil / solvent dumping Homeowner liquid waste disposal (e.g., oil, paint) Spill (trucking) Other industrial wastes | Enforcement, spill response Enforcement, spill response Education, enforcement Spill response Spill response |
| Solid Waste or Obstructions | Trash or garbageErosion from constructionErosion from landscaping (e.g., mulch, loam) | Enforcement Enforcement Warning, education, enforcement |



6. PROCESS FOR DOCUMENTATION AND VERIFICATION OF REMOVAL OF THE CONNECTION OR DISCHARGE

At a minimum, documentation will include a description of the following:

- Discharge and source location
- Description of the discharge
- Date and method of discovery
- Date of elimination
- Repair or enforcement action or planned corrective measures and a schedule for completing the illicit discharge removal
- Date and method to confirm removal.
- Estimate of flow volume removed

As described in Section 2.3.4.5.c of the General Permit, verification of removal of the connection must include water quality sampling for sanitary wastewater and may also include visual inspection, dye-testing, CCTV inspections, and/or damming techniques. Documentation will be kept in the Appendix H of the IDDE Plan.

Town of Wilbraham IDDE Program **Appendix F**Written Procedures and Forms

OUTFALL RECONNAISSANCE INVENTORY/SAMPLE COLLECTION FIELD SHEET

| Section 1: | Background | d Data | | | | | | | | | |
|------------------------------|---|-----------------------------|---------|--------------|----------------|--------------|----------|------------|------------------|-----------------------------|-------------|
| SUBWATERSHED: | | | | | | Outfall | ID: | | LOCATION: | | |
| Today's date: | | | | | | Time (N | Military | y): | | | |
| INVESTIG | ATORS: | | | | | | | | | | |
| TEMPERA | ATURE (°F): | | | RAINFALL (IN | I.): LAST 72 I | HOURS: | | I | AST 24 HOU | RS: | |
| Photo #s and | d short description | on: | | | | | | | | | |
| Land Use in | Land Use in Drainage Area (Check all that apply): | | | | | | | | | | |
| ∏Industria | al (Known Indus | stries): | | |) | _ | | e – Field | | | |
| Resident | tial | | | | | □Ope | n Space | e – Woode | d | | |
| Commer | rcial/Institutiona | ıl | | | | Other: | | | | | |
| Notes (e.g., | origin of outfall | , if known): | | | | | | | | | |
| Section 2: | Outfall Des | cription | | | | | | | | - | |
| | MATE | RIAL | | SH | HAPE | | DI | IMENSIO | NS (IN.) | SUBMERGED | |
| | □RCP | □СМР | Cir | rcular | Single | _ | Diame | eter/Dimen | sions: | In Water: | |
| | □PVC | □HDPE | Ell | liptical | Double | | | | | Partially Fully | |
| | □ DI/CI | Clay | Воз | ЭX | Triple | | S | LOPE (DI | EGREES) | With Sediment: | |
| | Other: | | Ot! | ther: | Other: | | ☐ Fla | at 🔲 I | Moderate | □No | |
| | | | 1 | | | | Ste | еер | | ☐ Partially ☐ Fully | |
| PIPE CO | ONDITION | Good Other | | | ed with Debris | ☐ Cru | ıshed | I | Deteriorated (co | oncrete) Corroded (met | al) |
| OUTLET S | STRUCTURE | Headwall | □R | Riprap | l End No (| Outfall Pro | otection | ı 🗌 Otho | er | | |
| In-Stream (a when collect | applicable ing samples) | ☐ Yes | | □No N | Maintenance/Re | epair Nee | ded? | □ No | Yes (See S | Section 8 for more descript | ion) |
| Flow Presen | ıt? | ☐ Yes | | □No | If No, Skip | ip to Sectio | on 5 | | | | |
| Flow Descri | ption | Trickle | □N | Moderate S | Substantial | (If | f presen | nt) | | | |
| Section 3: | Ouantitativ | e Character | -izatic | on | | | | | | | |
| | | | | | DATA FOR FLO | OWING | OUTF | ALLS | | | |
| PARAM | METER (Thres | shold Level) | | F | RESULT | | UNIT | | | EQUIPMENT | |
| TE | EMPERATURE | ₹ (> 83 ° F) | | | | | | °F | | YSI Meter or Thermon | neter |
| CONDUC | CTIVITY (> 2,0 | 000 UMHOS/cm | n) | | | | | umhos/cr | n | YSI Meter | |
| S | SALINITY (> 0 | .5 PPT) | | | | | | ppt | | YSI Meter | |
| DISSOI | LVED OXYGE | N (< 5.0 mg/L) | | | | | | mg/l | | YSI Meter | |
| A | MMONIA (≥ 0. | .5 mg/L) | | | | | | mg/l | | Test Strips | |
| CHLORINE (> 0.02 mg/L) | | | | | | | | mg/l | | Hach Pocket Colorime | ter II |

OUTFALL RECONNAISSANCE INVENTORY/ SAMPLE COLLECTION FIELD SHEET

Section 4: Physical Indicators for Flowing Outfalls Only Are Any Physical Indicators Present in the flow? \(\sigma\) Yes No (If No, Skip to Section 5) **CHECK if** INDICATOR DESCRIPTION **RELATIVE SEVERITY INDEX (1-3) Present** Sewage Rancid/sour Petroleum/gas □3 – Noticeable from a ODOR $\prod 1$ – Faint 2 – Easily detected distance Other: Sulfide Clear □Brown Gray ☐ Yellow ☐ 1 – Faint colors in ☐2 – Clearly visible in ☐3 – Clearly visible in COLOR sample bottle sample bottle outfall flow Orange Green Red Other: П **TURBIDITY** ☐ 1 – Slight cloudiness $\square 2$ – Cloudy $\square 3$ – Opaque See severity $\square 2$ – Some; indications □3 - Some; origin clear **FLOATABLES** Sewage (Toilet Paper, etc.) Suds □1 – Few/slight; origin of origin (e.g., (e.g., obvious oil - DOES NOT INCLUDE not obvious possible suds or oil sheen, suds, or floating Petroleum (oil sheen) Other: TRASH!! sanitary materials) sheen) Section 5: Physical Indicators for Both Flowing and Non-Flowing Outfalls Are physical indicators that are not related to flow present? ☐ Yes ☐ No (If No, Skip to Section 6) INDICATOR **CHECK if Present** DESCRIPTION COMMENTS □ None □ Grease/Oil □ Paper/Trash □ Foam DEPOSITS/STAINS Heavy sedimentation deposits Other SURROUNDING П Little or No Distress Moderate Distress High Distress VEGETATION ABNORMAL П Excessive Inhibited VEGETATION IN OUTFALL Little or No Erosion ☐ Small Areas of Erosion ☐ Many Eroded Areas **ERODIBILITY** П Colors Oil Sheen Odors Floatables POOR POOL QUALITY Suds ☐Excessive Algae Other: PIPE BENTHIC GROWTH Brown Orange Green Other: \Box Section 6: OVERALL OUTFALL CHARACTERIZATION AS AN ILLICIT DISCHARGE Potential (presence of two or more indicators) Suspect (one or more indicators with a severity of 3) Obvious Unlikely Section 7: Data Collection Surfactants ☐ Ammonia ☐ E. Coli Fecal Coliform ☐ Total Phosphorus SAMPLE FOR THE LAB? □ BOD₅ ☐ None 2. ☐ Flow ☐ Pool If yes, collected from: 3. П ☐ Yes ☐ Intermittent flow trap recommended? ΠNo

Section 8: Any Non-Illicit Discharge Concerns (e.g., trash or needed infrastructure repairs)?

The following document establishes procedures for sample collection, use of field kits, storage and conveyance of samples, and field data collection and storage requirements for dry weather sampling of outfalls in the Town of Wilbraham, MA in accordance with Section 2.3.4.7.b. of the EPA NPDES General Permits for Stormwater Discharges from Small Municipal Separate Storm Sewer Systems (MS4s) in Massachusetts (General Permit).

- 1) Review supplies of sampling bottles and test kits on a weekly basis and order as necessary for field sampling activities.
- 2) Notify the Town of Wilbraham Department of Public Works (DPW) of sampling schedule prior to going into the field (413-596-2800). They will notify the Police Department, as necessary.
- 3) Observe the physical attributes of each outfall or sampling location.
- 4) If dry weather flow is present, note flow volume, odor, and all other characteristics listed on the data collection form. If using an iPad, fill in form fields or drop-down menus as needed.
 - a. In the event that the flow is too slow to sample, place a sandbag upstream of the outfall to capture flow and return to the site in 24 hours to obtain a sample.
 - b. In the event that the outfall is submerged in the receiving water, record this information on the data sheet for the outfall and do not take a sample. An alternate sampling location at an upstream manhole should be located.
- 5) Take a photograph of the outfall with an iPad or camera. If possible, hold a piece of paper or a white board with the unique identifier written on it in the photograph. If using a GIS collection form, ensure the photograph is collected with the correct outfall identifier.
- 6) Sample storm drain outfalls as close to the outfall opening as possible, wearing a fresh pair of disposable gloves.
- 7) **Test Kits**. Using a sterile and pre-cleaned sampling bottle, collect the surface water with care to not disturb sediment materials or collect surface debris/scum as best possible. Use sampling pole if needed to safely reach the outfall. The collected water will be poured into the chlorine sample cell. Follow the manufacturer instructions for all test kit procedures. All waste from the field test kits should be retained and disposed of according to manufacturer instructions.
- 8) **Meters**. A properly calibrated meter should be used to record the following parameters directly from the stream or outfall:
 - a. Conductivity
 - b. Salinity
 - c. Temperature

When flow volume or depth is insufficient to immerse the meter probe, a clean sample bottle may be used to collect a sufficient volume of water to immerse the probe. In such instances, meter readings should be taken immediately.



9) Threshold Levels. In situ readings will be compared to field thresholds as follows:

| Parameter | Threshold Level | Source |
|------------------|------------------|--|
| Surfactants | ≥ 0.25 mg/L | EPA New England Bacterial Source Tracking Protocol |
| Ammonia | ≥ 0.5 mg/L | EPA New England Bacterial Source Tracking Protocol |
| Chlorine | ≥ 0.02 mg/L | EPA 2016 General Permit |
| Conductivity | > 2,000 uS/cm | Center for Watershed Protection |
| Temperature (°F) | > 83 °F | 314 CMR 4.00 for Class B Warm Water |
| Salinity | > 0.5 ppt Rivers | EPA Voluntary Estuary Monitoring Manual |

10) Water quality samples will be taken for laboratory analysis according to the following table. Each bottle will be marked with time, date, and outfall identifier, and parameter to be analyzed.

| All Flowing Outfalls | Impaired Waterbodies ¹ | EPA Approved Method for Analysis |
|--|---|--|
| | Chicopee River (MA36-22) E. coli ² | E. coli: 1603 (preferred); 1103.1; Colilert® 12 16; Colilert-18® 12 15 16; mColiBlue-24®17 |
| Collect E. coli samples first, in a separate sterile sample bottle. | Chicopee River (MA36-24) Fecal coliform | Fecal Coliform: 1680; 1681 |
| | Spectacle Pond (MA36142) Nutrient/Eutrophication Biological Indicators | Phosphorus (Total): 365.1;365.2; 365.3; SM 4500-P-E |
| | All outfalls - Long Island Sound TMDL Nitrogen (Total) | Nitrogen (Total): 351.1/351.2 + 353.2 |

Notes:

- ¹ Table is based on the most recent approved Massachusetts Integrated List of Waters (2014), and will need to be updated when Massachusetts Integrated Lists of Waters are finalized.
- ^z Constituents that are in *blue italics* will already be analyzed as part of the 2016 Small MS4 General Permit sampling requirements, and do not require additional lab analysis.

Results should be recorded, custody forms completed, and samples placed in a cooler on ice. If using an iPad, fill in all form fields for sampling data, check parameter analysis box if a threshold was exceeded, and check outfall completed box when done. Make note of the first bacteria sample time for determining the hold limit until lab analysis.

Be sure to upload all data entry before leaving the site. If there is any doubt whether data was captured, duplicate information on paper forms.

Upon completion of sampling and return to the laboratory, all samples will be turned over to the appropriate sample custodian(s) and accompanied by an appropriate Chain-of-Custody ("COC") form.



11) Equipment/Items Needed

| Field Equipment | Paperwork | Personal Gear |
|--|------------------------------------|--|
| ☐ Sample bottles (from lab with holding time and storage requirements) | ☐ Signed Site Safety Plan | ☐ Waders (or other appropriate footwear) |
| ☐ Extra sample bottles in case of contamination, cracking, or loss | ☐ Chain of Custody form filled out | ☐ Insect repellant |
| ☐ Sampling Pole | ☐ Bottle Labels in Ziploc Bag | □ Sunscreen |
| ☐ Cooler with ice | ☐ Field sheets | ☐ Steel-toed boots (if opening manholes) |
| ☐ Carry Caddy | ☐ CWP Chapter 11 | □ Safety goggles |
| ☐ Digital Camera or iPad | ☐ Field maps | ☐ Light colored long sleeve shirts and pants on-site |
| ☐ Cell Phone or hand-held radio | ☐ Sampling Plan & Locations | ☐ Reflective safety vest |
| ☐ First aid kit | | ■ Business cards |
| ☐ Flashlight or head lamp | | |
| ☐ Nitrile gloves | | |
| ☐ Tape measure | | |
| ☐ Water quality meter(s) | | |
| ☐ Chlorine Test Kit – use kits listed in EPA Bacteria Source Protocol 2012 Draft | | |
| ☐ 1 liter bottle | | |
| ☐ Watch with a second hand | | |
| ☐ Duct tape | | |
| ☐ Sharpies | | |
| ☐ Paper Towels | | |
| ☐ Glass Containers (3) for (1) surfactant kit liquid waste, (2) chloride kit liquid waste, and (3) surfactant kit glass ampules. All disposed of as hazardous waste. | | |
| ☐ Trash bag for gloves, etc. | | |
| ☐ White board/paper for unique outfall ID for photograph | | |



Chapter 11: The Outfall Reconnaissance Inventory

This chapter describes a simple field assessment known as the Outfall Reconnaissance Inventory (ORI). The ORI is designed to fix the geospatial location and record basic characteristics of individual storm drain outfalls, evaluate suspect outfalls, and assess the severity of illicit discharge problems in a community. Field crews should walk all natural and manmade streams channels with perennial and intermittent flow, even if they do not appear on available maps (Figure 19). The goal is to complete the ORI on every stream mile in the MS4 within the first permit cycle, starting with priority subwatersheds identified during the desktop analysis. The results of the ORI are then used to help guide future outfall monitoring and discharge prevention efforts.

11.1 Getting Started

The ORI requires modest mapping, field equipment, staffing and training resources. A complete list of the required and optional resources needed to perform an ORI is presented in Table 30. The ORI can be combined with other stream assessment



Figure 19: Walk all streams and constructed open channels

tools, and may be supplemented by simple indicator monitoring. Ideally, a Phase II community should plan on surveying its entire drainage network at least once over the course of each five-year permit cycle. Experience suggests that it may take up to three stream walks to identify all outfalls.

Best Times to Start

Timing is important when scheduling ORI field work. In most regions of the country, spring and fall are the best seasons to perform the ORI. Other seasons typically have challenges such as over-grown vegetation or high groundwater that mask illicit discharges, or make ORI data hard to interpret⁹.

Prolonged dry periods during the nongrowing season with low groundwater levels are optimal conditions for performing an ORI. Table 31 summarizes some of the regional factors to consider when scheduling ORI surveys in your community. Daily weather patterns also determine whether ORI field work should proceed. In general, ORI field work should be conducted at least 48 hours after the last runoff-producing rain event.

Field Maps

The field maps needed for the ORI are normally generated during the desktop assessment phase of the IDDE program described in Chapter 5. This section

⁹ Upon initial program start-up, the ORI should be conducted during periods of low groundwater to more easily identify likely illicit discharges. However, it should be noted that high water tables can increase sewage contamination in storm drain networks due to infiltration and inflow interactions. Therefore, in certain situations, seasonal ORI surveys may be useful at identifying these types of discharges. Diagnosis of this source of contamination, however, can be challenging.

| | Table 30: Resources Needed to Conduct the ORI | | | | | | | |
|--------------------|---|---|--|--|--|--|--|--|
| Need Area | Minimum Needed | Optional but Helpful | | | | | | |
| Mapping | RoadsStreams | Known problem areas Major land uses Outfalls Specific industries Storm drain network SIC-coded buildings Septics | | | | | | |
| Field Equipment | 5 one-liter sample bottles Backpack Camera (preferably digital) Cell phones or hand-held radios Clip boards and pencils Field sheets First aid kit Flash light or head lamp GPS unit Spray paint (or other marker) Surgical gloves Tape measure Temperature probe Waders (snake proof where necessary) Watch with a second hand | Portable Spectrophotometer and reagents (can be shared among crews) Insect repellant Machete/clippers Sanitary wipes or biodegradable soap Wide-mouth container to measure flow Test strips or probes (e.g., pH and ammonia) | | | | | | |
| Staff | Basic training on field methodology Minimum two staff per crew | Ability to track discharges up the drainage system Knowledge of drainage area, to identify probable sources. Knowledge of basic chemistry and biology | | | | | | |

| Table 31: Preferred Climate/Weather Considerations for Conducting the ORI | | | | | | | |
|---|---|---|--|--|--|--|--|
| Preferred Condition | Reason | Notes/Regional Factors | | | | | |
| Low groundwater (e.g., very few flowing outfalls) | High groundwater can confound results | In cold regions, do not conduct the ORI in the early spring, when the ground is saturated from snowmelt. | | | | | |
| No runoff-producing rainfall within 48 hours | Reduces the confounding influence of storm water | The specific time frame may vary depending on the drainage system. | | | | | |
| Dry Season | Allows for more days of field work | Applies in regions of the country with a "wet/dry seasonal pattern." This pattern is most pronounced in states bordering or slightly interior to the Gulf of Mexico or the Pacific Ocean. | | | | | |
| Leaf Off | Dense vegetation makes finding outfalls difficult | Dense vegetation is most problematic in the southeastern United States. This criterion is helpful but not required. | | | | | |

provides guidance on the basic requirements for good field maps. First, ORI field maps do not need to be fancy. The scale and level of mapping detail will vary based on preferences and navigational skills of field crews. At a minimum, maps should have labeled streets and hydrologic features (USGS blue line streams, wetlands, and lakes), so field crews can orient themselves and record their findings spatially.

Field maps should delineate the contributing drainage area to major outfalls, but only if they are readily available. Urban landmarks such as land use, property boundaries, and storm drain infrastructure are also quite useful in the field. ORI field maps should be used to check the accuracy and quality of pre-existing mapping information, such as the location of outfalls and stream origins.

Basic street maps offer the advantage of simplicity, availability, and well-labeled road networks and urban landmarks. Supplemental maps such as a 1": 2000' scale USGS Quad sheet or finer scale aerial photograph are also recommended for the field. USGS Quad sheets are readily available and display major transportation networks and landmarks, "blue line" streams, wetlands, and topography. Quad maps may be adequate for less developed subwatersheds, but are not always accurate in more urban subwatersheds.

Recent aerial photographs may provide the best opportunity to navigate the subwatershed and assess existing land cover. Aerial photos, however, may lack topography and road names, can be costly, and are hard to record field notes on due to their darkness. GIS-ready aerial photos and USGS Quad sheets can be downloaded from the internet or obtained from local planning, parks, or public works agencies.

Field Sheets

ORI field sheets are used to record descriptive and quantitative information about each outfall inventoried in the field. Data from the field sheets represent the building blocks of an outfall tracking system allowing program managers to improve IDDE monitoring and management. A copy of the ORI field sheet is provided in Appendix D, and is also available as a Microsoft WordTM document. Program managers should modify the field sheet to meet the specific needs and unique conditions in their community.

Field crews should also carry an authorization letter and a list of emergency phone numbers to report any emergency leaks, spills, obvious illicit discharges or other water quality problems to the appropriate local authorities directly from the field. Local law enforcement agencies may also need to be made aware of the field work. Figure 20 shows an example of a water pollution emergency contact list developed by Montgomery County, MD.

Equipment

Basic field equipment needed for the ORI includes waders, a measuring tape, watch, camera, GPS unit, and surgical gloves (see Table 30). GPS units and digital cameras are usually the most expensive equipment items; however, some local agencies may already have them for other applications. Adequate ranging, water-resistant, downloadable GPS units can be purchased for less than \$150. Digital cameras are preferred and can cost between \$200 and \$400, however, conventional or disposable cameras can also work, as long as they have flashes. Handheld data recorders and customized software can be used to record text, photos, and GPS coordinates electronically in the field. While

these technologies can eliminate field sheets and data entry procedures, they can be quite expensive. Field crews should always carry basic safety items, such as cell phones, surgical gloves, and first aid kits.

Staffing

The ORI requires at least a two-person crew, for safety and logistics. Three person crews provide greater safety and flexibility, which helps divide tasks, allows one person to assess adjacent land uses, and facilitates tracing outfalls to their source. All crew members should be trained on how to complete the ORI and should have a basic understanding of illicit discharges and their water quality impact. ORI crews can be staffed by trained volunteers, watershed groups and college interns. Experienced crews can normally expect to cover two to three stream miles per day, depending on stream access and outfall density.

11.2 Desktop Analysis to Support the ORI

Two tasks need to be done in the office before heading out to the field. The major ORI preparation tasks include estimating the total stream and channel mileage in the subwatershed and generating field maps. The total mileage helps program managers scope out how long the ORI will take and how much it will cost. As discussed before, field maps are an indispensable navigational aid for field crews working in the subwatershed.

Delineating Survey Reaches

ORI field maps should contain a preliminary delineation of **survey reaches**. The stream network within your subwatershed should be delineated into discrete segments of relatively uniform character. Delineating survey reaches provides good stopping and starting points for field crews, which




Figure 20: Example of a comprehensive emergency contact list for Montgomery County, MD

is useful from a data management and logistics standpoint. Each survey reach should have its own unique identifying number to facilitate ORI data analysis and interpretation. Figure 21 illustrates some tips for delineating survey reaches, and additional guidance is offered below:

- Survey reaches should be established above the confluence of streams and between road crossings that serve as a convenient access point.
- Survey reaches should be defined at the transition between major changes in land use in the stream corridor (e.g. forested land to commercial area).
- Survey reaches should generally be limited to a quarter mile or less in length. Survey reaches in lightly

- developed subwatersheds can be longer than those in more developed subwatersheds, particularly if uniform stream corridor conditions are expected throughout the survey reach.
- Access through private or public property should be considered when delineating survey reaches as permission may be required.

It should be noted that initial field maps are not always accurate, and changes may need to be made in the field to adjust survey reaches to account for conditions such as underground streams, missing streams or long culverts. Nevertheless, upfront time invested in delineating survey reaches makes it easier for field crews to perform the ORI.



Figure 21: Various physical factors control how survey reaches are delineated. (a) Survey reaches based on the confluence of stream tributaries. (b) A long tributary split into ¼ mile survey reaches. (c) Based on a major road crossing (include the culvert in the downstream reach). (d) Based on significant changes in land use (significant changes in stream features often occur at road crossings, and these crossings often define the breakpoints between survey reaches).

11.3 Completing the ORI

Field crews conduct an ORI by walking all streams and channels to find outfalls, record their location spatially with a GPS unit and physically mark them with spray paint or other permanent marker. Crews also photograph each outfall and characterize its dimensions, shape, and component material, and record observations on basic sensory and physical indicators. If dry weather flow occurs at the outfall, additional flow and water quality data are collected. Field crews may also use field probes or test strips to measure indicators such as temperature, pH, and ammonia at flowing outfalls.

The ORI field sheet is divided into eight sections that address both flowing and non-flowing outfalls (Appendix D). Guidance on completing each section of the ORI field sheet is presented below.

Outfalls to Survey

The ORI applies to all outfalls encountered during the stream walk, regardless of diameter, with a few exceptions noted in Table 32. Common outfall conditions seen in communities are illustrated in Figure 22 As a rule, crews should only omit an outfall if they can definitively conclude it has no potential to contribute to a transitory illicit discharge. While EPA's Phase I guidance only targeted major outfalls (diameter of 36 inches or greater), documenting all outfalls is recommended, since smaller pipes make up the majority of all outfalls and frequently have illicit discharges (Pitt et al., 1993 and Lalor, 1994). A separate ORI field sheet should be completed for each outfall.

| Table 32: Outfalls to Include in the Screening | | | | | | | |
|---|--|--|--|--|--|--|--|
| Outfalls to Record | Outfalls to Skip | | | | | | |
| Both large and small diameter pipes that appear to be part of the storm drain infrastructure | Drop inlets from roads in culverts (unless evidence of illegal dumping, dumpster | | | | | | |
| Outfalls that appear to be piped headwater streams | leaks, etc.) | | | | | | |
| Field connections to culverts | Cross-drainage culverts in transportation right-of-way (i.e., can see daylight at other | | | | | | |
| Submerged or partially submerged outfalls | end) | | | | | | |
| Outfalls that are blocked with debris or sediment | Weep holes | | | | | | |
| deposits | Flexible HDPE pipes that are known to | | | | | | |
| Pipes that appear to be outfalls from storm water | serve as slope drains | | | | | | |
| treatment practices | Pipes that are clearly connected to roof | | | | | | |
| Small diameter ductile iron pipes | downspouts via above-ground connections | | | | | | |
| Pipes that appear to only drain roof downspouts but that are subsurface, preventing definitive confirmation | | | | | | | |




Figure 22: Typical Outfall Types Found in the Field

Obvious Discharges

Field crews may occasionally encounter an obvious illicit discharge of sewage or other pollutants, typified by high turbidity, odors, floatables and unusual colors. When obvious discharges are encountered, field crews should STOP the ORI survey, track down the source of the discharge and immediately contact the appropriate water pollution agency for enforcement. Crews should photo-document the discharge, estimate its flow volume and collect a sample for water quality analysis (if this can be done safely). All three kinds of evidence are extremely helpful to support subsequent enforcement. Chapter 13 provides details on techniques to track down individual discharges.

11.4 ORI Section 1 - Background Data

The first section of the ORI field sheet is used to record basic data about the survey, including time of day, GPS coordinates for the outfall, field crew members, and current

and past weather conditions (Figure 23). Much of the information in this section is self-explanatory, and is used to create an accurate record of when, where, and under what conditions ORI data were collected.

Every outfall should be photographed and marked by directly writing a unique identifying number on each outfall that serves as its subwatershed "address" (Figure 24). Crews can use spray paint or another temporary marker to mark outfalls, but may decide to replace temporary markings with permanent ones if the ORI is repeated later. Markings help crews confirm outfall locations during future investigations, and gives citizens a better way to report the location of spills or discharges when calling a water pollution hotline. Crews should mark the spatial location of all outfalls they encounter directly on field maps, and record the coordinates with a GPS unit that is accurate to within 10 feet. Crews should take a digital photo of each outfall, and record photo numbers in Section 1 of the field sheet.

| Section 1: Background Data | | | | | |
|--|----------|--------------------------------|--------------------|------------|--|
| Subwatershed: | | | Outfall ID: | | |
| Today's date: | | | Time (Military): | | |
| Investigators: | | | Form completed by: | | |
| Temperature (°F): | | Rainfall (in.): Last 24 hours: | Last 48 hours: | | |
| Latitude: | Long | itude: | GPS Unit: | GPS LMK #: | |
| Camera: | | | Photo #s: | | |
| Land Use in Drainage Area (Check all th | at apply | r): | | | |
| | | | ☐ Open Space | | |
| Ultra-Urban Residential | | | ☐ Institutional | | |
| ☐ Suburban Residential | | | Other: | | |
| ☐ Commercial | | | Known Industries: | | |
| Notes (e.g., origin of outfall, if known): | | | | | |
| | | | | | |

Figure 23: Section 1 of the ORI Field Sheet



Figure 24: Labeling an outfall (a variety of outfall naming conventions can be used)

The land use of the drainage area contributing to the outfall should also be recorded. This may not always be easy to characterize at large diameter outfalls that drain dozens or even hundreds of acres (unless you have aerial photographs). On the other hand, land use can be easily observed at smaller diameter outfalls, and in some cases, the specific origin can be found (e.g., a roof leader or a parking lot; Figure 25). The specific origin should be recorded in the "notes" portion of Section 1 on the field sheet.

11.5 ORI Section 2 - Outfall Description

This part of the ORI field sheet is where basic outfall characteristics are noted (Figure 26). These include material, and presence of flow at the outfall, as well as the pipe's dimensions (Figure 27). These measurements are used to confirm and supplement existing storm drain maps (if they are available). Many communities only map storm drain outfalls that exceed a given pipe diameter, and may not contain data on the material and condition of the pipe.



Figure 25: The origin of this corrugated plastic pipe was determined to be a roof leader from the house up the hill.

Section 2 of the field sheet also asks if the outfall is submerged in water or obstructed by sediment and the amount of flow, if present. Figure 28 provides some photos that illustrate how to characterize relative

submergence, deposition and flow at outfalls. If no flow is observed at the outfall, you can skip the next two sections of the ORI field sheet and continue with Section 5.

| section 2: Outrain Description | | | | | | | | |
|----------------------------------|---|----------------|---------------------------------------|-------------------------------------|---------------------------------|--|--|--|
| LOCATION | MATE | RIAL | SHA | APE | DIMENSIONS (IN.) | SUBMERGED | | |
| ☐ Closed Pipe | RCP PVC Steel Other: | ☐ CMP | ☐ Circular ☐ Eliptical ☐ Box ☐ Other: | ☐ Single ☐ Double ☐ Triple ☐ Other: | Diameter/Dimensions: | In Water: No Partially Fully With Sediment: No Partially Fully | | |
| ☐ Open drainage | ☐ Concrete ☐ Earthen ☐ rip-rap ☐ Other: | _ | ☐ Trapezoid ☐ Parabolic ☐ Other: | | Depth: Top Width: Bottom Width: | | | |
| ☐ In-Stream | (applicable w | hen collecting | samples) | | | | | |
| Flow Present? | ☐ Yes | ☐ No | If No, Ski | ip to Section 5 | | | | |
| Flow Description (If present) | Trickle | ☐ Moderate | e ☐ Substantial | | | | | |

Figure 26: Section 2 of the ORI Field Sheet



Figure 27: Measuring Outfall Diameter



Figure 28: Characterizing Submersion and Flow

11.6 ORI Section 3 -Quantitative Characterization for Flowing Outfalls

This section of the ORI records direct measurements of **flowing outfalls**, such as flow, temperature, pH and ammonia (Figure 29). If desired, additional water quality parameters can be added to this section. Chapter 12 discusses the range of water quality parameters that can be used.

Field crews measure the rate of flow using one of two techniques. The first technique simply records the time it takes to fill a container of a known volume, such as a one liter sample bottle. In the second technique,

| | FIELD DATA FOR FLOWING OUTFALLS | | | | | | | |
|-------------|---------------------------------|--|----------|------------------|--|--|--|--|
| PA | PARAMETER RESULT UNIT EQUIPMENT | | | | | | | |
| □Flow #1 | Volume | | Liter | Bottle | | | | |
| 110w #1 | Time to fill | | Sec | | | | | |
| □Flow #2 | Flow depth | | In | Tape measure | | | | |
| | Flow width | | Ft, In | Tape measure | | | | |
| | Measured length | | Ft, In | Tape measure | | | | |
| | Time of travel | | S | Stop watch | | | | |
| Temperature | | | °F | Thermometer | | | | |
| pН | | | pH Units | Test strip/Probe | | | | |
| Ammonia | | | mg/L | Test strip | | | | |

Figure 29: Section 3 of the ORI Field Sheet

the crew measures the velocity of flow, and multiplies it by the estimated cross sectional area of the flow.

To use the flow volume technique, it may be necessary to use a "homemade" container to capture flow, such as a cut out plastic milk container that is marked to show a one liter volume. The shape and flexibility of plastic containers allows crews to capture relatively flat and shallow flow (Figure 30). The flow volume is determined as the volume of flow captured in the container per unit time.

The second technique measures flow rate based on velocity and cross sectional area, and is preferred for larger discharges where containers are too small to effectively capture the flow (Figure 31). The crew measures and marks off a fixed flow length (usually about five feet), crumbles leaves or other light material, and drops them into the discharge (crews can also carry peanuts or ping pong balls to use). The crew then measures the time it takes the marker to travel across the length. The velocity of flow is computed as the length of the flow path (in feet) divided by the travel time (in seconds). Next, the cross-sectional flow area is measured by taking multiple readings of the depth and width of flow. Lastly, crosssectional area (in square feet) is multiplied by flow velocity (feet/second) to calculate the flow rate (in cubic feet/second).

Crews may also want to measure the quality of the discharge using relatively inexpensive probes and test strips (e.g., water temperature, pH, and ammonia). The choice of which indicator parameters to measure is usually governed by the overall IDDE monitoring framework developed by the community. Some communities have used probes or test strips to measure additional indicators such as conductivity, chlorine, and hardness. Research by Pitt (for this project) suggests that probes by Horiba for pH and conductivity are the most reliable and



Figure 30: Measuring flow (as volume per time)

accurate, and that test strips have limited value.

When probes or test strips are used, measurements should be made from a sample bottle that contains flow captured from the outfall. The exact measurement recorded by the field probe should be recorded in Section 3 of the field sheet. Some interpolation may be required for test strips, but do not interpolate further than the mid-range between two color points.

11.7 ORI Section 4 – Physical Indicators for Flowing Outfalls Only

This section of the ORI field sheet records data about four sensory indicators associated with flowing outfalls—odor, color, turbidity and floatables (Figure 32). Sensory indicators can be detected by smell or sight, and require no measurement equipment. Sensory indicators do not always reliably predict illicit discharge, since the senses can be fooled, and may result in a "false negative" (i.e., sensory indicators fail to detect an illicit discharge when one is actually present). Sensory indicators are important, however, in detecting the most severe or obvious discharges. Section 4 of the field sheet asks whether the sensory indicator is present, and if so, what is its severity, on a scale of one to three.

Section 4: Physical Indicators for Flowing Outfalls Only





Figure 31: Measuring flow (as velocity times cross-sectional area)

| Are Any Physical Indicators Present in the flow? Yes No (If No. Skip to Section 5) | | | | | |
|--|---------------------|---|--------------------------------------|---|---|
| INDICATOR | CHECK if Present | DESCRIPTION | RELATIVE SEVERITY INDEX M(1-3) | | |
| Odor | | ☐ Sewage ☐ Rancid/sour ☐ Petroleum/gas ☐ Sulfide ☐ Other: | 1 – Faint | 2 – Easily detected | 3 – Noticeable from a distance |
| Color | | □ Clear □ Brown □ Gray □ Yellow □ Green □ Orange □ Red □ Other: | ☐ 1 – Faint colors in sample bottle | 2 – Clearly visible in sample bottle | 3 - Clearly visible in outfall flow |
| Turbidity | | See severity | ☐ 1 – Slight cloudiness | 2 - Cloudy | 3 - Opaque |
| Floatables -Does Not Include Trash!! | | Sewage (Toilet Paper, etc.) Suds Petroleum (oil sheen) Other: | ☐ 1 – Few/slight; origin not obvious | 2 – Some; indications of origin (e.g., possible suds or oil sheen) | 3 - Some; origin clear (e.g., obvious oil sheen, suds, or floating sanitary materials) |

Figure 32: Section 4 of the ORI Field Sheet

Odor

Section 4 asks for a description of any odors that emanate from the outfall and an associated severity score. Since noses have different sensitivities, the entire field crew should reach consensus about whether an odor is present and how severe it is. A severity score of one means that the odor is faint or the crew cannot agree on its presence or origin. A score of two indicates a moderate odor within the pipe. A score of three is assigned if the odor is so strong that the crew smells it a considerable distance away from the outfall.

TIP

Make sure the origin of the odor is the outfall. Sometimes shrubs, trash or carrion, or even the spray paint used to mark the outfall can confuse the noses of field crews.

Color

The color of the discharge, which can be clear, slightly tinted, or intense is recorded next. Color can be quantitatively analyzed in the lab, but the ORI only asks for a visual assessment of the discharge color and its intensity. The best way to measure color is to collect the discharge in a clear sample bottle and hold it up to the light (Figure 33). Field crews should also look for downstream plumes of color that appear to be associated with the outfall. Figure 34 illustrates the spectrum of colors that may be encountered during an ORI survey, and offers insight on how to rank the relative intensity or strength of discharge color. Color often helps identify industrial discharges; Appendix K provides guidance on colors often associated with specific industrial operations.

Turbidity

The ORI asks for a visual estimate of the turbidity of the discharge, which is a measure of the cloudiness of the water. Like color, turbidity is best observed in a clear sample bottle, and can be quantitatively measured using field probes. Crews should also look for turbidity in the plunge pool below the outfall, and note any downstream turbidity plumes that appear to be related to the outfall. Field crews can sometimes confuse turbidity with color, which are related but are not the same. Remember, turbidity is a measure of how easily light can penetrate through the sample bottle, whereas color is defined by the tint or intensity of the color observed. Figure 34 provides some examples of how to distinguish turbidity from color, and how to rank its relative severity.



Figure 33: Using a sample bottle to estimate color and turbidity




Figure 34: Interpreting Color and Turbidity

Floatables

The last sensory indicator is the presence of any floatable materials in the discharge or the plunge pool below. Sewage, oil sheen, and suds are all examples of floatable indicators; trash and debris are generally not in the context of the ORI. The presence of floatable materials is determined visually, and some guidelines for ranking their severity are provided in Figure 35, and described below.

If you think the floatable is sewage, you should automatically assign it a severity score of three since no other source looks quite like it. Surface oil sheens are ranked based on their thickness and coverage. In some cases, surface sheens may not be related to oil discharges, but instead are

created by in-stream processes, such as shown in Figure 36. A thick or swirling sheen associated with a petroleum-like odor may be diagnostic of an oil discharge.

Suds are rated based on their foaminess and staying power. A severity score of three is designated for thick foam that travels many feet before breaking up. Suds that break up quickly may simply reflect water turbulence, and do not necessarily have an illicit origin. Indeed, some streams have naturally occurring foams due to the decay of organic matter. On the other hand, suds that are accompanied by a strong organic or sewage-like odor may indicate a sanitary sewer leak or connection. If the suds have a fragrant odor, they may indicate the presence of laundry water or similar wash waters.



Figure 35: Determining the Severity of Floatables





Figure 36: Synthetic versus Natural Sheen (a) Sheen from bacteria such as iron floc forms a sheet-like film that cracks if disturbed (b) Synthetic oil forms a swirling pattern

11.8 ORI Section 5 - Physical Indicators for Both Flowing and Non-Flowing Outfalls

Section 5 of the ORI field sheet examines physical indicators found at both **flowing** and non-flowing outfalls that can reveal the impact of past discharges (Figure 37). Physical indicators include outfall damage, outfall deposits or stains, abnormal vegetation growth, poor pool quality, and benthic growth on pipe surfaces. Common

examples of physical indicators are portrayed in Figures 38 and 39. Many of these physical conditions can indicate that an intermittent or transitory discharge has occurred in the past, even if the pipe is not currently flowing. Physical indicators are not ranked according to their severity, because they are often subtle, difficult to interpret and could be caused by other sources. Still, physical indicators can provide strong clues about the discharge history of a storm water outfall, particularly if other discharge indicators accompany them.

| Section 5: Physical Indicators for Both Flowing and Non-Flowing Outfalls Are physical indicators that are not related to flow present? | | | | | |
|---|------------------|---|----------|--|--|
| INDICATOR | CHECK if Present | DESCRIPTION | COMMENTS | | |
| Outfall Damage | | Spalling, Cracking or Chipping Pecling Paint Corrosion | | | |
| Deposits/Stains | | ☐ Oily ☐ Flow Line ☐ Paint ☐ Other: | | | |
| Abnormal Vegetation | | ☐ Excessive ☐ Inhibited | | | |
| Poor pool quality | | ☐ Odors ☐ Colors ☐ Floatables ☐ Oil Sheen ☐ Suds ☐ Excessive Algae ☐ Other: | | | |
| Pipe benthic growth | | ☐ Brown ☐ Orange ☐ Green ☐ Other: | | | |

Figure 37: Section 5 of the ORI Field Sheet



Figure 38: Interpreting Benthic and Other Biotic Indicators

This brownish algae indicates an elevated nutrient level.



Figure 39: Typical Findings at Both Flowing and Non-Flowing Outfalls

11.9 ORI Sections 6-8 - Initial Outfall Designation and Actions

The last three sections of the ORI field sheet are where the crew designates the illicit discharge severity of the outfall and recommends appropriate management and monitoring actions (Figure 40). A discharge rating is designated as obvious, suspect,

potential or unlikely, depending on the number and severity of discharge indicators checked in preceding sections.

It is important to understand that the ORI designation is only an initial determination of discharge potential. A more certain determination as to whether it actually is an illicit discharge is made using a more sophisticated indicator monitoring method. Nevertheless, the ORI outfall

designation gives program managers a better understanding of the distribution and severity of illicit discharge problems within a subwatershed

Section 7 of the ORI field sheet records whether indicator samples were collected for laboratory analysis, or whether an intermittent flow trap was installed (e.g., an optical brightener trap or caulk dam described in Chapter 13). Field crews should record whether the sample was taken from a pool or directly from the outfall, and the type of intermittent flow trap used, if any. This section can also be used to recommend follow-up sampling, if the crew does not carry sample bottles or traps during the survey.

The last section of the ORI field sheet is used to note any unusual conditions near the outfall such as dumping, pipe failure, bank erosion or maintenance needs. While these maintenance conditions are not directly related to illicit discharge detection, they often are of interest to other agencies and utilities that maintain infrastructure.

11.10 Customizing the ORI for a Community

The ORI method is meant to be adaptable, and should be modified to reflect local conditions and field experience. Some

indicators can be dropped, added or modified in the ORI form. This section looks at four of the most common adaptations to the ORI:

- Open Channels
- Submerged/Tidally Influenced Outfalls
- Cold Climates
- Use of Biological Indicators

In each case, it may be desirable to revise the ORI field sheet to collect data reflecting these conditions.

Open Channels

Field crews face special challenges in more rural communities that have extensive open channel drainage. The ditches and channels serve as the primary storm water conveyance system, and may lack storm drain and sewer pipes. The open channel network is often very long with only a few obvious outfalls that are located far apart. While the network can have illicit discharges from septic systems, they can typically only be detected in the ORI if a straight pipe is found. Some adaptations for open channel systems are suggested in Table 33.

| Section 6: Overall Outfall Character | rization | | |
|--------------------------------------|---------------------------|----------|---|
| Unlikely Potential (pre | sence of two or more indi | icators) | ☐ Suspect (one or more indicators with a severity of 3) ☐ Obvious |
| Section 7: Data Collection | | | |
| 1. Sample for the lab? | ☐ Yes | ☐ No | |
| 2. If yes, collected from: | Flow | Pool | |
| 3. Intermittent flow trap set? | ☐ Yes | ☐ No | If Yes, type: OBM Caulk dam |

Section 8: Any Non-Illicit Discharge Concerns (e.g., trash or needed infrastructure repairs)?

Figure 40: Sections 6-8 of the ORI Field Sheet

Submerged/Tidally Influenced Outfalls

The ORI can be problematic in coastal communities where outfalls are located along the waterfront and may be submerged at high tide. The ORI methods need to be significantly changed to address these constraints. Often, outfalls are initially located from offshore using canoes or boats, and then traced landward to the first manhole that is not tidally influenced. Field crews then access the storm drain pipe at the manhole and measure whatever indicators they can observe in the confined and dimly lit space. Table 33 recommends strategies to sample outfalls in the challenging environment of coastal communities.

Winter and Ice

Ice can be used as a discharge indicator in northern regions when ice forms in streams and pipes during the winter months (Figure 41). Because ice lasts for many weeks, and most illicit discharges are warm, astute field crews can interpret outfall history from ice melting patterns along pipes and streams. For example, exaggerated

melting at a frozen or flowing outfall may indicate warm water from sewage or industrial discharge. Be careful, because groundwater is warm enough to cause some melting at below freezing temperatures. Also, ice acts like an intermittent flow trap, and literally freezes these discharges. Crews should also look for these traps to find any discolored ice within the pipe or below the outfall.

A final winter indicator is "rime ice," which forms when steam freezes. This beautiful ice formation is actually a good indicator of sewage or other relatively hot discharge that causes steam to form (Figure 41).

Biological Indicators

The diversity and pollution tolerance of various species of aquatic life are widely used as an indicator of overall stream health, and has sometimes been used to detect illicit discharges. One notable example is the presence of the red-eared slider turtle, which is used in Galveston, Texas to find sewage discharges, as they have a propensity for the nutrient rich waters associated with sewage (Figure 42).

| Table 33: Special Considerations for Open Channels/Submerged Outfalls | | | | |
|---|---|--|--|--|
| OPEN CHANNELS | | | | |
| Challenge Suggested Modification | | | | |
| Too many miles of channel to walk | Stop walking at a given channel size or drainage area | | | |
| Difficulty marking them | Mark on concrete or adjacent to earth channel | | | |
| Interpreting physical indicators | For open channels with mild physical indicators, progress up the system to investigate further. | | | |
| SUBMERGED | TIDALLY INFLUENCED OUTFALLS | | | |
| Challenge | Suggested Modification | | | |
| Access for ORI – Tidal Influence | Access during low tide | | | |
| Access for ORI – Always submerged | Access by boat or by shore walking | | | |
| Interpreting physical indicators | For outfalls with mild physical indicators, also inspect from the nearest manhole that is not influenced by tides | | | |
| Sampling (if necessary) | Sample "up pipe" | | | |





Figure 42: One biological indicator is this red-eared slider turtle

Figure 41: Cold climate indicators of illicit discharges

11.11 Interpreting ORI Data

The ORI generates a wealth of information that can provide managers with valuable insights about their illicit discharge problems, if the data are managed and analyzed effectively. The ORI can quickly define whether problems are clustered in a particular area or spread across the community. This section presents a series of methods to compile, organize and interpret ORI data, including:

- 1. Basic Data Management and Quality Control
- 2. Outfall Classification
- 3. Simple Suspect Outfall Counts
- 4. Mapping ORI Data
- 5. Subwatershed and Reach Screening
- 6. Characterizing IDDE Problems at the Community Level

The level of detail for each analysis method should be calibrated to local resources, program goals, and the actual discharge problems discovered in the stream corridor. In general, the most common conditions and problems will shape your initial monitoring strategy, which prioritizes the subwatersheds or reaches that will be targeted for more intensive investigations.

Program managers should analyze ORI data well before every stream mile is walked in the community, and use initial results to modify field methods. For example, if initial results reveal widespread potential problems, program managers may want to add more indicator monitoring to the ORI to track down individual discharge sources (see Chapter 12). Alternatively, if the same kind of discharge problem is repeatedly found, it may be wise to investigate whether there is a common source or activity generating it (e.g., high turbidity observed at many flowing outfalls as a result of equipment washing at active construction sites).

Basic Data Management and Quality Control

The ORI produces an enormous amount of raw data to characterize outfall conditions. It is not uncommon to compile dozens of individual ORI forms in a single subwatershed. The challenge is to devise a system to organize, process, and translate this data into simpler outputs and formats that can guide illicit discharge elimination efforts. The system starts with effective quality control procedures in the field.

Field sheets should be managed using either a three-ring binder or a clipboard. A small field binder offers the ability to quickly flip back and forth among the outfall forms. Authorization letters, emergency contact lists, and extra forms can also be tucked inside.

At the end of each day, field crews should regroup at a predetermined location to compare notes. The crew leader should confirm that all survey reaches and outfalls of interest have been surveyed, discuss initial findings, and deal with any logistical problems. This is also a good time to check whether field crews are measuring and recording outfall data in the same way, and are consistent in what they are (or are not) recording. Crew leaders should also use this time to review field forms for accuracy and thoroughness. Illegible handwriting should be neatened and details added to notes and any sketches. The crew leader should also organize the forms together into a single master binder or folder for future analysis.

Once crews return from the field, data should be entered into a spreadsheet or database. A Microsoft Access database is provided with this Manual as part of Appendix D (Figure 43), and is supplied

on a compact disc with each hard copy. It can also be downloaded with Appendix D from http://www.stormwatercenter.net. Information stored in this database can easily be imported into a GIS for mapping purposes. The GIS can generate its own database table that allows the user to create subwatershed maps showing outfall characteristics and problem areas.

Once data entry is complete, be sure to check the quality of the data. This can be done quickly by randomly spot-checking 10% of the entered data. For example, if 50 field sheets were completed, check five of the spreadsheet or database entries. When transferring data into GIS, quality control maps that display labeled problem outfalls should be created. Each survey crew is responsible for reviewing the accuracy of these maps.

Outfall Classification

A simple outfall designation system has been developed to summarize the discharge potential for individual ORI field sheets. Table 34 presents the four outfall designations that can be made.

| Table 34: Outfall Designation System Using ORI Data | | | |
|--|---|--|--|
| Designation | Description | | |
| 1. Obvious Discharge | Outfalls where there is an illicit discharge that doesn't even require sample collection for confirmation | | |
| 2. Suspect Discharge | Flowing outfalls with high severity on one or more physical indicators | | |
| 3. Potential Discharge | Flowing or non-flowing outfalls with presence of two or more physical indicators | | |
| 4. Unlikely Discharge | Non-flowing outfalls with no physical indicators of an illicit discharge | | |

Simple Suspect Outfall Counts

The first priority is to count the frequency of each outfall designation in the subwatershed or the community as a whole. This simple screening analysis counts the number of problem outfalls per stream mile (i.e., the sum of outfalls designated as having potential, suspected or obvious illicit discharge potential). The density of problem outfalls per stream mile is an important metric to target and screen subwatersheds.

Based on problem outfall counts, program managers may discover that a particular monitoring strategy may not apply to the community. For example, if few problem outfalls are found, an extensive follow-up monitoring program may not be needed, so that program resources can be shifted to pollution hotlines to report and control transitory discharges such as illegal dumping. The key point of this method is to avoid getting lost in the raw data, but look instead to find patterns that can shape a cost-effective IDDE program.

Mapping ORI Data

Maps are an excellent way to portray outfall data. If a GIS system is linked to the ORI database, maps that show the spatial distribution of problem outfalls, locations of dumping, and overall reach conditions can be easily generated. Moreover, GIS provides flexibility that allows for rapid updates to maps as new data are collected and compiled. The sophistication and detail of maps will depend on the initial findings, program goals, available software, and GIS capability.

Subwatershed maps are also an effective and important communication and education tool to engage stakeholders (e.g., public officials, businesses and community residents), as

they can visually depict reach quality and the location of problem outfalls. The key point to remember is that maps are tools for understanding data. Try to map with a purpose in mind. A large number of cluttered maps may only confuse, while a smaller number with select data may stimulate ideas for the follow-up monitoring strategy.

Subwatershed and Survey Reach Screening

Problem outfall metrics are particularly valuable to screen or rank priority subwatersheds or survey reaches. The basic approach is simple: select the outfall metrics that are most important to IDDE program goals, and then see how individual subwatersheds or reaches rank in the process. This screening process can help determine which subwatersheds will be priorities for initial follow-up monitoring efforts. When feasible, the screening process should incorporate non-ORI data, such as existing dry weather water quality data, citizen complaints, permitted facilities, and habitat or biological stream indicators.




Figure 43: Sample screen from ORI Microsoft Access database

An example of how outfall metrics can screen subwatersheds is provided in Table 35. In this hypothetical example, four metrics were used to screen three subwatersheds within a community: number of suspect discharges, subwatershed population as a percent of the total community, number of industrial discharge permits, and number of outfalls per stream mile. Given these screening criteria, subwatershed C was selected for the next phase of detailed investigation.

Characterizing the IDDE Problem at the Community Level

ORI data should be used to continuously revisit and revise the IDDE program as more is learned about the nature and

distribution of illicit discharge problems in the community. For example, ORI discharge designation should be compared against illicit discharge potential (IDP) predictions made during the original desktop analysis (Chapter 5) to refine discharge screening factors, and formulate new monitoring strategies.

In general, community illicit discharge problem can be characterized as minimal, clustered, or severe (Table 36). In the minimal scenario, very few and scattered problems exist; in the clustered scenario, problems are located in isolated subwatersheds; and in the severe scenario, problems are widespread.

| Table 35: An Example of ORI Data Being Used to Compare Across Subwatersheds | | | | |
|---|-------------------------|--|---|--|
| | # of suspect discharges | Population as % of total community | # of industrial discharge permits | # of outfalls per stream/ conveyance mile |
| Subwatershed A | 2 | 30 | 4 | 6 |
| Subwatershed B | 1 | 10 | 0 | 3 |
| Subwatershed C | 8 | 60 | 2 | 12 |

| Table 36: Using Stream and ORI Data to Categorize IDDE Problems | | | |
|---|---|--|--|
| Extent | ORI Support Data | | |
| Minimal | Less than 10% of total outfalls are flowing | | |
| | Less than 20% of total outfalls with obvious, suspect or potential designation | | |
| Clustered | Two thirds of the flowing outfalls are located within one third of the subwatersheds | | |
| | More than 20% of the communities subwatersheds have greater than 20% of outfalls with obvious, suspect or potential designation | | |
| Severe | More than 10% of total outfalls are flowing | | |
| | More than 50% of total outfalls with obvious, suspect or potential designation | | |
| | More than 20% of total outfalls with obvious or suspect designation | | |

11.12 Budgeting and Scoping the ORI

Many different factors come into play when budgeting and scoping an ORI survey: equipment needs, crew size and the stream miles that must be covered. This section presents some simple rules of thumb for ORI budgeting.

Equipment costs for the ORI are relatively minor, with basic equipment to outfit one team of three people totaling about \$800 (Table 37). This cost includes one-time expenses to acquire waders, a digital camera and a GPS unit, as well as disposable supplies.

The majority of the budget for an ORI is for staffing the desktop analysis, field crews and data analysis. Field crews can consist of two or three members, and cover about two to three miles of stream (or open channel) per day. Three staff-days should be allocated for pre- and post-field work for each day spent in the field.

Table 38 presents example costs for two hypothetical communities that conduct the ORI. Community A has 10 miles of open channel to investigate, while Community B has 20 miles. In addition, Community A has fewer staff resources available and therefore uses two-person field crews, while Community B uses three-person field crews. Total costs are presented as annual costs, assuming that each community is able to conduct the ORI for all miles in one year.

| Table 37: Typical Field Equipment Costs for the ORI | | | | |
|---|--------------|--|--|--|
| Item | Cost | | | |
| 100 Latex Disposable Gloves | \$25 | | | |
| 5 Wide Mouth Sample Bottles (1 Liter) | \$20 | | | |
| Large Cooler | \$25 | | | |
| 3 Pairs of Waders | \$150 | | | |
| Digital Camera | \$200 | | | |
| 20 Cans of Spray Paint | \$50 | | | |
| Test Kits or Probes | \$100-\$500 | | | |
| 1 GPS Unit | \$150 | | | |
| 1 Measuring Tape | \$10 | | | |
| 1 First Aid Kit | \$30 | | | |
| Flashlights, Batteries, Labeling tape, Clipboards | \$25 | | | |
| Total | \$785-\$1185 | | | |

| Table 38: Example ORI Costs | | | | |
|--------------------------------|-------------|-------------|--|--|
| Item | Community A | Community B | | |
| Field Equipment ¹ | \$700 | \$785 | | |
| Staff Field Time ² | \$2,000 | \$6,000 | | |
| Staff Office Time ³ | \$3,000 | \$6,000 | | |
| Total | \$5,700 | \$12,785 | | |

¹ From Table 44

 ² Assumes \$25/hour salary (2 person teams in Community A and three- person teams in Community B) and two miles of stream per day.
 ³ Assumes three staff days for each day in field.

Chapter 11: The Outfall Reconnaissance Inventory

Chapter 13: Tracking Discharges To A Source

Once an illicit discharge is found, a combination of methods is used to isolate its specific source. This chapter describes the four investigation options that are introduced below.

Storm Drain Network Investigation

Field crews strategically inspect manholes within the storm drain network system to measure chemical or physical indicators that can isolate discharges to a specific segment of the network. Once the pipe segment has been identified, on-site investigations are used to find the specific discharge or improper connection.

Drainage Area Investigation

This method relies on an analysis of land use or other characteristics of the drainage area that is producing the illicit discharge. The investigation can be as simple as a "windshield" survey of the drainage area or a more complex mapping analysis of the storm drain network and potential generating sites. Drainage area investigations work best when prior indicator monitoring reveals strong clues as to the likely generating site producing the discharge.

On-site Investigation

On-site methods are used to trace the source of an illicit discharge in a pipe segment, and may involve dye, video or smoke testing within isolated segments of the storm drain network.

Septic System Investigation

Low-density residential watersheds may require special investigation methods if they are not served by sanitary sewers and/ or storm water is conveyed in ditches or swales. The major illicit discharges found in low-density development are failing septic systems and illegal dumping. Homeowner surveys, surface inspections and infrared photography have all been effectively used to find failing septic systems in low-density watersheds.

13.1 Storm Drain Network Investigations

This method involves progressive sampling at manholes in the storm drain network to narrow the discharge to an isolated pipe segment between two manholes. Field crews need to make two key decisions when conducting a storm drain network investigation—where to start sampling in the network and what indicators will be used to determine whether a manhole is considered clean or dirty.

Where to Sample in the Storm Drain Network

The field crew should decide how to attack the pipe network that contributes to a problem outfall. Three options can be used:

- Crews can work progressively up the trunk from the outfall and test manholes along the way.
- Crews can split the trunk into equal segments and test manholes at strategic junctions in the storm drain system.
- Crews can work progressively down from the upper parts of the storm drain network toward the problem outfall.

The decision to move up, split, or move down the trunk depends on the nature and land use of the contributing drainage area. Some guidance for making this decision is provided in Table 53. Each option requires different levels of advance preparation. Moving up the trunk can begin immediately when an illicit discharge is detected at the outfall, and only requires a map of the storm drain system. Splitting the trunk and moving down the system require a little more preparation to analyze the storm drain map to find the critical branches to strategically sample manholes. Accurate storm drain maps are needed for all three options. If good mapping is not available, dye tracing

can help identify manholes, pipes and junctions, and establish a new map of the storm drain network.

Option 1: Move up the Trunk

Moving up the trunk of the storm drain network is effective for illicit discharge problems in relatively small drainage areas. Field crews start with the manhole closest to the outfall, and progressively move up the network, inspecting manholes until indicators reveal that the discharge is no longer present (Figure 50). The goal is to isolate the discharge between two storm drain manholes.

| Table 53: Methods to Attack the Storm Drain Network | | | |
|---|--|---|--------------------------|
| Method | Nature of Investigation | Drainage System | Advance Prep Required |
| Follow the discharge up | Narrow source of an individual discharge | Small diameter outfall (< 36") Simple drainage network | No |
| Split into segments | Narrow source of a discharge identified at outfall | Large diameter outfall (> 36"), Complex drainage Logistical or traffic issues may make sampling difficult. | Yes |
| Move down the storm drain | Multiple types of pollution, many suspected problems—possibly due to old plumbing practices or number of NPDES permits | Very large drainage area (> one square mile). | Yes |




Figure 50: Example investigation following the source up the storm drain system

Option 2: Split the storm drain network

When splitting the storm drain network, field crews select strategic manholes at junctions in the storm drain network to isolate discharges. This option is particularly suited in larger and more complex drainage areas since it can limit the total number of manholes to inspect, and it can avoid locations where access and traffic are problematic.

The method for splitting the trunk is as follows:

- 1. Review a map of the storm drain network leading to the suspect outfall.
- 2. Identify major contributing branches to the trunk. The trunk is defined as the largest diameter pipe in the storm drain network that leads directly to the outfall. The "branches" are networks of smaller pipes that contribute to the trunk.
- 3. Identify manholes to inspect at the farthest downstream node of each contributing branch and one immediately upstream (Figure 51).
- 4. Working up the network, investigate manholes on each contributing branch and trunk, until the source is narrowed to a specific section of the trunk or contributing branch.
- 5. Once the discharge is narrowed to a specific section of trunk, select the appropriate on-site investigation method to trace the exact source.

6. If narrowed to a contributing branch, move up or split the branch until a specific pipe segment is isolated, and commence the appropriate on-site investigation to determine the source.

Option 3: Move down the storm drain network

In this option, crews start by inspecting manholes at the "headwaters" of the storm drain network, and progressively move down pipe. This approach works best in very large drainage areas that have many potential continuous and/or intermittent discharges. The Boston Water and Sewer Commission has employed the headwater option to investigate intermittent discharges in complex drainage areas up to three square miles (Jewell, 2001). Field crews certify that each upstream branch of the storm drain network has no contributing discharges before moving down pipe to a "junction manhole" (Figure 52). If discharges are found, the crew performs dye testing to pinpoint the discharge. The crew then confirms that the discharge is removed before moving farther down the pipe network. Figure 53 presents a detailed flow chart that describes this option for analyzing the storm drain network.




Figure 51: Key initial sampling points along the trunk of the storm drain




Figure 52: Storm Drain Schematic Identifying "Juncture Manholes" (Source: Jewell, 2001)




Figure 53: A Process for Following Discharges Down the Pipe (Source: Jewell, 2001)

Dye Testing to Create a Storm Drain Map

As noted earlier, storm drain network investigations are extremely difficult to perform if accurate storm drain maps are not available. In these situations, field crews may need to resort to dye testing to determine the flowpath within the storm drain network. Fluorescent dye is introduced into the storm drain network and suspected manholes are then inspected to trace the path of flow through the network (U.S. EPA, 1990). Two or three member crews are needed for dye testing. One person drops the dye into the trunk while the other(s) looks for evidence of the dye down pipe.

To conduct the investigation, a point of interest or down pipe "stopping point" is identified. Dye is then introduced into manholes upstream of the stopping point to determine if they are connected. The process continues in a systematic manner until an upstream manhole can no longer be determined, whereby a branch or trunk of the system can be defined, updated or corrected. More information on dye testing methods is provided in Section 13.3.

Manhole Inspection: Visual Observations and Indicator Sampling

Two primary methods are used to characterize discharges observed during manhole inspections—visual observations and indicator sampling. In both methods, field crews must first open the manhole to determine whether an illicit discharge is present. Manhole inspections require a crew of two and should be conducted during dry weather conditions.

Basic field equipment and safety procedures required for manhole inspections are outlined

in Table 54. In particular, field crews need to be careful about how they will safely divert traffic (Figure 54). Other safety considerations include proper lifting of manhole covers to reduce the potential for back injuries, and testing whether any toxic or flammable fumes exist within the manhole before the cover is removed. Wayne County, MI has developed some useful operational procedures for inspecting manholes, which are summarized in Table 55.

Table 54: Basic Field Equipment Checklist

- Camera and film or digital camera
- Storm drain, stream, and street maps
- Clipboards
- Reflective safety vests
- Field sheets
- Rubber / latex gloves
- Field vehicle
- Sledgehammer
- First aid kit
- Spray paint
- Flashlight or spotlight
- Tape measures
- Gas monitor and probe
- Traffic cones
- Manhole hook/crow har
- Two-way radios
- Mirror
- Waterproof marker/ pen
- Hand held global positioning satellite (GPS) system receiver (best resolution available within budget, at least 6' accuracy)



Figure 54: Traffic cones divert traffic from manhole inspection area

Table 55: Field Procedure for Removal of Manhole Covers (Adapted from: Pomeroy et al., 1996)

Field Procedures:

- 1. Locate the manhole cover to be removed.
- 2. Divert road and foot traffic away from the manhole using traffic cones.
- 3. Use the tip of a crowbar to lift the manhole cover up high enough to insert the gas monitor probe. Take care to avoid creating a spark that could ignite explosive gases that may have accumulated under the lid. Follow procedures outlined for the gas monitor to test for accumulated gases.
- 4. If the gas monitor alarm sounds, close the manhole immediately. Do not attempt to open the manhole until some time is allowed for gases to dissipate.
- 5. If the gas monitor indicates the area is clear of hazards, remove the monitor probe and position the manhole hook under the flange. Remove the crowbar. Pull the lid off with the hook.
- 6. When testing is completed and the manhole is no longer needed, use the manhole hook to pull the cover back in place. Make sure the lid is settled in the flange securely.
- 7. Check the area to ensure that all equipment is removed from the area prior to leaving.

Safety Considerations:

- 1. Do not lift the manhole cover with your back muscles.
- 2. Wear steel-toed boots or safety shoes to protect feet from possible crushing injuries that could occur while handling manhole covers.
- 3. Do not move manhole covers with hands or fingers.
- 4. Wear safety vests or reflective clothing so that the field crew will be visible to traffic.
- 5. Manholes may only be entered by properly trained and equipped personnel and when all OSHA and local rules a.

Visual Observations During Manhole Inspection

Visual observations are used to observe conditions in the manhole and look for any signs of sewage or dry weather flow. Visual observations work best for obvious illicit discharges that are not masked by groundwater or other "clean" discharges, as shown in Figure 55. Typically, crews progressively inspect manholes in the storm drain network to look for contaminated

flows. Key visual observations that are made during manhole inspections include:

- Presence of flow
- Colors
- Odors
- Floatable materials
- Deposits or stains (intermittent flows)



Figure 55: Manhole observation (left) indicates a sewage discharge. Source is identified at an adjacent sewer manhole that overflowed into the storm drain system (right).

Indicator Sampling

If dry weather flow is observed in the manhole, the field crew can collect a sample by attaching a bucket or bottle to a tape measure/rope and lowering it into the manhole (Figure 56). The sample is then immediately analyzed in the field using probes or other tests to get fast results as to whether the flow is clean or dirty. The most common indicator parameter is ammonia, although other potential indicators are described in Chapter 12.

Manhole indicator data is analyzed by looking for "hits," which are individual samples that exceed a benchmark concentration. In addition, trends in indicator concentrations are also examined throughout the storm drain network.



Figure 56: Techniques to sample from the storm drain

Figure 57 profiles a storm drain network investigation that used ammonia as the indicator parameter and a benchmark concentration of 1.0 mg/L. At both the outfall and the first manhole up the trunk, field crews recorded finding "hits" for ammonia of 2.2 mg/L and 2.3 mg/ L, respectively. Subsequent manhole inspections further up the network revealed one manhole with no flow, and a second with a hit for ammonia (2.4 mg/L). The crew then tracked the discharge upstream of the second manhole, and found a third manhole with a low ammonia reading (0.05 mg/L) and a fourth with a much higher reading (4.3 mg/L). The crew then redirected its effort to sample above the fourth manhole with the 4.3 mg/L concentration, only to find another low reading. Based on this pattern, the crew concluded the discharge source was located between these two manholes, as nothing else could explain this sudden increase in concentration over this length of pipe.

The results of storm drain network investigations should be systematically documented to guide future discharge investigations, and describe any infrastructure maintenance problems encountered. An example of a sample manhole inspection field log is displayed in Figure 58.




Figure 57: Use of ammonia as a trace parameter to identify illicit discharges

| Street: | Manhole Type: |
|--|--|
| | Priminote Type. |
| Inspection: Not Found Surface internal | Sanitary Sewer Storm Drain |
| Follow Up Inspection | High Outlet Lovejoy |
| | Time Since Last Rain: |
| - A | 8 hours 48 – 72 hours > 72 hours |
| Martin Company | 6 HOULS |
| Observations: | |
| | Color of Water: Clear Cloudy Other |
| Flow in Manhole: Yes No Velocity: | Slow Medium Fast Depth of Flow: in |
| Color of Flow: No Flow: Clear Clor | udy Suspended Solids Other |
| Blockages: Yes No Sediment in Mar | nhole: Yes No If Yes: Percent of Pipe Filled: % |
| Floatables: None Sewage Oily Shee | n Foam Other |
| Odor: None Sewage Oil Soa | |
| | |
| Field Testing: | |
| Control of the contro | factants: Yes No Ammonia: Yes No |
| | |
| | aced NoYes Give Date was Captured Not Captured: Common Manholes: |
| Grade: At Above Below Hig | |
| | wejoy: Cover Plate in Place Yes No NA |
| Good Fair Poor Comm | The state of the s |
| Pavement | WWW. |
| Cover | Construction Material: |
| Frame | Brick Precast Other |
| Corbel | |
| Walls | |
| Floor | |
| | |
| | |
| Comments: Manhole Correct as Mapped Yes | No N† |
| Comments: Manhole Correct as Mapped Yes | No Nt |
| Corbel Walls Floor | |
| | |

Figure 58: Boston Water and Sewer Commission Manhole Inspection Log (Source: Jewell, 2001)

Methods to isolate intermittent discharges in the storm drain network

Intermittent discharges are often challenging to trace in the storm drain network, although four techniques have been used with some success.

Sandbags

This technique involves placement of sandbags or similar barriers within strategic manholes in the storm drain network to form a temporary dam that collects any intermittent flows that may occur. Any flow collected behind the sandbag is then assessed using visual observations or by indicator sampling. Sandbags are lowered on a rope through the manhole to form a dam along the bottom of the storm drain, taking care not to fully block the pipe (in case it rains before the sandbag is retrieved). Sandbags are typically installed at junctions in the network to eliminate contributing branches from further consideration (Figure 59). If no flow collects behind the sandbag, the upstream pipe network can be ruled out as a source of the intermittent discharge.

Sandbags are typically left in place for no more than 48 hours, and should only be installed when dry weather is forecast. Sandbags should not be left in place during a heavy rainstorm. They may cause a blockage in the storm drain, or, they may be washed downstream and lost. The biggest downside to sandbagging is that it requires at least two trips to each manhole.

Optical Brightener Monitoring (OBM) Traps

Optical brightener monitoring (OBM) traps, profiled in Chapter 12, can also be used to detect intermittent flows at manhole junctions. When these absorbent pads are anchored in the pipe to capture dry weather flows, they can be used to determine the presence of flow and/or detergents. These OBM traps are frequently installed by lowering them into an open-grate drop inlet or storm drain inlet, as shown in Figure 60. The pads are then retrieved after 48 hours and are observed under a fluorescent light (this method is most reliable for undiluted washwaters).




Figure 59: Example sandbag placement (Source: Jewell, 2001)



Figure 60: Optical Brightener Placement in the Storm Drain (Source: Sargent and Castonguay, 1998)

Automatic Samplers

A few communities have installed automated samplers at strategic points within the storm drain network system that are triggered by small dry weather flows and collect water quality samples of intermittent discharges. Automated sampling can be extremely expensive, and is primarily used in very complex drainage areas that have severe intermittent discharge problems. Automated samplers can pinpoint the specific date and hours when discharges occur, and characterize its chemical composition, which can help crews fingerprint the generating source.

Observation of Deposits or Stains

Intermittent discharges often leave deposits or stains within the storm drain pipe or manhole after they have passed. Thus, crews should note whether any deposits or stains are present in the manhole, even if no dry weather flow is observed. In some cases, the origin of the discharge can be surmised by collecting indicator samples in the water ponded within the manhole sump. Stains and deposits, however, are not always a conclusive way to trace intermittent discharges in the storm drain network.

13.2 Drainage Area Investigations

The source of some illicit discharges can be determined through a survey or analysis of the drainage area of the problem outfall. The simplest approach is a rapid windshield survey of the drainage area to find the potential discharger or generating sites. A more sophisticated approach relies on an analysis of available GIS data and permit databases to identify industrial or other generating sites. In both cases, drainage area investigations are only effective if the discharge observed at an outfall has distinct or unique characteristics that allow crews to quickly ascertain the probable operation or business that is generating it. Often, discharges with a unique color, smell, or offthe-chart indicator sample reading may point to a specific industrial or commercial source. Drainage area investigations are not helpful in tracing sewage discharges, since they are often not always related to specific land uses or generating sites.

Rapid Windshield Survey

A rapid drive-by survey works well in small drainage areas, particularly if field crews are already familiar with its business operations. Field crews try to match the characteristics of the discharge to the most likely type of generating site, and then inspect all of the sites of the same type within the drainage area until the culprit is found. For example, if fuel is observed at an outfall, crews might quickly check every business operation in the catchment that stores or dispenses fuel. Another example is illustrated in Figure 61 where extremely dense algal growth was observed in a small stream during the winter. Field crews were aware of a fertilizer storage site in the drainage area, and a quick inspection identified it as the culprit.







Figure 61: Symptom (left): Discoloration of stream; Diagnosis: Extra hydroseed leftover from an upstream application (middle) was dumped into a storm drain by municipal officials (right).

A third example of the windshield survey approach is shown in Figure 62, where a very thick, sudsy and fragrant discharge was noted at a small outfall. The discharge appeared to consist of wash water, and the only commercial laundromat found upstream was confirmed to be the source. On-site testing may still be needed to identify the specific plumbing or connection generating the discharge.

Detailed Drainage Area Investigations

In larger or more complex drainage areas, GIS data can be analyzed to pinpoint the source of a discharge. If only general land use data exist, maps can at least highlight suspected industrial areas. If more detailed SIC code data are available digitally, the GIS can be used to pull up specific hotspot

operations or generating sites that could be potential dischargers. Some of the key discharge indicators that are associated with hotspots and specific industries are reviewed in Appendix K.

13.3 On-site Investigations

On-site investigations are used to pinpoint the exact source or connection producing a discharge within the storm drain network. The three basic approaches are dye, video and smoke testing. While each approach can determine the actual source of a discharge, each needs to be applied under the right conditions and test limitations (see Table 56). It should be noted that on-site investigations are not particularly effective in finding *indirect* discharges to the storm drain network.





Figure 62: The sudsy, fragrant discharge (left) indicates that the laundromat is the more likely culprit than the florist (right).

| Table 56: Techniques to Locate the Discharge | | |
|--|--|--|
| Technique | Best Applications | Limitations |
| Dye Testing | Discharge limited to a very small drainage area (<10 properties is ideal) Discharge probably caused by a connection from an individual property Commercial or industrial land use | May be difficult to gain access to some properties |
| Video Testing | Continuous discharges Discharge limited to a single pipe segment Communities who own equipment for other investigations | Relatively expensive equipment Cannot capture non-flowing discharges Often cannot capture discharges from pipes submerged in the storm drain |
| Smoke Testing | Cross-connection with the sanitary sewer Identifying other underground sources (e.g., leaking storage techniques) caused by damage to the storm drain | Poor notification to public can cause alarm Cannot detect all illicit discharges |

TIP

The Wayne County Department of the Environment provides excellent training materials on on-site investigations, as well as other illicit discharge techniques. More information about this training can be accessed from their website: http://www.wcdoe.org/Watershed/Programs___Srvcs_/IDEP/idep.htm.

Dye Testing

Dye testing is an excellent indicator of illicit connections and is conducted by introducing non-toxic dye into toilets, sinks, shop drains and other plumbing fixtures (see Figure 63). The discovery of dye in the storm drain, rather than the sanitary sewer, conclusively determines that the illicit connection exists.

Before commencing dye tests, crews should review storm drain and sewer maps to identify lateral sewer connections and how they can be accessed. In addition, property owners must be notified to obtain entry permission. For industrial or commercial properties, crews should carry a letter to document their legal authority to gain



Figure 63: Dye Testing Plumbing (NEIWPCC, 2003)

access to the property. If time permits, the letter can be sent in advance of the dye testing. For residential properties, communication can be more challenging. Unlike commercial properties, crews are not guaranteed access to homes, and should call ahead to ensure that the owner will be home on the day of testing.

Communication with other local agencies is also important since any dye released to the storm drain could be mistaken for a spill or pollution episode. To avoid a costly and embarrassing response to a false alarm,

crews should contact key spill response agencies using a "quick fax" that describes when and where dye testing is occurring (Tuomari and Thomson, 2002). In addition, crews should carry a list of phone numbers to call spill response agencies in the event dye is released to a stream.

At least two staff are needed to conduct dye tests – one to flush dye down the plumbing fixtures and one to look for dye in the downstream manhole(s). In some cases,

three staff may be preferred, with two staff entering the private residence or building for both safety and liability purposes.

The basic equipment to conduct dye tests is listed in Table 57 and is not highly specialized. Often, the key choice is the type of dye to use for testing. Several options are profiled in Table 58. In most cases, liquid dye is used, although solid dye tablets can also be placed in a mesh bag and lowered into the manhole on a rope (Figure 64). If a

Table 57: Key Field Equipment for Dye Testing (Source: Wayne County, MI, 2000)

Maps, Documents

- Sewer and storm drain maps (sufficient detail to locate manholes)
- Site plan and building diagram
- · Letter describing the investigation
- Identification (e.g., badge or ID card)
- Educational materials (to supplement pollution prevention efforts)
- List of agencies to contact if the dye discharges to a stream.
- Name of contact at the facility

Equipment to Find and Lift the Manhole Safely (small manhole often in a lawn)

- Probe
- Metal detector
- Crow bar
- Safety equipment (hard hats, eye protection, gloves, safety vests, steel-toed boots, traffic control equipment, protective clothing, gas monitor)

Equipment for Actual Dye Testing and Communications

- 2-way radio
- Dye (liquid or "test strips")
- High powered lamps or flashlights
- Water hoses
- Camera





Figure 64: Dye in a mesh bag is placed into an upstream manhole (left); Dye observed at a downstream manhole traces the path of the storm drain (right)

longer pipe network is being tested, and dye is not expected to appear for several hours, charcoal packets can be used to detect the dye (GCHD, 2002). Charcoal packets can be secured and left in place for a week or two, and then analyzed for the presence of dye. Instructions for using charcoal packets in dye testing can be accessed at the following website: http://bayinfo.tamug.tamu.edu/gbeppubs/ms4.pdf.

The basic drill for dye tests consists of three simple steps. First, flush or wash dye down the drain, fixture or manhole. Second, pop open downgradient sanitary sewer manholes and check to see if any dye appears. If none is detected in the sewer manhole after an hour or so, check downgradient storm drain manholes or outfalls for the presence of dye. Although dye testing is fairly straightforward, some tips to make testing go more smoothly are offered in Table 59.

| Table 58: Dye Testing Options | | |
|-------------------------------|--|--|
| Product | Applications | |
| Dye Tablets | Compressed powder, useful for releasing dye over time Less messy than powder form Easy to handle, no mess, quick dissolve Flow mapping and tracing in storm and sewer drains Plumbing system tracing Septic system analysis Leak detection | |
| Liquid Concentrate | Very concentrated, disperses quickly Works well in all volumes of flow Recommended when metering of input is required Flow mapping and tracing in storm and sewer drains Plumbing system tracing Septic system analysis Leak detection | |
| Dye Strips | Similar to liquid but less messy | |
| Powder | Can be very messy and must dissolve in liquid to reach full potential Recommended for very small applications or for very large applications where liquid is undesirable Leak detection | |
| Dye Wax Cakes | Recommended for moderate-sized bodies of water Flow mapping and tracing in storm and sewer drains | |
| Dye Wax Donuts | Recommended for large sized bodies of water (lakes, rivers, ponds) Flow mapping and tracing in storm and sewer drains Leak detection | |

Table 59: Tips for Successful Dye Testing (Adapted from Tuomari and Thompson, 2002)

Dye Selection

- · Green and liquid dyes are the easiest to see.
- Dye test strips can be a good alternative for residential or some commercial applications. (Liquid can leave a permanent stain).
- Check the sanitary sewer before using dyes to get a "base color." In some cases, (e.g., a print shop with a permitted discharge to the sanitary sewer), the sewage may have an existing color that would mask a dye.
- Choose two dye colors, and alternate between them when testing multiple fixtures.

Selecting Fixtures to Test

- Check the plumbing plan for the site to isolate fixtures that are separately connected.
- For industrial facilities, check most floor drains (these are often misdirected).
- For plumbing fixtures, test a representative fixture (e.g., a bathroom sink).
- Test some locations separately (e.g., washing machines and floor drains), which may be misdirected.
- If conducting dye investigations on multiple floors, start from the basement and work your way up.
- At all fixtures, make sure to flush with plenty of water to ensure that the dye moves through the system.

Selecting a Sewer Manhole for Observations

- Pick the closest manhole possible to make observations (typically a sewer lateral).
- If this is not possible, choose the nearest downstream manhole.

Communications Between Crew Members

- The individual conducting the dye testing calls in to the field person to report the color dye used, and when it is dropped into the system.
- The field person then calls back when dye is observed in the manhole.
- If dye is not observed (e.g., after two separate flushes have occurred), dye testing is halted until the dye appears.

Locating Missing Dye

- The investigation is not complete until the dye is found. Some reasons for dye not appearing include:
- The building is actually hooked up to a septic system.
- The sewer line is clogged.
- There is a leak in the sewer line or lateral pipe.

Video Testing

Video testing works by guiding a mobile video camera through the storm drain pipe to locate the actual connection producing an illicit discharge. Video testing shows flows and leaks within the pipe that may indicate an illicit discharge, and can show cracks and other pipe damage that enable sewage or contaminated water to flow into the storm drain pipe.

Video testing is useful when access to properties is constrained, such as residential neighborhoods. Video testing can also be expensive, unless the community already owns and uses the equipment for sewer inspections. This technique will not detect all types of discharges, particularly when the illicit connection is not flowing at the time of the video survey.

Different types of video camera equipment are used, depending on the diameter and condition of the storm sewer being tested.

Field crews should review storm drain maps, and preferably visit the site before selecting the video equipment for the test. A field visit helps determine the camera size needed to fit into the pipe, and if the storm drain has standing water.

In addition to standard safety equipment required for all manhole inspections, video testing requires a Closed-Circuit Television (CCTV) and supporting items. Many commercially available camera systems are specifically adapted to televise storm sewers, ranging from large truck or van-mounted systems to much smaller portable cameras. Cameras can be self-propelled or towed. Some specifications to look for include:

- The camera should be capable of radial view for inspection of the top, bottom, and sides of the pipe and for looking up lateral connections.
- The camera should be color.
- Lighting should be supplied by a lamp on the camera that can light the entire periphery of the pipe.

When inspecting the storm sewer, the CCTV is oriented to keep the lens as close as possible to the center of the pipe. The camera can be self-propelled through the pipe using a tractor or crawler unit or it may be towed through on a skid unit (see Figures 65 and 66). If the storm drain



Figure 65: Camera being towed

has ponded water, the camera should be attached to a raft, which floats through the storm sewer from one manhole to the next. To see details of the sewer, the camera and lights should be able to swivel both horizontally and vertically. A video record of the inspection should be made for future reference and repairs (see Figure 67).

Smoke Testing

Smoke testing is another "bottom up" approach to isolate illicit discharges. It works by introducing smoke into the storm drain system and observing where the smoke surfaces. The use of smoke testing to detect illicit discharges is a relatively new application, although many communities have used it to check for infiltration and inflow into their sanitary sewer network. Smoke testing can find improper



Figure 66: Tractor-mounted camera



Figure 67: Review of an inspection video

connections, or damage to the storm drain system (Figure 68). This technique works best when the discharge is confined to the upper reaches of the storm drain network, where pipe diameters are to small for video testing and gaining access to multiple properties renders dye testing infeasible.

Notifying the public about the date and purpose of smoke testing before starting is critical. The smoke used is non-toxic, but can cause respiratory irritation, which can be a problem for some residents. Residents should be notified at least two weeks prior to testing, and should be provided the following information (Hurco Technologies, Inc., 2003):

- Date testing will occur
- Reason for smoke testing
- Precautions they can take to prevent smoke from entering their homes or businesses
- What they need to do if smoke enters their home or business, and any health concerns associated with the smoke
- A number residents can call to relay any particular health concerns (e.g., chronic respiratory problems)

MANHOLE MANHOLE MANHOLE

SMOKE MANHOLE

MANHOLE

SMOKE SMOKE

SMOKE STOPPER

Figure 68: Smoke Testing System Schematic

Program managers should also notify local media to get the word out if extensive smoke testing is planned (e.g., television, newspaper, and radio). On the actual day of testing, local fire, police departments and 911 call centers should be notified to handle any calls from the public (Hurco Technologies, Inc., 2003).

The basic equipment needed for smoke testing includes manhole safety equipment, a smoke source, smoke blower, and sewer plugs. Two smoke sources can be used for smoke testing. The first is a smoke "bomb," or "candle" that burns at a controlled rate and releases very white smoke visible at relatively low concentrations (Figure 69). Smoke bombs are suspended beneath a blower in a manhole. Candles are available in 30 second to three minute sizes. Once opened, smoke bombs should be kept in a dry location and should be used within one year.

The second smoke source is liquid smoke, which is a petroleum-based product that is injected into the hot exhaust of a blower where it is heated and vaporized (Figure 70). The length of smoke production can vary depending on the length of the pipe being




Figure 69: Smoke Candles



Figure 70: Smoke blower

tested. In general, liquid smoke is not as consistently visible and does not travel as far as smoke from bombs (USA Blue Book).

Smoke blowers provide a high volume of air that forces smoke through the storm drain pipe. Two types of blowers are commonly used: "squirrel cage" blowers and direct-drive propeller blowers. Squirrel cage blowers are large and may weigh more than 100 pounds, but allow the operator to generate more controlled smoke output. Direct-drive propeller blowers are considerably lighter and more compact, which allows for easier transport and positioning.

Three basic steps are involved in smoke testing. First, the storm drain is sealed off by plugging storm drain inlets. Next, the smoke is released and forced by the blower through the storm drain system. Lastly, the crew looks for any escape of smoke above-ground to find potential leaks.

One of three methods can be used to seal off the storm drain. Sandbags can be lowered into place with a rope from the street surface. Alternatively, beach balls that have a diameter slightly larger than the drain can be inserted into the pipe. The beach ball is then placed in a mesh bag with a rope attached to it so it can be secured and retrieved. If the beach ball gets stuck in the pipe, it can simply be punctured, deflated and removed. Finally, expandable plugs are available, and may be inserted from the ground surface.

Blowers should be set up next to the open manhole after the smoke is started. Only one manhole is tested at a time. If smoke candles are used, crews simply light the candle, place it in a bucket, and lower it in the manhole. The crew then watches to see where smoke escapes from the pipe. The two most common situations that indicate an illicit discharge are when smoke is seen rising from internal plumbing fixtures (typically reported by residents) or from sewer vents. Sewer vents extend upward from the sewer lateral to release gas buildup, and are not supposed to be connected to the storm drain system.

13.4 Septic System Investigations

The techniques for tracing illicit discharges are different in rural or low-density residential watersheds. Often, these watersheds lack sanitary sewer service and storm water is conveyed through ditches or swales, rather than enclosed pipes. Consequently, many illicit discharges enter the stream as indirect discharges, through surface breakouts of septic fields or through straight pipe discharges from bypassed septic systems.

The two broad techniques used to find individual septic systems—on-site investigations and infrared imagery—are described in this section.

On-Site Septic Investigations

Three kinds of on-site investigations can be performed at individual properties to determine if the septic system is failing, including homeowner survey, surface condition analysis and a detailed system inspection. The first two investigations are rapid and relatively simple assessments typically conducted in targeted watershed areas. Detailed system inspections are a much more thorough investigation of the functioning of the septic system that is conducted by a certified professional. Detailed system inspections may occur at time of sale of a property, or be triggered by poor scores on the rapid homeowner survey or surface condition analysis.

Homeowner Survey

The homeowner survey consists of a brief interview with the property owner to determine the potential for current or future failure of the septic system, and is often done in conjunction with a surface condition analysis.

Table 60 highlights some common questions to ask in the survey, which inquire about resident behaviors, system performance and maintenance activity.

Surface Condition Analysis

The surface condition analysis is a rapid site assessment where field crews look for obvious indicators that point to current or potential production of illicit discharges by the septic system (Figure 71). Some of the key surface conditions to analyze have been described by Andrews *et al.*, (1997) and are described below:

- Foul odors in the yard
- Wet, spongy ground; lush plant growth; or burnt grass near the drain field
- Algal blooms or excessive weed growth in adjacent ditches, ponds and streams
- Shrubs or trees with root damage within 10 feet of the system
- Cars, boats, or other heavy objects located over the field that could crush lateral pipes
- Storm water flowing over the drain field
- Cave-ins or exposed system components
- Visible liquid on the surface of the drain field (e.g., surface breakouts)
- Obvious system bypasses (e.g., straight pipe discharges)

Table 60: Septic System Homeowner Survey Questions

(Adapted from Andrews et al., 1997 and Holmes Inspection Services)

- How many people live in the house?¹
- What is the septic tank capacity?2
- Do drains in the house empty slowly or not at all?
- When was the last time the system was inspected or maintained?
- Does sewage back up into the house through drain lines?
- Are there any wet, smelly spots in the yard?
- Is the septic tank effluent piped so it drains to a road ditch, a storm sewer, a stream, or is it connected to a farm drain tile?

¹ Water usage ranges from 50 to 100 gallons per day per person. This information can be used to estimate the wastewater load from the house (Andrews et. al, 1997).

² The septic tank should be large enough to hold two days' worth of wastewater (Andrews et. al, 1997).





Figure 71: (a) Straight pipe discharge to nearby stream. (b) Algal bloom in a nearby pond. (Sources: a- Snohomish County, WA, b- King County, WA)

Detailed System Inspection

The detailed system inspection is a much more thorough inspection of the performance and function of the septic system, and must be completed by a certified professional. The inspector certifies the structural integrity of all components of the system, and checks the depth of solids in the septic tank to determine if the system needs to be pumped out. The inspector also sketches the system, and estimates distance to groundwater, surface water, and drinking water sources. An example septic system inspection form from Massachusetts can be found at http://www.state.ma.us/dep/brp/wwm/soilsys.htm.

Although not always incorporated into the inspection, dye testing can sometimes point to leaks from broken pipes, or direct discharges through straight pipes that might be missed during routine inspection. Dye can be introduced into plumbing fixtures in the home, and flushed with sufficient running water. The inspector then watches the septic field, nearby ditches, watercourses and manholes for any signs of the dye. The

dye may take several hours to appear, so crews may want to place charcoal packets in adjacent waters to capture dye until they can return later to retrieve them.

Infrared Imagery

Infrared imagery is a special type of photography with gray or color scales that represent differences in temperature and emissivity of objects in the image (www.stocktoninfrared.com), and can be used to locate sewage discharges. Several different infrared imagery techniques can be used to identify illicit discharges. The following discussion highlights two of these: aerial infrared thermography¹³ and color infrared aerial photography.

Infrared Thermography

Infrared thermography is increasingly being used to detect illicit discharges and failing septic systems. The technique uses the temperature difference of sewage as a marker to locate these illicit discharges. Figure 72 illustrates the thermal difference

¹³ Infrared thermography is also being used by communities such as Mecklenburg County and the City of Charlotte in NC to detect illicit discharges at outfalls.

between an outfall discharge (with a higher temperature) and a stream.

The equipment needed to conduct aerial infrared thermography includes an aircraft (plane or helicopter); a high-resolution, large format, infrared camera with appropriate mount; a GPS unit; and digital recording equipment. If a plane is used, a higher resolution camera is required since it must operate at higher altitudes. Pilots should be experienced since flights take place at night, slowly, and at a low altitude. The camera may be handheld, but a mounted camera will provide significantly clearer results for a larger area. The GPS can be combined with a mobile mapping program and a video encoder-decoder that encodes and displays the coordinates, date, and time (Stockton, 2000). The infrared data are analyzed after the flight by trained analysts to locate suspected discharges, and field crews then inspect the ground-truthed sites to confirm the presence of a failing septic system.

Late fall, winter, and early spring are typically the best times of year to conduct these investigations in most regions of the

FEB16/02,0231;25,302,-05,9/00,02108F 0111,3509,897N,08050,227W, 48KTS,220

Figure 72: Aerial thermography showing sewage leak

country. This allows for a bigger difference between receiving water and discharge temperatures, and interference from vegetation is minimized (Stockton, 2004b). In addition, flights should take place at night to minimize reflected and direct daylight solar radiation that may adversely affect the imagery (Stockton, 2004b).

Color Infrared Aerial Photography

Color infrared aerial photography looks for changes in plant growth, differences in soil moisture content, and the presence of standing water on the ground to primarily identify failing septic systems (Figure 73).

The Tennessee Valley Authority (TVA) uses color infrared aerial photography to detect failing septic systems in reservoir watersheds. Local health departments conduct follow-up ground-truthing surveys to determine if a system is actually failing (Sagona, 1986). Similar to thermography, it is recommended that flights take place at night, during leaf-off conditions, or when the water table is at a seasonal high (which is when most failures typically occur (U.S. EPA, 1999).



Figure 73: Dead vegetation and surface effluent are evidence of a septic system surface failure.

(Source: U.S. EPA, 1999)

13.5 The Cost to Trace Illicit Discharge Sources

Tracing illicit discharges to their source can be an elusive and complex process, and precise staffing and budget data are difficult to estimate. Experience of Phase I NPDES communities that have done these investigations in the past can shed some light on cost estimates. Some details on unit costs for common illicit discharge investigations are provided below.

Costs for Dye, Video, and Smoke Testing

The cost of smoke, dye, and video testing can be substantial and staff intensive, and often depend on investigation specific factors, such as the complexity of the drainage network, density and age of buildings, and complexity of land use. Wayne County, MI, has estimated the cost of dye testing at \$900 per facility. Video testing costs range from \$1.50 to \$2.00 per foot, although this increases by \$1.00 per foot if pipe cleaning is needed prior to testing.

Table 61 summarizes the costs of start-up equipment for basic manhole entry and inspection, which is needed regardless of which type of test is performed. Tables 62 through 64 provide specific equipment costs for dye, video and smoke testing, respectively.

| Table 61: Common Field Equipment Needed for Dye, Video, and Smoke Testing | | |
|---|---------------------|--|
| Item | Cost | |
| 1 Digital Camera | \$200 | |
| Clipboards, Pens, Batteries | \$25 | |
| 1 Field vehicle | \$15,000 - \$35,000 | |
| 1 First aid kit | \$30 | |
| 1 Spotlight | \$40 | |
| 1 Gas monitor and probe | \$900 - \$2,100 | |
| 1 Hand-held GPS Unit | \$150 | |
| 2 Two-way radios | \$250 - \$750 | |
| 1 Manhole hook | \$80 - \$130 | |
| 1 Mirror | \$70 - \$130 | |
| 2 Reflective safety vests | \$40 | |
| Rubber/latex gloves (box of 100) | \$25 | |
| 1 Can of Spray Paint | \$5 | |
| 4 Traffic Cones | \$50 | |

| Table 62: Equipment Costs for Dye Testing | | | |
|---|-------------------------|--|--|
| Product | Water Volume | Cost | |
| Dye Strips | 1 strip/500 gallons | \$75 – \$94 per 100 strips | |
| Dye Tablets | 0 - 50,000 gallons | \$40 per 200 tablets | |
| Liquid Concentrate (Rhodamine WT) | 0 – 50,000 gallons | \$80 – \$90 per gallon \$15 – \$20 per pint | |
| Powder | 50,000 + gallons | \$77 per lb | |
| Dye Wax Cakes | 20,000 - 50,000 gallons | \$12 per one 1.25 ounce cake | |
| Dye Wax Donuts | 50,000 + gallons | \$104 – \$132 per 42 oz. donut | |

Price Sources:

Aquatic Eco-Systems http://www.aquaticeco.com/ Cole Parmer http://www.coleparmer.com USA Blue Book http://www.usabluebook.com

| Table 63: Equipment Costs for Video Testing | | |
|---|--|--|
| Equipment | Cost | |
| GEN-EYE 2 [™] B&W Sewer Camera with VCR & 200' Push Cable | \$5,800 | |
| 100' Push Rod and Reel Camera for 2" – 10" Pipes | \$5,300 | |
| 200' Push Rod and Reel Camera for 8" – 24" Pipes | \$5,800 | |
| Custom Saturn III Inspection System 500' cable for 6-16" Lines | \$32,000 (\$33,000 with 1000 foot cable) | |
| OUTPOST | | |
| Box with build-outGeneratorWashdown system | \$6,000 \$2,000 \$1,000 | |
| Video Inspection Trailer • 7'x10' trailer & build-out • Hardware and software package • Incidentals | \$18,500 \$15,000 \$5,000 | |
| Sprinter Chassis Inspection Vehicle Van (with build-out for inspecting 6" – 24" pipes) Crawler (needed to inspect pipes >24") Software upgrade (optional but helpful for extensive pipe systems) | \$130,000 \$18,000 \$8,000 | |
| Sources: USA Blue Book and Envirotech | | |

| Table 64: Equipment Costs for Smoke Testing | | | |
|---|-------------------------|--|--|
| Equipment Cost | | | |
| Smoke Blower | \$1,000 to \$2,000 each | | |
| Liquid Smoke | \$38 to \$45 per gallon | | |
| Smoke Candles, 30 second (4,000 cubic feet) | \$27.50 per dozen | | |
| Smoke Candles, 60 Second (8,000 cubic feet) | \$30.50 per dozen | | |
| Smoke Candles, 3 Minute (40,000 cubic feet) \$60.00 per dozen | | | |
| Sources: Hurco Tech, 2003 and Cherne Industries, 2003 | | | |

Costs for Septic System Investigations

Most septic system investigations are relatively low cost, but factors such as private property access, notification, and the total number of sites investigated can increase costs. Unit costs for the three major septic system investigations are described below.

Homeowner Survey and Surface Condition Analysis

Both the homeowner survey and the surface condition analysis are relatively low cost investigation techniques. Assuming that a staff person can investigate one home per hour, the average cost per inspection is approximately \$25. A substantial cost savings can be realized by using interns or volunteers to conduct these simple investigations.

Detailed System Inspection

Septic system inspections are more expensive, but a typical unit cost is about \$250, and may also include an additional cost of pumping the system, at roughly \$150, if pumping is required to complete the inspection (Wayne County, 2003). This cost is typically charged to the homeowner as part of a home inspection.

Aerial Infrared Thermography

The equipment needed to conduct aerial infrared thermography is expensive; cameras alone may range from \$250,000 to \$500,000 (Stockton, 2004a). However, private contractors provide this service. In general, the cost to contract an aerial infrared thermography investigation depends on the length of the flight (flights typically follow streams or rivers); how difficult it will be to fly the route; the number of heat anomalies expected to be encountered; the expected post-flight processing time (typically, four to five hours of analysis for every hour flown); and the distance of the site from the plane's "home" (Stockton, 2004a). The cost range is typically \$150 to \$400 per mile of stream or river flown, which includes the flight and post-flight analyses (Stockton, 2004a).

As an alternative, local police departments may already own an infrared imaging system that may be used. For instance, the Arkansas Department of Health used a state police helicopter with a Forward Looking Infrared (FLIR) imaging system, GPS, video equipment, and maps (Eddy, 2000). The disadvantage to this is that the equipment may not be available at optimal times to conduct the investigation. In addition, infrared imaging equipment used by police departments may not be sensitive enough to detect the narrow range of temperature difference (only a few degrees) often expected for sewage flows (Stockton, 2004a).

EPA New England Bacterial Source Tracking Protocol

Draft – January 2012

Purpose

This document provides a common framework for EPA New England ("EPA-NE") staff to develop and implement bacterial source tracking sample events, and provides a recommended approach to watershed association, municipal, and State personnel. Adopted from Boston Water and Sewer Commission ("BWSC") (2004), Pitt (2004), and based upon fieldwork conducted and data collected by EPA-NE, the protocol relies primarily on visual observations and the use of field test kits and portable instrumentation during dry and wet weather to complete a screening-level investigation of stormwater outfall discharges or flows within the drainage system. When necessary, the addition of more conclusive chemical markers may be included. The protocol is applicable to most typical Municipal Separate Storm Sewer Systems ("MS4s") and smaller tributary streams. The smaller the upstream catchment area and/or more concentrated the flow, the greater the likelihood of identifying an upstream wastewater source.

Introduction

The protocol is structured into several phases of work that progress through investigation planning and design, laboratory coordination, sample collection, and data evaluation. The protocol involves the concurrent collection and analyses of water samples for surfactants, ammonia, total chlorine, and bacteria. When more precise confirmation regarding the presence or absence of human sanitary sewage is necessary, and laboratory capacity is available, the additional concurrent collection of samples for select Pharmaceutical and Personal Care Product ("PPCP") analysis is advised. When presented with a medium to large watershed or numerous stormwater outfalls, the recommended protocol is the screening of all outfalls using the surfactant, ammonia, total chlorine, and bacterial analyses, in addition to a thorough visual assessment. The resulting data and information should then be used to prioritize and sample a subset of outfalls for all parameters, including PPCP compounds and additional analyses as appropriate. Ideally, screening-level analyses can be conducted by state, municipal, or local watershed association personnel, and a prioritized sub-set of outfalls can be sampled through a commercial laboratory or by EPA-NE using more advanced confirmatory techniques.

Step I – Reconnaissance and Investigation Design

Each sample event should be designed to answer a specific problem statement and work to identify the source of contamination. Any relevant data or reports from State, municipal, or local watershed associations should be reviewed when selecting sample locations. Aerial photography, mapping services, or satellite imagery resources are available free to the public through the internet, and offer an ideal way to pre-select locations for either field verification or sampling.

Sample locations should be selected to segregate outfall sub-catchment areas or surface waters into meaningful sections. A common investigative approach would be the identification of a

specific reach of a surface water body that is known to be impaired for bacteria. Within this specific reach, stormwater outfalls and smaller tributary streams would be identified by desktop reconnaissance, municipal outfall mapping, and field investigation when necessary. Priority outfalls or areas to field verify the presence of outfalls should be selected based on a number of factors, including but not limited to the following: those areas with direct discharges to critical or impaired waters (e.g. water supplies, swimming beaches); areas served by common/twin-invert manholes or underdrains; areas with inadequate levels of sanitary sewer service, Sanitary Sewer Overflows ("SSOs") or the subject of numerous/chronic sanitary sewer customer complaints; formerly combined sewer areas that have been separated; culverted streams, and; outfalls in densely populated areas with older infrastructure. Pitt (2004) provides additional detailed guidance.

When investigating an area for the first time, the examination of outfalls in dry-weather is recommended to identify those with dry-weather flow, odor, and the presence of white or gray filamentous bacterial growth that is common (but not exclusively present) in outfalls contaminated with sanitary. For those outfalls with dry-weather flow and no obvious signs of contamination, one should never assume the discharge is uncontaminated. Sampling by EPA-NE staff has identified a number of outfalls with clear, odorless discharges that upon sampling and analyses were quite contaminated. Local physical and chemical conditions, in addition to the numerous causes of illicit discharges, create outfall discharges that can be quite variable in appearance. Outfalls with no dry-weather flow should be documented, and examined for staining or the presence of any obvious signs of past wastewater discharges downstream of the outfall.

As discussed in BWSC (2004), the protocol may be used to sample discreet portions of an MS4 sub-catchment area by collecting samples from selected junction manholes within the stormwater system. This protocol expands on the BWSC process and recommends the concurrent collection of bacteria, surfactant, ammonia, and chlorine samples at each location to better identify and prioritize contributing sources of illicit discharges, and the collection of PPCP compounds when more conclusive source identification is necessary.

Finally, as discussed further in Step IV, application of this sampling protocol in wet-weather is recommended for most outfalls, as wet-weather sampling data may indicate a number of illicit discharge situations that may not be identified in dry weather.

Step II - Laboratory Coordination

All sampling should be conducted in accordance with a Quality Assurance Project Plan ("QAPP"). A model QAPP is included as Attachment 1. While the QAPP details sample collection, preservation, and quality control requirements, detailed coordination with the appropriate laboratory staff will be necessary. Often sample events will need to be scheduled well in advance. In addition, the sampling team must be aware of the strict holding time requirements for bacterial samples – typically samples analysis must begin within 6 hours of sample collection. For sample analyses conducted by a commercial laboratory, appropriate coordination must occur to determine each facilities respective procedures and requirements.

The recommendations in this protocol are based on the use of a currently unpublished EPA-NE modification to *EPA Method 1694 – Pharmaceuticals and Personal Care Products in Water, Soil, Sediment, and Biosolids by HPLC/MS/MS.* Several commercial laboratories may offer Method 1694 capability. EPA-NE recommends those entities wishing to utilize a contract laboratory for PPCP analyses ensure that the laboratory will provide quantitative analyses for acetaminophen, caffeine, cotinine, carbamazepine, and 1,7-dimethylexanthine, at Reporting Limits similar to those used by EPA-NE (See Attachment 2). Currently, the EPA-NE laboratory has limited capacity for PPCP sampling, and any proposed EPA-NE PPCP sample events must be coordinated well in advance with the appropriate staff.

Step III – Sample Collection

Once a targeted set of outfalls has been selected, concurrent sampling and analyses for surfactants, ammonia, and total chlorine (which can all be done through the use of field kits), in addition to bacteria (via laboratory analysis) should be conducted. When numerous outfalls with dry-weather flow exist, sample locations should be prioritized according to the criteria mentioned above. In addition, field screening using only the field kits may occur during the field reconnaissance. However, it must be emphasized that the concurrent sampling and analyses of bacteria, surfactant, ammonia, and total chlorine parameters is the most efficient and cost-effective screening method.

When first observed, the physical attributes of each outfall or sampling location should be noted for construction materials, size, flow volume, odor, and all other characteristics listed on the data collection form (Attachment 3). In addition, GPS coordinates should be collected and a photograph of the sample location taken. Whenever possible, the sampling of storm drain outfalls should be conducted as close to the outfall opening as possible. Bacterial samples should be collected first, with care to not disturb sediment materials or collect surface debris/scum as best possible. A separate bottle is used to collect a single water sample from which aliquots will be analyzed for surfactants, ammonia, and total chlorine. A sample for PPCP analysis is recommended to be collected last, as the larger volume required and larger bottle size may cause some sediment disturbance in smaller outfalls or streams. If necessary, a second smaller, sterile and pre-cleaned sampling bottle may be used to collect the surface water which can then be poured into the larger PPCP bottle. Last, a properly calibrated temperature/specific conductance/salinity meter should be used to record all three parameters directly from the stream or outfall. When flow volume or depth is insufficient to immerse the meter probe, a clean sample bottle may be utilized to collect a sufficient volume of water to immerse the probe. In such instances, meter readings should be taken immediately.

As soon as reasonably possible, sample aliquots from the field kit bottle should be analyzed. When concurrent analyses are not possible, ammonia and chlorine samples should be processed first, followed by surfactant analysis, according to each respective Standard Operating Procedure as appropriate based on the particular brand and type of field test kit being used. All waste from the field test kits should be retained and disposed of according to manufacture instructions. Where waste disposal issues would otherwise limit the use of field kits, EPA-NE recommends

that, at a minimum, ammonia test strips with a Reporting Limit below 0.5 mg/L be utilized. Such test strips typically are inexpensive and have no liquid reagents associated with their use. Results should be recorded, samples placed in a cooler on ice, and staff should proceed to the next sample location.

Upon completion of sampling and return to the laboratory, all samples will be turned over to the appropriate sample custodian(s) and accompanied by an appropriate Chain-of-Custody ("COC") form.

Step IV – Data Evaluation

Bacterial results should be compared to the applicable water quality standards. Surfactant and ammonia concentrations should be compared to the thresholds listed in Table 1. Evaluation of the data should include a review for potential positive results due to sources other than human wastewater, and for false negative results due to chemical action or interferences. In the EPA-NE region, field sampling has indicated that the biological breakdown of organic material in historically filled tidal wetlands may cause elevated ammonia readings, as can the discharge from many landfills. In addition, salinity levels greater than 1 part per thousand may cause elevated surfactant readings, the presence of oil may likewise indicate elevated levels, and fine suspended particulate matter may cause inconclusive surfactant readings (for example, the indicator ampule may turn green instead of a shade of blue). Finally, elevated chlorine from leaking drinking water infrastructure or contained in the illicit wastewater discharge may inhibit bacterial growth and cause very low bacterial concentrations. Any detection of total chlorine above the instrument Reporting Limit should be noted.

Table 1 – Freshwater Water Quality Criteria, Threshold Levels, and Example Instrumentation ¹

| Analyte/ Indicator | Threshold Levels/ Single Sample ³ | Instrumentation |
|----------------------------|---|--|
| E. coli ² | 235 cfu/100ml | Laboratory via approved method |
| Enterococci ² | 61 cfu/100ml | Laboratory via approved method |
| Surfactants (as MBAS) | $\geq 0.25 \text{ mg/l}$ | MBAS Test Kit (e.g. CHEMetrics K-9400) |
| Ammonia (NH ₃) | ≥ 0 .5 mg/l | Ammonia Test Strips (e.g. Hach brand) |
| Chlorine | > Reporting Limit | Field Meter (e.g. Hach Pocket Colorimeter II) |
| Temperature | See Respective State Regulations | Temperature/Conductivity/Salinity Meter (e.g. YSI Model 30) |

The mention of trade names or commercial products does not constitute endorsement or recommendation for use by the U.S. EPA

² 314 CMR 4.00 MA - Surface Water Quality Standards - Class B Waters.

³ Levels that may be indicative of potential wastewater or washwater contamination

Once dry-weather data has been examined and compared to the appropriate threshold values, outfalls or more discreet reaches of surface water can be selected for sampling or further investigation. Wet-weather sampling is also recommended for all outfalls, in particular for those that did not have flow in dry weather or those with dry-weather flow that passed screening thresholds. Wet-weather sampling will identify a number of situations that would otherwise pass unnoticed in dry weather. These wet-weather situations include, but are not limited to the following: elevated groundwater that can now cause an exchange of wastewater between cracked or broken sanitary sewers, failed septic systems, underdrains, and storm drains; increased sewer volume that can exfiltrate through cracks in the sanitary piping; increased sewer volume that can enter the storm drain system in common manholes or directly-piped connections to storm drains; areas subject to capacity-related SSO discharges, and; illicit connections that are not carried through the storm drain system in dry-weather.

Step V - Costs

Use of field test kits and field instruments for a majority of the analytical parameters allows for a significantly reduced analytical cost. Estimated instrument costs and pro-rated costs per 100 samples are included in Table 2. The cost per 100 samples metric allows averaged costs to account for reagent refills that are typically less expensive as they do not include the instrument cost, and to average out the initial capital cost for an instrument such as a temperature/conductivity/salinity meter. For such capital costs as the meters, the cost over time will continue to decrease.

Table 2 – Estimated Field Screening Analytical Costs ¹

| Analyte/ Indicator | Instrument or Meter ² | Instrument or Meter Cost/No. of Samples | Cost per Sample (Based on 100 Samples) ³ |
|-------------------------------------|----------------------------------|---|---|
| Surfactants (as MBAS) | Chemetrics K- 9400 | \$77.35/20 samples (\$58.08/20 sample refill) | \$3.09 |
| Ammonia (NH ₃) | Hach brand 0 – 6 mg/l | \$18.59/25 samples | \$0.74 |
| Total Chlorine | Hach Pocket Colorimeter II | \$389/100 samples (\$21.89 per 100 sample refill) | \$3.89 |
| Temperature/ Conductivity/ Salinity | YSI | \$490 (meter and cable probe) | \$4.90 |

Estimated costs as of February 2011

From Table 2, the field analytical cost is approximately \$13 per outfall. Typical bacterial analyses costs can vary depending on the analyte, method, and total number of samples to be

The mention of trade names or commercial products does not constitute endorsement or recommendation for use by the U.S. EPA

One-time meter costs and/or refill kits will reduce sample costs over time

performed by the laboratory. These bacterial analyses costs can range from \$20 to \$60. Therefore, the analytical cost for a single outfall, based on the cost per 100 samples, ranges from \$33 to \$73. As indicated above, these costs will decrease slightly over time due to one-time capitals costs for the chlorine and temperature/conductivity/salinity meters.

Step VI – Follow-Up

Once all laboratory data has been reviewed and determined final in accordance with appropriate quality assurance controls, results should be reviewed with appropriate stakeholders to determine next steps. Those outfalls or surface water segments that fail to meet the appropriate water quality standard, and meet or exceed the surfactant and ammonia threshold values, in the absence of potential interferences mentioned in Step IV, indicate a high likelihood for the presence of illicit connections upstream in the drainage system or surface water. Whereas illicit discharges are quite variable in nature, the exceedance of the applicable water quality standard and only the ammonia or surfactant threshold value may well indicate the presence of an illicit connection. When available, the concurrent collection and analyses of PPCP data can greatly assist in confirming the presence of human wastewater. However, such data will not be available in all instances, and the collective data set and information regarding the physical characteristics of each sub-catchment or surface water reach should be used to prioritize outfalls for further investigation. As warranted, data may be released to the appropriate stakeholders, and should be accompanied by an explanation of preliminary findings. Release of EPA data should be fully discussed with the case team or other appropriate EPA staff.

References Cited

Boston Water & Sewer Commission, 2004, A systematic Methodology for the Identification and Remediation of Illegal Connections. 2003 Stormwater Management Report, chap. 2.1.

Pitt, R. 2004 Methods for Detection of Inappropriate Discharge to Storm Drain Systems. Internal Project Files. Tuscaloosa, AL, in The Center for Watershed Protection and Pitt, R., Illicit Discharge Detection and Elimination: A Guidance Manual for Program Development and Technical Assessments: Cooperative Agreement X82907801-0, U.S. Environmental Protection Agency, variously paged. Available at: http://www.cwp.org.

Instrumentation Cited (Manufacturer URLs)

MBAS Test Kit - CHEMetrics K-9400: http://www.chemetrics.com/Products/Deterg.htm

Portable Colorimeter – Hach Pocket Colorimeter II: http://www.hach.com/

Ammonia (Nitrogen) Test Strips: http://www.hach.com/

Portable Temperature/Conductivity/Salinity Meter: YSI Model 30: http://www.vsi.com/productsdetail.php?30-28

Disclaimer: The mention of trade names or commercial products in this protocol does not constitute endorsement or recommendation for use by the U.S. EPA.

Stormwater Monitoring Program QAPP 5/17/12 Revision 1 Page 1 of 7

Stormwater Monitoring Quality Assurance Project Plan 2012-2017

RFA#

Sampling Plan Acceptance

| EPA | |
|---|-------|
| OES Enforcement and Project Manager/Coordinator | |
| J. W. W. B. | |
| Signature: | Date: |
| EPA | |
| OEME Project Managers/Coordinator | |
| 3 6 | |
| Signature: | Date: |
| EPA | |
| OEME QA Officer | |
| | |
| Signature: | Date: |
| EPA | |
| Chemistry Team Lead | |
| | |
| Signature | Date |

Stormwater Monitoring Program QAPP 5/17/12 Revision 1 Page 2 of 7

1.0 Background

U.S. EPA Administrative Order 5360.1 requires that "all projects involving environmental monitoring performed by or for the U.S. EPA shall not be undertaken without an adequate Quality Assurance Project Plan (QAPP)." The purpose of this document is to describe the process used to develop, select, manage, and finalize stormwater monitoring projects. In describing this process, quality assurance goals and methods will be established, thus ensuring that the overall program and each monitoring project will meet or exceed EPA requirements for quality assurance.

The objective of these projects will be to collect data that is usable by EPA OES enforcement staff for enforcement actions and information requests. The primary focus of this project will be on urban water stormwater outfalls in the New England Region watersheds.

2.0 Sampling overview

Monitoring will be conducted on pre-scheduled days with the Laboratory. Samples will be retrieved from surface water, in stream or outfalls at suspected hotspots or areas that need further delineation. Sample sites will be located using GPS, with an accuracy goal of ± 1 meter and PDOP less than 6. Less accurate GPS reading or coordinates from maps will be accepted when site or other conditions do not allow + 1 meter accuracy.

The primary focus of this sampling will be used to identify illegal discharges.

Results from the sampling will be used by EPA enforcement staff for enforcement purposes. For this project, sampling will be conducted according to EPA's Ambient Water Sampling SOP (Table 3). Volunteers and watershed association staff may assist in sampling. All procedures will be followed that are specified in Table 3. Parameter to be sampled will be predetermined by enforcement (OES) and OEME staff, based on data needs.

A. Locations

Site locations will be determined from field or desktop reconnaissance by project staff. Sample analyses will be predetermined based on conditions known about the sampling location prior to sampling. These may include data from previous sampling or from data collected from Mass DEP or local watershed associations. Any of the parameters listed in table 2 may be analyzed.

B. Analytical Methods and Reporting limits

Sample analyses will be conducted by EPA Laboratories.

This effort will test and compare the most appropriate analytical methods including, but not limited to; laboratory analysis, test kits and field analysis to determine the most effective and cost-efficient outfall and in-stream sampling approach.

Multiple and repeated testing will occur at each location to compare different method for identifying sewage contamination.

PPCPs, E.coli and enterococcus will be analyzed by EPA's Laboratory. Surfactants, ammonia, total chlorine will be analyzed with field test kits. Potential additional laboratory analyses include nitrogen (nitrate/nitrite), TSS, BOD, surfactants, ammonia and TPH. The Laboratory used

Stormwater Monitoring Program QAPP 5/17/12 Revision 1 Page 3 of 7

for each sampling event will be determined prior to sampling by the OEME Project Manager based on required analyses Laboratory availability and contract funds available.

Where available, a known concentration sample will be used to evaluate the performance of each test method. The known concentration sample will be processed in the field and Laboratory as a routine sample. The analyst or field technician will not know the concentration of the sample prior to analyzing and reporting the sample result. Sampling for PPCP testing will be done using extreme care not to contaminate the sample. No caffeine products should be consumed prior to sampling.

Table 1: Parameter specifications

| Description (1-1) | D | II -1 3! 4! |
|--------------------------------------|-------------------------|--------------------------|
| Parameter (lab - equipment) | Preservation | Holding time |
| PH | None | Immediate |
| Temperature | None | Immediate |
| Sp Cond | None | Immediate |
| DO | None | Immediate |
| Total Phosphorus (EPA) | H_2SO_4 (pH <2) + Ice | 28 days |
| TSS (EPA) | Ice | 7 days |
| TSS (Alpha) | Ice | 7 days |
| BOD (Alpha) | Ice | 48 hours |
| Surfactants (Alpha) | Ice | 48 hours |
| Surfactants (field kit – Chemetrics) | None | Immediate |
| Ammonia (alpha) | H_2SO_4 (pH <2) + Ice | 28 days |
| Ammonia (test strips) | None | Immediate |
| | Ice | 7 Days to extraction |
| TPH Petroleum ID (alpha) | | 40 days after extraction |
| E. Coli (EPA) | Ice | 6 hrs to lab |
| Enterococcus (EPA) | Ice | 6 hrs to lab |
| | Ice | 7 day to extraction |
| PPCP | (acidified in Lab) | 40 days after extraction |
| Chlorine (Field kit – Hach) | None | Immediate |

Stormwater Monitoring Program QAPP 5/17/12 Revision 1 Page 4 of 7

Table 2: Analytical References and Quality Control Goals

| Table 2: Analytical References and Quality Control Goals | | | | | |
|--|-----------------------|----------------------|-------------------------|----------------------|--------------|
| | | Water Quality | | | |
| | | Criteria or | | | |
| | | Guidelines | Quality Assurance Goals | | |
| | Reporting | | | | |
| (lab- equipment) | | (MA or EPA) | Precision | | Completeness |
| PH | | 6.5 - 8.3 | 0.02 unit | <u>+</u> 0.3 units | 90% |
| Temperature | 0 to +40°C | 28.3°C | 0.1 °C | <u>+</u> 0.15°C | 90% |
| | 0 to 100 | | | <u>+</u> 10% cal std | |
| Sp Cond | mS/cm | NA | 5 uS/cm | (µS/cm) | 90% |
| | 0.5mg/l to | ≥5 mg/l , | | | |
| DO | Sat | ≥60% saturation | 0.02mg/l | \pm .5 mg/l | 90% |
| Total Phosphorus | | | Field dup 30% | | |
| (EPA) | 5.0 ug/l | NA | RPD | MS 70-130% | 90% |
| | | | Field dup 30% | | |
| TSS (EPA) | 5mg/L | NA | RPD | See SOP | |
| | | | Field dup 30% | | |
| TSS (Alpha) | 5 mg/L | NA | RPD | See SOP | 90% |
| | | | Field dup 30% | | |
| BOD (Alpha) | 2 mg/L | NA | RPD | See SOP | 90% |
| Surfactants (field | | | Field dup 30% | | |
| kit – Chemetrics) | 0.25 mg/L^1 | 0.25 mg/L | RPD | TBD | 90% |
| Ammonia (test | | | Field dup 30% | | |
| strips) | 0.25 mg/L^1 | 1.0 mg/L | RPD | TBD | 90% |
| TPH Petroleum | | | Field dup 30% | | |
| ID (alpha) | Variable | NA | RPD | See SOP | |
| | | <=126 col./100 ml* | +100 col/100ml or | | |
| E. Coli (EPA) | 4 col./ 100 ml | <= 235 col./100 ml | 30% RPD | N/A | 90% |
| Enterococcus | | <=33 col./100 ml* | +100 col/100ml or | | |
| (EPA) | 1 col/100ml | <= 61 col./100 ml | 30% RPD | See SOP | 90% |
| | | | Field dup 50% | | |
| PPCP | TBD | NA | RPD | TBD | 90% |
| Chlorine (Field | | | Field dup 30% | | |
| | 0.02 mg/l | NA | RPD | TBD | 90% |

Note

^{*}Geometric mean Criteria

TBD = To be determined, Field methods and some colorimeter methods do not have accuracy criteria determined.

¹ Needs field verification to confirm

Attachment 1

Stormwater Monitoring Program QAPP 5/17/12 Revision 1 Page 5 of 7

Table 3: Field and Laboratory References

| able 3: Field and Laboratory References | | | | | | | | |
|---|-----------------------------|--------------------------------|--|--|--|--|--|--|
| | Analytical Method | | | | | | | |
| Parameter | Reference | SOP reference | | | | | | |
| | Field References- | | | | | | | |
| | 5/2005 | | | | | | | |
| рН | | | | | | | | |
| Conductivity | | | | | | | | |
| Temperature | | | | | | | | |
| dissolved oxygen | n/a | ECASOP-YSISondes9 | | | | | | |
| Ambient water samples | n/a | ECASop-Ambient Water Sampling2 | | | | | | |
| Chain of custody of samples | n/a | EIASOP-CHAINOFCUST | | | | | | |
| Sample login, tracking, disposition | n/a | EIASOP-ADMLOG14 | | | | | | |
| | Lab. References- 5/ 2005 | | | | | | | |
| Total Phosphorus (EPA) | EPA 365.3 | EIASOP-INGTP8 | | | | | | |
| TSS (EPA) | EPA 160.2 | EIASOP-INGTSS-TDS-VRES5 | | | | | | |
| TSS (Alpha) | EPA 160.2,SM2540D | SOP/07-29 | | | | | | |
| BOD (Alpha) | EPA 405.1,SM5210B | SOP/07-13 | | | | | | |
| Surfactants (field kit – Chemetrics) | Chemetrics | Draft | | | | | | |
| Ammonia (test strips) | Hach | Draft | | | | | | |
| TPH Petroleum ID (alpha) | 8015B (M) | 0-017 | | | | | | |
| E. Coli (EPA) | SM9230 | ECASOP- TC/EC Colilert2 | | | | | | |
| Enterococcus (EPA) | SM9230 | ECASOP-Enterolert1 | | | | | | |
| PPCP | EPA 1694 | TBD | | | | | | |
| Chlorine (Field kit – Hach) | Hach | TBD | | | | | | |

^{*}Specific conductance is the only parameter identified as non critical

Bottle list

Table 4: Bottle Sampling List

| Table 4: Dottle Sampling Li | St | |
|-----------------------------|--------------------------------------|-------------------------|
| Parameter (lab - equipment | Bottle | Preservation |
| | Primary analyses | |
| E. Coli (EPA) | (2) 120ml or 250ml sterile | Ice |
| Enterococcus (EPA) | | Ice |
| PPCP | 1 Liter Amber | Ice (acidified in Lab) |
| | Optional analyses | |
| Chlorine (Alpha) | 500 ml | Ice |
| Total Phosphorus (EPA) | 125 ml | H_2SO_4 (pH <2) + Ice |
| TSS (EPA) | 1 liter | Ice |
| TSS (Alpha) | 1 liter | Ice |
| BOD (Alpha) | 1 Liter | Ice |
| TPH Petroleum ID (alpha) | 2 -1 Liter Amber Glass tephlon lined | Ice |
| E. Coli (Alpha) | 120 ml sterile | Ice |
| Enterococcus (Alpha) | 120 ml sterile | Ice |

Attachment 1

Stormwater Monitoring Program QAPP 5/17/12 Revision 1 Page 6 of 7

C. Quality Control

Calibration: EPA will calibrate its sondes according to the EPA sonde calibration

SOP.

Field duplicate: One duplicate sample will be collected per sampling event or

approximately for every ten samples.

Trip Blank: OEME Chemist will run appropriate QA samples for PPCP's. One blank

sample will be collected for approximately every ten bacteria samples. Reported data that is less than 5 times the trip (field) blank concentration

will be flagged.

QC Criteria: Are specified in table 2, data not meeting this criteria will be reviewed by

the Project Manager. Data that does not meet laboratory QA/QC criteria

will be flagged by the laboratory.

D. Chain of Custody

Chain of custody procedures will follow the OEME/Investigations Office SOP (Table 3)

3.0 Data Review

EPA Microbiology data will be reviewed by the Biology QAO. Alpha generated microbiology samples will be reviewed by the OEME Project Manager. All field data and draft data reports will be reviewed by the OEME Project manager. Laboratory generated data (from Alpha and EPA) will be reviewed by the Chemistry Team Leader.

4.0 Data reports

Data reports will be reviewed by the Project Coordinator and the OEME Project Manager before a final report is release to the Enforcement Coordinator. Draft reports may be released without a complete review.

Attachment 1

Stormwater Monitoring Program QAPP 5/17/12 Revision 1 Page 7 of 7

5.0 Attachments

- 1) Standard Operating Procedure Enterococcus (SM9230B), Multiple Tube Technique. SOP/07-01 *Alpha Analytical, Inc. May* 28, 2005
- 2) Standard Operating Procedure E. Coli (SM9213D). SOP/07-41 *Alpha Analytical, Inc. May* 28, 2005
- 3) Standard Operating Procedure MBAS, Ionic Surfactants. Draft SOP *EPA Laboratory*. *January* 28, 2010
- 4) Standard Operating Procedure Nitrogen Ammonia. Draft SOP *EPA Laboratory*. *February 10, 2011*
- 5) Standard Operating Procedure Total Chlorine. Draft SOP *EPA Laboratory*. *February 12, 2010*
- 6) Standard Operating Procedure TSS/ TVSS (SM2540 D, EPA 160.2). SOP/07-29 Alpha Analytical, Inc. September 29, 2007
- 7) Standard Operating Procedure BOD-5day, SBOD-5day, and cBOD-5day (SM 5210B, and EPA 405.1). SOP/07-13 *Alpha Analytical, Inc. September* 29, 2007
- 8) Standard Operating Procedure TPH 8015D Modified 0-017 (EPA 8015D Modified) *Alpha Analytical, Inc. March 04, 2008*
- 9) Standard Operating Procedure determination of Trace Elements in Water and Wastes by Inductively Coupled Plasma- Mass Spectrometry (200.8). SOP/06-11 Alpha Analytical, Inc. July 13, 200
- 10) Standard Operating Procedure Inductively Coupled Plasma Mass Spectrometry (6020). SOP/06-10 Alpha Analytical, Inc. October 25, 2007



Target Compounds, Uses, and Reporting Limits

| Target | Major Use | RL | Daily Dose |
|---------------|-----------------------------|--------|----------------|
| Compound | | (ng/L) | (ng) |
| Caffeine | Natural Stimulant | 5.0 | 200,000,000 |
| 1,7-DMX | Metabolite of caffeine | 2.5 | N/A |
| Acetaminophen | Pain Reliever | 2.5 | 650,000,000 |
| Carbamazepine | Anti- depressant / bi-polar | 0.5 | 100,000,000 |
| | Anti-convulsant (epilepsy) | | |
| Primidone | Anti- epilepsy drug (AED) | 5.0 | 100,000,000 |
| Atenolol | Beta Blocker | 2.5 | 50,000,000 |
| | High Blood Pressure | | |
| Cotinine | Metabolite of Nicotine | 0.5 | 3,500-7,200 |
| | | | (ng/mL) |
| Urobilin | By-product of hemoglobin | 5.0 | 1,300,000 ng/g |
| | breakdown (mammals) | | in feces |
| Azithromycin | Antibiotic | 1.6 | 200,000,000 |

STORMWATER MONITORING

<u>Field Collection Requirements</u> (To be recorded at each site)

| Sample- | Location information- |
|---------------------------------------|---|
| Site Name | Short description of where sample was |
| | collected at site |
| Time collected | |
| Date collected | |
| Inspection- | |
| **Take picture at site** | GPS |
| Outfall diameter('na' if open stream) | |
| Flow estimate('na' if open stream) | |
| | Field Kits listed in the order they should be |
| Odor | conducted in, include any applicable notes- |
| Color | NH3 strip |
| Turbidity | Cl2 kit |
| | Hach meter – (3 min wait) |
| Floatables | |
| | Surfactant |
| Other observations | Chemetrics K-9400 Blue box/detergent test kit |
| | Additional Notes: |
| YSI Meter (calibrate in lab)- | (Note any changes in weather |
| Salinity | conditions) |
| Temp | |
| Conductivity (give both #'s) | |
| | |

STORMWATER MONITORING (PAGE 2)

Field Equipment List

Waste Containers (2 total – clearly labeled):

- 1 liter amber plastic for surfactants/detergents kit waste
- 1 liter amber plastic for CI2 kit waste

Sample Bottles (3 total for each sample location)-

120ml sterile - E.coli/entero


1 Liter amber glass: PPCP, EPA (Peter Philbrook)

120ml-250ml plastic - Field Kit Bottle - to be used on site for kits listed above

***Fill out chain of custody

| n Carboy Container |
|------------------------------------|
| □Log book |
| □COC forms |
| ∃Extra sample bottles |
| □Colored tape |
| ∃Sharpies |
| □Write-On-Rain Pens |
| □Paper towels |
| □GPS |
| □Sampling plan & GPS locations |
| □Regular length Powder Free Gloves |
| □Squirt bottle of DI Water |
| □Coolers with Ice |
| □ Waders /Boots |
| □YSI multi parameter Meter |

Town of Wilbraham IDDE Program Appendix G Impaired Waters and TMDLs



Wilbraham, MA



Map produced by EPA Region I GIS Center Map Tracker ID 6678, February 25, 2010 Data Sources: TeleAtlas, Census Bureau, USGS, MassDEP

Waterbody Label

State ID, Waterbody Name (Category) (TMDL(s) approved for this waterbody

See companion table for a listing of pollutants non-pollutants, and TMDLs for each waterbody Assessment of Waterbody Segment

Category 2: Attaining some uses; other uses

Category 3: Insufficient information to make

Category 4a: TMDL is completed and approved for

Category 4c: Impairment not caused by a pollutant. Category 5: Impaired or threatened for one or more

Waterbodies

MS4 Urbanized Areas (2000 Census)

Municipal Boundaries

Massachusetts Year 2014 Integrated List of Waters

Final Listing of the Condition of Massachusetts' Waters Pursuant to Sections 305(b), 314 and 303(d) of the Clean Water Act





CN 450.1

Commonwealth of Massachusetts
Executive Office of Energy and Environmental Affairs
Matthew A. Beaton, Secretary
Massachusetts Department of Environmental Protection
Martin Suuberg, Commissioner
Bureau of Water Resources
Douglas E. Fine, Assistant Commissioner

Massachusetts Category 2 Waters "Attaining some uses; other uses not assessed"

| | | | | | | US | SES ATTAIN | ED* | |
|------------------------------|------------|--|------|-------|-----------|---|-------------------------------|------------------------------------|-------------------------|
| NAME | SEGMENT ID | DESCRIPTION | SIZE | UNITS | Aesthetic | Fish, other Aquatic Life and Wildlife | Primary Contact Recreation | Secondary Contact Recreation | Shellfish Harvesting |
| Chicopee River | MA36-23 | Red Bridge Impoundment Dam, Wilbraham/Ludlow to Wilbraham Pumping Station (old WWTP), Wilbraham/Ludlow. | 3.8 | MILES | X | X | Х | X | |
| Conant Brook Reservoir | MA36038 | ivionson | 4 | ACRES | Х | | | | |
| Cooley Brook | MA36-38 | From the outlet of Chicopee Reservoir, Chicopee to the confluence with the Chicopee River, Chicopee. (segment includes "braid" that confluences with the Chicopee River upstream of the mouth of Cooley Brook) | 1.2 | MILES | X | Х | Х | Х | |
| Cranberry River | MA36-20 | Source, outlet Cranberry Meadow Pond, Spencer to confluence with Sevenmile River, Spencer. (through Howe Pond formerly segment MA36073) | 3.6 | MILES | Х | Х | Х | Х | |
| Dunn Brook | MA36-19 | From confluence with Forget-Me-Not Brook, East Brookfield/Brookfield to confluence with Quaboag River, Brookfield. | 2.4 | MILES | Х | | Х | Х | |
| East Branch Swift River | MA36-35 | Headwaters at the confluence of Shattuck and Popple Camp Brooks, Phillipston to mouth at Pottapaug Pond, Petersham. (through Connor Pond formerly segment MA36039) | 9.8 | MILES | Х | Х | | | |
| Forget-Me-Not Brook | MA36-18 | Headwaters, North Brookfield to North Brookfield WWTP discharge, North Brookfield. | 1.7 | MILES | Х | Х | Х | Х | |
| Higher Brook | MA36-42 | Headwaters south of Route 21, Ludlow through Harris Pond (formely reported as segment MA36067) to the Ludlow/Chicopee corporate boundary where the stream name changes to Fuller Brook. | 6.3 | MILES | Х | Х | Х | Х | |
| Hop Brook | MA36-32 | Headwaters upstream of West Street, New Salem to mouth at Quabbin Reservoir, New Salem. | 3.7 | MILES | Х | | | | |
| Middle Branch Swift River | MA36-33 | Headwaters just north of Wendell and New Salem State Forests (south of the Swift River School), Wendell to mouth at Quabbin Reservoir, New Salem. | 6.9 | MILES | Х | | | | |
| Quaboag River | MA36-14 | Outlet of Quaboag Pond, Brookfield to Route 67 bridge, West Brookfield. | 6.1 | MILES | Х | Х | Х | Х | |

Massachusetts Category 3 Waters "No uses assessed"

| NAME | SEGMENT ID | DESCRIPTION | SIZE | UNITS |
|-----------------------------|------------|---|------|-------|
| Brigham Pond | MA36020 | Hubbardston | 45 | ACRES |
| Brooks Pond | MA36022 | Petersham | 86 | ACRES |
| Calkins Brook | MA36-26 | Headwaters, southeast of Baptist Hill, Palmer to confluence with Twelvemile Brook, Wilbraham. | 2.7 | MILES |
| Carter Pond | MA36029 | Petersnam | 44 | ACRES |
| Chicopee Brook | MA36-21 | Headwaters, east of Peaked Mountain, Monson (through Chicopee Brook Pond, formerly segment MA36031) to confluence with Quaboag River, Monson. | 9.9 | MILES |
| Chicopee Reservoir | MA36033 | Chicopee | 22 | ACRES |
| Cloverdale Street Pond | MA36036 | Rutland | 19 | ACRES |
| Comins Pond | MA36037 | Warren | 26 | ACRES |
| Cranberry Meadow Pond | MA36040 | Spencer/Charlton | 69 | ACRES |
| Crystal Lake | MA36043 | Palmer | 16 | ACRES |
| Cunningham Pond | MA36044 | Hubbardston | 27 | ACRES |
| Cusky Pond | MA36045 | New Braintree | 28 | ACRES |
| Demond Pond | MA36051 | Rutland | 120 | ACRES |
| Dimmock Pond | MA36053 | Springfield | 9 | ACRES |
| Edson Pond | MA36180 | Rutland | 36 | ACRES |
| Fivemile Pond | MA36061 | Springfield | 36 | ACRES |
| Fivemile Pond South | MA36182 | Springfield | 4 | ACRES |
| Gaston Pond | MA36065 | Barre | 15 | ACRES |
| Haviland Pond | MA36069 | Ludlow | 25 | ACRES |
| Horse Pond | MA36072 | North Brookfield | 63 | ACRES |
| Knights Pond | MA36077 | Belchertown | 36 | ACRES |
| Lovewell Pond | MA36085 | Hubbardston | 82 | ACRES |
| Mare Meadow Reservoir | MA36090 | Westminster/Hubbardston | 240 | ACRES |
| Mare Meadow Reservoir North | MA36178 | Westminster | 38 | ACRES |
| Moose Hill Reservoir | MA36179 | Spencer/Leicester | 52 | ACRES |
| Moulton Pond | MA36098 | Rutland | 65 | ACRES |
| Muddy Pond | MA36102 | Oakham/Rutland | 23 | ACRES |
| Murphy Pond | MA36103 | Ludlow | 6 | ACRES |
| Palmer Reservoir | MA36115 | Palmer | 8 | ACRES |
| Paradise Lake | MA36116 | Monson | 17 | ACRES |
| Pattaquattic Pond | MA36117 | Palmer | 18 | ACRES |
| Peppers Mill Pond | MA36121 | Ware | 11 | ACRES |
| Perry Hill Pond | MA36122 | Hubbardston | 23 | ACRES |
| Prince River | MA36-08 | Source, outlet Hemingway Pond, Barre to confluence with Ware River, Barre (excluding approximately 0.6 miles through Old Reservoir, segment MA36114). | 7.1 | MILES |

Massachusetts Category 3 Waters "No uses assessed"

| NAME | SEGMENT ID | DESCRIPTION | SIZE | UNITS |
|-------------------------------|------------|---|---------|-------|
| Spencer Brook | MA82B-15 | From the outlet of an unnamed pond north of Bellows Hill, Carlisle to the inlet of Angiers Pond, Concord. | 3.794 | MILES |
| Sudbury River | MA82A-01 | From the source at the outlet of Cedar Swamp Pond, Westborough to the Fruit Street Bridge, Hopkinton/Westborough. | 1.895 | MILES |
| Tripp Pond | MA82107 | Hudson | 3.501 | ACRES |
| Westborough Reservoir | MA82114 | Westborough | 41.007 | ACRES |
| White Pond | MA82118 | Concord | 36.112 | ACRES |
| White Pond | MA82119 | Hudson/Stow | 48.837 | ACRES |
| Whitehall Brook | MA82A-11 | From the outlet of Whitehall Reservoir, Hopkinton to confluence with the Sudbury River, Westborough. | 3.485 | MILES |
| Williams Lake | MA82121 | Marlborough | 69.316 | ACRES |
| Connecticut | | | | |
| Atkins Reservoir | MA34006 | Shutesbury | 46.468 | ACRES |
| Brickyard Brook | MA34-13 | Headwaters, Westfield to confluence with Manhan River, Westfield. | 1.616 | MILES |
| Cooley Brook | MA34-20 | Headwaters, Longmeadow to confluence with Connecticut River, Longmeadow. | 1.44 | MILES |
| Danks Pond | MA34019 | Northampton/Easthampton | 2.796 | ACRES |
| Factory Hollow Pond | MA34021 | Amherst | 11.89 | ACRES |
| Green Pond | MA34028 | Montague | 14.727 | ACRES |
| Lake Pleasant | MA34070 | Montague | 54.006 | ACRES |
| Long Plain Brook | MA34-09 | Headwaters, Leveret/Sunderland town line (in Mt. Toby State Forest) to confluence with Russellville Brook at Route 116, Sunderland. | 5.012 | MILES |
| Longmeadow Brook | MA34-21 | Headwaters, outlet Turner Park Pond, Longmeadow to confluence with Connecticut River, Longmeadow. | 4.454 | MILES |
| Lower Highland Lake | MA34047 | Goshen | 90.731 | ACRES |
| Manhan River | MA34-10 | Headwaters, northeast of Norwich Pond, Huntington to inlet Tighe Carmody Reservoir, Southampton (thru White Reservoir formely segment MA34100). | 6.551 | MILES |
| Mill River Diversion | MA34-32 | Headwaters, outlet Paradise Pond to confluence with Oxbow (east of Old Springfield Road), Northampton (thru Hulberts Pond formely segment MA34036). | 2.538 | MILES |
| Mountain Street Reservoir | MA34056 | Williamsburg/Hatfield/Whately | 66.673 | ACRES |
| Nine Mile Pond | MA34127 | Wilbraham (PALIS/Segment changed from 36107 to 34127, TRD 6/21/02) | 32.531 | ACRES |
| Nortnampton Reservoir | IVIA34059 | vvnately | 80.365 | ACRES |
| Northfield Mountain Reservoir | MA34061 | Erving | 237.269 | ACRES |
| Pine Island Lake | MA34069 | Westhampton | 55.096 | ACRES |
| Plympton Brook Pond | MA34071 | Wendell | 4.894 | ACRES |
| Potash Brook | MA34-12 | Headwaters to confluence with Manhan River, Southampton. | 0.96 | MILES |
| Raspberry Brook | MA34-22 | From Massachusetts/Connecticut border to confluence with Connecticut River, Longmeadow. | 1.794 | MILES |
| Roberts Meadow Reservoir | MA34076 | Northampton | 22.421 | ACRES |
| Sawmill River | MA34-40 | Headwaters, outlet Lake Wyola, Shutesbury to Dudleyville Road, Leverett (formerly part of MA34-26). | 2.032 | MILES |

Massachusetts Category 4a Waters "TMDL is completed"

| NAME | SEGMENT ID | DESCRIPTION | SIZE | UNITS | POLLUTANTS ADDRESSED BY TMDL | EPA TMDL NUMBER |
|------------------------|--------------|---|---------|--------|--|--------------------|
| Uncas Pond | MA72122 | Franklin | 17.3 | ACRES | (Non-Native Aquatic Plants*) | |
| | | | | | Oxygen, Dissolved | 40319 |
| Unnamed Tributary | MA72-32 | Locally known as Sawins Brook - emerges east of Elm Street, Watertown to confluence with the Charles River, Watertown (sections culverted). | 0.539 | MILES | Escherichia coli | 32382 |
| Chicopee | | | | | | |
| Lake | MA36079 | North Brookfield/East Brookfield | 274 | ACRES | (Non-Native Aquatic Plants*) | |
| Lashaway | | | | | Mercury in Fish Tissue | 33880 |
| Long Pond | MA36083 | Springfield | 14 | ACRES | Nutrient/Eutrophication Biological Indicators | 722 |
| Minechoag Pond | MA36093 | Ludlow | 21 | ACRES | Nutrient/Eutrophication Biological Indicators | 3629 |
| Mona Lake | MA36094 | Springfield | 11 | ACRES | Nutrient/Eutrophication Biological Indicators | 3630 |
| Pottapaug | MA36125 | Petersham/Hardwick | 568 | ACRES | (Non-Native Aquatic Plants*) | |
| Pond | | | | | Mercury in Fish Tissue | 33880 |
| Quabbin | MA36129 | Petersham/Pelham/Ware/Hardwick/Shutesbury/Belcherto | 24012 | ACRES | (Non-Native Aquatic Plants*) | |
| Reservoir | | wn/New Salem | | | Mercury in Fish Tissue | 33880 |
| Quacumquasit Pond | MA36131 | Brookfield/East Brookfield/Sturbridge | 223 | ACRES | (Eurasian Water Milfoil, Myriophyllum spicatum*) | |
| | | | | | (Non-Native Aquatic Plants*) | |
| | | | | | Mercury in Fish Tissue | 33880 |
| Spectacle Pond | MA36142 | Wilbraham | 9 | ACRES | Nutrient/Eutrophication Biological Indicators | 3631 |
| Sugden | MA30150 | Opencer | 05 | ACRES | Nutrient/Eutrophication Biological | 3633 |
| Reservoir Wickaboag | MA36166 | West Brookfield | 315 | ACRES | Indicators Aquatic Plants (Macrophytes) | 1332 |
| Pond | WIAGOTOO | West Brookleid | 313 | AONEO | Turbidity | 1332 |
| Concord (SuAs | :Co) | | | | Taiblaity | 1002 |
| Ashland | MA82003 | Ashland | 167.961 | ACRES | (Non-Native Aquatic Plants*) | |
| Reservoir | 1417-102-000 | Tornaria | 107.501 | /\OKLO | Mercury in Fish Tissue | 42396 |
| Boons Pond | MA82011 | Stow/Hudson | 173,442 | ACRES | (Non-Native Aquatic Plants*) | 72000 |
| 230101 0110 | | 5.5 | 1.0.442 | , | Excess Algal Growth | 2353 |
| | | | | | Mercury in Fish Tissue | 33880 |
| Nutting Lake | MA82124 | [West Basin] Billerica | 51.408 | ACRES | Mercury in Fish Tissue | 33880 |
| Sudbury Reservoir | MA82106 | Southborough/Marlborough | 1177.98 | ACRES | Mercury in Fish Tissue | 33880 |
| Walden Pond | MA82109 | Concord | 62.946 | ACRES | Mercury in Fish Tissue | 33880 |

Final Massachusetts Year 2014 Integrated List of Waters December, 2015 (2) CN 450.1

Massachusetts Category 5 Waters "Waters requiring a TMDL"

| NAME | SEGMENT ID | DESCRIPTION | SIZE | UNITS | IMPAIRMENT CAUSE | EPA TMD NO. |
|---------------------------|------------|---|------|-------|--|----------------|
| Browning Pond | MA36025 | Oakham/Spencer | 106 | ACRES | (Non-Native Aquatic Plants*) | |
| | | | | | Mercury in Fish Tissue | |
| | | | | | Nutrient/Eutrophication Biological Indicators | 3626 |
| Chicopee River | MA36-22 | Source, confluence of Ware River and Quaboag | 2.8 | MILES | Escherichia coli | |
| | | River, Palmer (through Red Bridge Impoundment formerly segment MA36171) to Red Bridge Impoundment Dam, Wilbraham/Ludlow. | | | Mercury in Fish Tissue | |
| Chicopee River | MA36-24 | Wilbraham Pumping Station (old WWTP), Wilbraham/Ludlow to Chicopee Falls Dam, Chicopee. | 9.1 | MILES | Fecal Coliform | |
| Chicopee River | MA36-25 | Chicopee Falls Dam, Chicopee to confluence with Connecticut River, Chicopee. | 3 | MILES | Escherichia coli | |
| Dean Pond | MA36050 | Oakham | 64 | ACRES | Excess Algal Growth | |
| | | | | | Turbidity | |
| Doane Pond | MA36054 | North Brookfield | 28 | ACRES | Aquatic Plants (Macrophytes) | |
| Eames Pond | MA36056 | Paxton | 58 | ACRES | Oxygen, Dissolved | |
| East Branch Ware River | MA36-01 | Outlet Bickford Pond, Hubbardston to confluence with the West Branch Ware River, Barre. | 12.4 | MILES | Oxygen, Dissolved | |
| East Brookfield River | MA36-13 | Outlet Lake Lashaway, East Brookfield to | 2.4 | MILES | (Non-Native Aquatic Plants*) | |
| | | Quaboag Pond, East Brookfield. | | | Oxygen, Dissolved | |
| Forget-Me-Not Brook | MA36-28 | North Brookfield WWTP discharge, North | 1.3 | MILES | Aquatic Macroinvertebrate Bioassessments | |
| | | Brookfield to confluence with Dunn Brook, East Brookfield/Brookfield. | | | Escherichia coli | |
| | | Brookfield/Brookfield. | | | Taste and Odor | |
| | | | | | Whole Effluent Toxicity (WET) | |
| Fuller Brook | MA36-41 | From the Ludlow/Chicopee corporate boundary where the stream name changes from Higher Brook, to the confluence with the Chicopee River, Chicopee. | 1.9 | MILES | Escherichia coli | |
| Lake Whittemore | MA36165 | Spencer | 52 | ACRES | Turbidity | |
| Quaboag Pond | MA36130 | Brookfield/East Brookfield | 544 | ACRES | (Eurasian Water Milfoil, Myriophyllum spicatum*) | |
| | | | | | (Non-Native Aquatic Plants*) | |
| | | | | | Excess Algal Growth | 33846 |
| | | | | | Mercury in Fish Tissue | |
| | | | | | Phosphorus (Total) | 33846 |
| Quaboag River | MA36-16 | Warren WWTP discharge, Warren to Route 32 bridge, Palmer/Monson. | 8.7 | MILES | Fecal Coliform | |

Massachusetts Year 2016 Integrated List of Waters

Proposed Listing of the Condition of Massachusetts' Waters Pursuant to Sections 305(b), 314 and 303(d) of the Clean Water Act





CN 470.0

Commonwealth of Massachusetts
Executive Office of Energy and Environmental Affairs
Matthew A. Beaton, Secretary
Massachusetts Department of Environmental Protection
Martin Suuberg, Commissioner
Bureau of Water Resources
Douglas E. Fine, Assistant Commissioner

Category 2 waters listed alphabetically by major watershed "Attaining some uses; other uses not assessed"

| | Т | | II | | | Uses | Attaine | ed* | |
|-------------------------|---|--|---------------|-----------------------|-----------|--|-------------------------------|---------------------------------|----------------------|
| WATER BODY | SEGMENT ID | Description | SIZE | UNITS | Aesthetic | Fish, other Aquatic Life and Wildlife | Primary Contact Recreation | Secondary Contact Recreation | Shellfish Harvesting |
| BOTTLE BROOK | MA36-46 | Headwaters, perennial portion, east of Dunhamtown Brimfield Road, Brimfield to mouth at confluence with Quaboag River, Brimfield. | 2 | MILES | X | | X | Х | |
| - | MA36-37 from listing as Massachusetts | Category 3 ence with Canesto Brook, Barre (through | 8.6 | MILES | Х | | Х | Х | |
| Cadwell Creek | ed List of Wate | if Route 202 and northwest of Dodge Hill | 3.2 | MILES | | Х | | | |
| Calkins Brook | MA36-26 | Headwaters, perennial portion, southeast of Baptist Hill, Palmer to mouth at confluence with Twelvemile Brook, Wilbraham. | 2.7 | MILES | Х | | Х | Х | |
| Chiconea Reservoir | MASEUSS | Chiconee | 22 | ACRES | | | Y | Y | |
| Chicopee River | MA36-23 | Red Bridge Impoundment Dam (NATID: MA00723), Wilbraham/Ludlow to Wilbraham Pumping Station (old WWTP) Wilbraham/Ludlow. | 3.8 change | MILES from Massach | X | X Year | Х | Х | |
| CONANT BROOK | MA36-45 | Headwaters, outlet Conant Brook Reservoir dam (NATID: MA00965), Monson to mouth at confluence with Chicopee Brook, Monson. |)14 Integr | ated List of W | aters | | Х | Х | |
| Cooley Brook | MA36-38 | | 1.2 | MILES | | Х | | | |
| Cranberry River | MA36-20 | Headwaters, outlet Cranberry Meadow Pond, Spencer to mouth at confluence with Sevenmile River, Spencer (through Howe Pond formerly segment MA36073). | 3.6 | MILES | | Х | | | |
| Dunn Brook | MA36-19 | From confluence with Forget-Me-Not Brook, East Brookfield/Brookfield to mouth at confluence with Quaboag River, Brookfield. | 2.4 | MILES | Х | | X | Х | |
| East Branch Swift River | MA36-35 | Headwaters, confluence of Shattuck and Popple Camp brooks, Phillipston to mouth at inlet Pottapaug Pond, Petersham (through Connor Pond formerly segment MA36039). | 9.8 | MILES | | Х | | | |
| Higher Brook | MA36-42 | | 6.3 | MILES | | Х | | | |

Proposed Massachusetts Year 2016 Integrated List of Waters June, 2017(5) CN 470.0

^{*} Attained uses denoted by "X". The Fish Consumption use is not supported in any waters due to the DPH statewide health advisory.

Category 3 waters listed alphabetically by major watershed "No uses assessed"

| WATER BODY | SEGMENT ID | Description | SIZE | UNITS |
|-------------------------------|------------|--|----------------|-------------|
| White Pond | MA82119 | Hudson/Stow. | 49 | ACRES |
| Whitehall Brook | MA82A-11 | Headwaters, outlet Whitehall Reservoir, Hopkinton to mouth at confluence with the Sudbury River, Westborough. | 3.5 | MILES |
| Williams Lake | MA82121 | Marlborough. | 69 | ACRES |
| Connecticut | | | | |
| Atkins Reservoir | MA34006 | Shutesbury/Amherst. | 46 | ACRES |
| Brickyard Brook | MA34-13 | Headwaters, perennial portion, Westfield to mouth at confluence with Manhan River, Westfield. | 1.6 | MILES |
| BUFFUM BROOK | MA34-49 | Headwaters, west of West Pelham Road, Shutesbury to mouth at confluence with Harris Brook, (forming headwaters Amethyst Brook), Pelham. | 3.1 | MILES |
| Cooley Brook | MA34-20 | Headwaters, Longmeadow to mouth at confluence with Connecticut River, Longmeadow. | 1.4 | MILES |
| Danks Pond | MA34019 | Northampton/Easthampton. | 3 | ACRES |
| DEAN BROOK | MA34-50 | Headwaters, east of West Pelham Road (at mouth of Baker Brook), Shutesbury to mouth at confluence with Adams Brook (in small "diversion pool" for Atkins Reservoir), Shutesbury. | 2.4 | MILES |
| Factory Hollow Pond | MA34021 | Amherst. | 12 | ACRES |
| Green Pond | MA34028 | Montague. | 15 | ACRES |
| HARRIS BROOK | MA34-48 | Headwaters, northeast of Enfield Road, Pelham to Intake Reservoir Dam (NATID: MA01270) outlet, Pelham (excluding approximately 0.2 miles through Hawley Reservoir, Pelham). | 1.2 | MILES |
| JOE WRIGHT BROOK | MA34-52 | Headwaters south of Hemenway Trail, Williamsburg to mouth at confluence with Mill River, Williamsburg. | 3.3 | MILES |
| Lake Pleasant | MA34070 | Montague. | 54 | ACRES |
| Loon Pond | MA34045 | Springfield. | 26 | ACRES |
| Lower Highland Lake | MA34047 | Goshen. | 91 | ACRES |
| Manhan River | MA34-10 | Headwaters, northeast of Norwich Pond, Huntington to inlet Tighe Carmody Reservoir, Southampton (thru White Reservoir formely segment MA34100). | | MILES |
| MILL BROOK | MA34-55 | Headwaters, outlet Stevens Swamp, Warwick to mouth at confluence with Connecticut River, Northfield. | 7.7 | MILES |
| Mill River Diversion | MA34-32 | Headwaters, outlet Paradise Pond, Northampton to mouth at confluence with Oxbow (east of Old Springfield Road), Northampton (thru Hulberts Pond formely segment MA34036). | 2.5 | MILES |
| Mountain Street Reservoir | MA34056 | Williamsburg/Hatfield/Whately. | 67 | ACRES |
| Nine Mile Pond | MA34127 | Wilbraham (PALIS/Segment changed from 36107 to 34127, TRD 6/21/02). | 33 | ACRES |
| Northampton Reservoir | MA34059 | Whately. No change | from Massacl | nusetts Yea |
| Northfield Mountain Reservoir | MA34061 | | ated List of W | |
| NURSE BROOK | MA34-59 | Headwaters, west of Pratt Corner Road, Shutesbury to mouth at confluence with Auams Brook (in small "diversion pool" for Atkins Reservoir), Shutesbury. | 1.2 | WILES |
| Pine Island Lake | MA34069 | Westhampton. | 55 | ACRES |
| Plympton Brook Pond | MA34071 | Wendell. | 5 | ACRES |
| Potash Brook | MA34-12 | Headwaters, perennial portion, Southampton to confluence with Manhan River, Southampton. | 1 | MILES |
| Raspberry Brook | MA34-22 | From Massachusetts/Connecticut border to mouth at confluence with Connecticut River, Longmeadow. | | MILES |
| RICE BROOK | MA34-47 | Headwaters, perennial portion, south of Burt Road, Westhampton to mouth at confluence with Sodom Brook, Westhampton. | | MILES |
| Roberts Meadow Reservoir | MA34076 | Northampton. | 22 | ACRES |
| ROGERS BROOK | MA34-51 | Headwaters east of Oak Hill Road near the Goshen/Ashfield border to mouth at confluence with West Branch Mill River, Goshen. | 2.6 | MILES |
| SACKET BROOK | MA34-45 | Headwaters, perennial portion, north of Southampton Road, Montgomery to mouth at confluence with Manhan River, Southampton. | 2.1 | MILES |

Category 4a waters listed alphabetically by major watershed "TMDL is completed"

| WATER BODY | SEGMENT ID | DESCRIPTION | SIZE | UNITS | POLLUTANTS ADDRESSED BY TMDL | EPA TMDL NO. |
|-------------------|-------------|---|-------|---------|--|-----------------|
| | | | | | Turbidity | 40319 |
| Lymans Pond | MA72070 | Dover. | 4 | ACRES | Aquatic Plants (Macrophytes) | 40319 |
| | | | | | Turbidity | 40319 |
| Mirror Lake | MA72078 | Wrentham/Norfolk. | 62 | ACRES | (Non-Native Aquatic Plants*) | |
| | | | | | Nutrient/Eutrophication Biological Indicators | 40319 |
| | | | | | Phosphorus (Total) | 40319 |
| | | | | | Secchi disk transparency | 40319 |
| Rosemary Brook | MA72-25 | Headwaters, outlet Rosemary Lake, Needham to mouth | 3.3 | MILES | Oxygen, Dissolved | 40317 |
| · | | at confluence with the Charles River, Wellesley. | | | Phosphorus (Total) | 40317 |
| South Meadow | MA72-24 | From emergence west of Parker Street, Newton to | 1.7 | MILES | (Bottom Deposits*) | |
| Brook | | mouth at confluence with the Charles River, Newton | | | (Debris/Floatables/Trash*) | |
| | | (three culverted portions totaling approximately 2870 | | | (Physical substrate habitat alterations*) | |
| | | feet (0.54mile)). | Ì | | Escherichia coli | 32377 |
| | | | | | Oxygen, Dissolved | 40317 |
| | | | | | Phosphorus (Total) | 40317 |
| | | | | | Turbidity | 40317 |
| Uncas Pond | MA72122 | Franklin. | 17 | ACRES | (Non-Native Aquatic Plants*) | |
| oniodo i ond | W W Z 1 Z Z | T TOTAL THE | '' | 7101120 | Oxygen, Dissolved | 40319 |
| Unnamed Tributary | MA72-32 | Locally known as "Sawins Brook" - emerges east of Elm Street, Watertown to mouth at confluence with the Charles River, Watertown (one culverted portion approximately 360 feet (0.07mile)). | 0.5 | MILES | Escherichia coli | 32382 |
| Chicopee | | | · | | | |
| Lake Lashaway | MA36079 | North Brookfield/East Brookfield. | 274 | ACRES | (Non-Native Aquatic Plants*) | |
| · | | | | | Mercury in Fish Tissue | 33880 |
| Long Pond | MA36083 | Springfield. | 14 | ACRES | Nutrient/Eutrophication Biological Indicators | 722 |
| Minechoag Pond | MA36093 | Ludlow. | 21 | ACRES | Nutrient/Eutrophication Biological Indicators | 3629 |
| Mona Lake | MA36094 | Springfield. | 11 | ACRES | Nutrient/Eutrophication Biological Indicators | 3630 |
| Pottapaug Pond | MA36125 | Petersham/Hardwick. | 568 | ACRES | (Non-Native Aquatic Plants*) | |
| | | | | | Mercury in Fish Tissue | 33880 |
| Quabbin Reservoir | MA36129 | Petersham/Pelham/Ware/Hardwick/Shutesbury/Belcher | 2401 | ACRES | (Non-Native Aquatic Plants*) | |
| | | town/New Salem. | 2 | | Mercury in Fish Tissue | 33880 |
| Quacumquasit Pond | MA36131 | Brookfield/East Brookfield/Sturbridge. | 223 | ACRES | (Eurasian Water Milfoil, Myriophyllum spicatum*) | |
| | | | | | (Non-Native Aquatic Plants*) | |
| | | | | | Mercury in Fish Tissue | 33880 |
| Spectacle Pond | MA36142 | Wilbraham. No change from Massachusetts Y | 9 | ACRES | Nutrient/Eutrophication Biological Indicators | 3631 |
| Sugden Reservoir | WA36150 | Spencer. 100 change from Massachusetts Y 2014 Integrated List of Waters | ear = | ACRES | Nutrient/Eutrophication Biological Indicators | 3033 |
| Wickaboag Pond | MA36166 | West Brookfield. | 316 | ACRES | Turbidity | 1332 |

Proposed Massachusetts Year 2016 Integrated List of Waters June, 2017(5)
CN 470.0

Category 5 waters listed alphabetically by major watershed The 303(d) List – "Waters requiring a TMDL"

| WATER BODY | SEGMENT ID | DESCRIPTION | SIZE | UNITS | IMPAIRMENT | EPA TMDL NO. | |
|-------------------|------------|---|------|-------|--|----------------------|--|
| Unnamed Tributary | MA72-30 | Locally known as "Laundry Brook" - emerges north of California Street, Watertown to mouth at confluence with the Charles River, | 0.02 | MILES | (Physical substrate habita alterations*) | t | |
| | | Watertown (stream not depicted on 1987 Newton USGS map). | | | Enterococcus | 32381 | |
| | | | | | Escherichia coli | 32381 | |
| | | | | | Phosphorus (Total) | | |
| | | | | | Taste and Odor | | |
| | | | | | Total Suspended Solids | | |
| | | | | | (TSS) | | |
| | | | | | Turbidity | | |
| Unnamed Tributary | MA72-31 | Locally known as "Millers River" - from emergence near Route 93, | 0.2 | MILES | (Bottom Deposits*) | | |
| · | | Cambridge/Boston to mouth at confluence with the Charles River, | | | (Debris/Floatables/Trash* |) | |
| | | Cambridge. | | | (Habitat Assessment | , | |
| | | | | | (Streams)*) | | |
| | | | | | Foam/Flocs/Scum/Oil Slic | ks | |
| | | | | | Other (Unspecified Metals | s) | |
| | | | | | Petroleum Hydrocarbons | | |
| | | | | | Polychlorinated biphenyls | | |
| | | | | | Polycyclic Aromatic | | |
| | | | | | Hydrocarbons (PAHs) | | |
| | | | | | | (Aquatic Ecosystems) | |
| | | | | | Sedimentation/Siltation | | |
| | | | | | Taste and Odor | | |
| | | | | | Turbidity | | |
| Unnamed Tributary | MA72-41 | Unnamed tributary to the Charles River, outlet Lymans Pond, Dover to mouth at confluence with the Charles River, Dover. | 0.5 | MILES | Escherichia coli | | |
| Unnamed Tributary | MA72-43 | Unnamed tributary to Morses Pond, headwaters outlet Reeds Pond, Wellesley to mouth at confluence with Morses Pond, Wellesley. | 0.2 | MILES | Escherichia coli | | |
| Waban Brook | MA72-17 | Headwaters, outlet Lake Waban, Wellesley to mouth at confluence | 0.7 | MILES | Temperature, water | | |
| | | with the Charles River, Wellesley. | | | | | |
| Chicopee | | | , | | | | |
| Abbey Brook | MA36-40 | Headwaters west of Saint James Avenue, Springfield through | 1.5 | MILES | Escherichia coli | | |
| | | Bemis Pond (formely reported as segment MA36011) to mouth at | | | Total Suspended Solids | | |
| | | confluence with the Chicopee River, Chicopee. | | | (TSS) | | |
| Alden Pond | MA36003 | Ludlow. | 4 | ACRES | Nutrient/Eutrophication | | |
| | 144.0000 | W | | | Biological Indicators | | |
| Brookhaven Lake | MA36021 | West Brookfield. | 34 | ACRES | Turbidity | | |
| Browning Pond | MA36025 | Oakham/Spencer. | 106 | ACRES | (Non-Native Aquatic Plant | ts*) | |
| | | | | | Mercury in Fish Tissue | | |
| | | | | | Nutrient/Eutrophication | 3626 | |
| O | 1116555 | | | | Biological Indicators | | |
| Chicopee Brook | MA36-21 | Headwaters, east of Peaked Mountain, Monson (through Chicopee | 9.9 | MILES | Escherichia coli | | |
| | | Brook Pond, formerly segment MA36031) to mouth at confluence | | | F- | | |
| Ohisanaa Dissa | MAGG 00 | with Quaboag River, Monson. | 0.0 | MUEO | | No change from | |
| Chicopee River | MA36-22 | Source, confluence of Ware River and Quaboag River, Palmer | 2.8 | MILES | Escherichia coli | Massachusetts Yea | |
| | | | | | | ntegrated List of Wa | |

Proposed Massachusetts Year 2016 Integrated List of Waters June, 2017(5) CN 470.0

Category 5 waters listed alphabetically by major watershed The 303(d) List – "Waters requiring a TMDL"

| | | 555(a) <u></u> | J - | | | INO Change hom | |
|------------------------|-------------|--|------|---------|---|------------------------|----------|
| WATER BODY | SEGMENT ID | DESCRIPTION | SIZE | UNITS | IMPAIRMENT | Massachusetts Ye | |
| | | (through Red Bridge Impoundment formerly segment MA36171) to Red Bridge Impoundment Dam (NATID: MA00723), Wilbraham/Ludlow. | | | Mercury in Fish Tissue | Integrated List of | Water |
| Chicopee River | MA36-24 | Wilbraham Pumping Station (old WWTP), Wilbraham/Ludlow to Chicopee Falls Dam (NATID: MA00719), Chicopee. | 8.8 | MILES | Escherichia coli Fecal Coliform | | <u> </u> |
| Chicopee River | MA36-25 | Chicopee Falls Dam (NATID: MA00719), Chicopee to mouth at | 3 | MILES | Escherichia coli | Addition of E. Coli si | ince |
| Onicopec raver | WIAGO 25 | confluence with Connecticut River, Chicopee. | 3 | IVIILLO | L301101101110 COII | Massachusetts Year | r 2014 |
| DANFORTH BROOK | MA36-50 | Headwaters, east of Charity Road, Hardwick to mouth at confluence with Ware River, Hardwick. | 5.8 | MILES | Escherichia coli | Integrated List of Wa | aters |
| Dean Pond | MA36050 | Oakham. | 64 | ACRES | Excess Algal Growth | | |
| Doane Pond | MA36054 | North Brookfield. | 28 | ACRES | Turbidity Aquatic Plants | | |
| Eames Pond | MA36056 | Paxton. | 58 | ACRES | (Macrophytes) Oxygen, Dissolved | | |
| East Branch Ware | MA36-01 | Headwaters, outlet Bickford Pond, Hubbardston to mouth at | 12.4 | MILES | Oxygen, Dissolved | | |
| River | WIAGO | confluence with West Branch Ware River (forming headwaters of Ware River), Barre. | 12.4 | IVIILLO | Oxygen, Dissolved | | |
| East Brookfield | MA36-13 | Headwaters, outlet Lake Lashaway, East Brookfield to mouth at | 2.4 | MILES | (Non-Native Aquatic Pla | nts*) | |
| River | | inlet Quaboag Pond, East Brookfield. | | | Oxygen, Dissolved | | |
| Forget-Me-Not Brook | MA36-18 | Headwaters, North Brookfield to North Brookfield WWTP discharge (NPDES: MA0101061), North Brookfield. | 1.2 | MILES | Escherichia coli | | |
| Forget-Me-Not | MA36-28 | North Brookfield WWTP discharge (NPDES: MA0101061), North | 1.3 | MILES | Aquatic Macroinvertebra | ite | |
| Brook | | Brookfield to mouth at confluence with Dunn Brook, East | ļ | | Bioassessments | | |
| | | Brookfield/Brookfield. | | | Whole Effluent Toxicity (WET) | | |
| Fuller Brook | MA36-41 | From the Ludlow/Chicopee corporate boundary where the stream name changes from Higher Brook, to mouth at confluence with the Chicopee River, Chicopee. | 1.9 | MILES | Escherichia coli | | |
| Lake Lorraine | MA36084 | Springfield. | 28 | ACRES | (Non-Native Aquatic Pla | nts*) | |
| | | | | | Enterococcus | | |
| Lake Whittemore | MA36165 | Spencer. | 52 | ACRES | Turbidity | | |
| Prince River | MA36-08 | Headwaters, outlet Hemingway Pond, Barre to mouth at confluence with Ware River, Barre (excluding approximately 0.6 miles through Old Reservoir, segment MA36114). | 7.1 | MILES | Escherichia coli | | |
| Quaboag Pond | MA36130 | Brookfield/East Brookfield. | 544 | ACRES | (Eurasian Water Milfoil, Myriophyllum spicatum* | | |
| | | | | | (Non-Native Aquatic Pla | | |
| | | | ļ | | Excess Algal Growth | 33846 | |
| | | | | | Mercury in Fish Tissue | 22040 | |
| Quaboag River | MA36-15 | Route 67 bridge, West Brookfield to Warren WWTP discharge (NPDES: MA0101567), Warren. | 6.2 | MILES | Phosphorus (Total) Escherichia coli | 33846 | |
| Quaboag River | MA36-16 | Warren WWTP discharge (NPDES: MA0101567), Warren to Route | 8.7 | MILES | Escherichia coli | | |
| | 11111100 10 | 32 bridge, Palmer/Monson. | 0 | | Fecal Coliform | | |
| Quaboag River | MA36-17 | Route 32 bridge, Palmer/Monson to mouth at confluence with Ware River (forming headwaters of Chicopee River), Palmer. | 5.3 | MILES | Escherichia coli | | |

Proposed Massachusetts Year 2016 Integrated List of Waters June, 2017(5) CN 470.0 No change from

APPENDIX F

Requirements for Discharges to Impaired Waters with an Approved TMDL

Table of Contents

| | Requirements for Discharges to Impaired Waters with an Approved MassDEP In S | |
|------|---|----|
| | I. Charles River Watershed Phosphorus TMDL Requirements | 2 |
| | II. Lake and Pond Phosphorus TMDL Requirements | 18 |
| | III. Bacteria and Pathogen TMDL Requirements | 27 |
| | IV. Cape Cod Nitrogen TMDL Requirements | 40 |
| | V. Assabet River Phosphorus TMDL Requirements | 44 |
| | Requirements for Discharges to Impaired Waters with an Approved Out of State TMDL | 47 |
| | I. Nitrogen TMDL Requirements | 47 |
| | II. Phosphorus TMDL Requirements | 51 |
| | III. Bacteria and Pathogen TMDL Requirements | 55 |
| | IV. Metals TMDL Requirements | 58 |
| C. I | Requirements for Discharges to Impaired Waters with a Regional TMDL | 61 |
| | I. The "Northeast Regional Mercury TMDL (2007)" | 61 |
| Atta | Phosphorus TMDLs (Applicable To part II Of Appendix F Only) And Method To Calculate Increases in Phosphorus Load due to Development | |
| Atta | achment 2 – Phosphorus Reduction Credits For Selected Enhanced Non-Structural BMPs | |
| Atta | achment 3 - Phosphorus Reduction Credits For Selected Structural BMPs | |

II. Lake and Pond Phosphorus TMDL Requirements

Between 1999 and 2010 EPA has approved 13 Lake TMDLs¹⁰ completed by MassDEP covering 78 lakes and ponds within the Commonwealth of Massachusetts. Any permittee (traditional or non-traditional) that discharges to a waterbody segment in Table F-6 is subject to the requirements of this part.

1. Permittees that operate regulated MS4s (traditional and non-traditional) that discharge to the identified impaired waters or their tributaries must reduce phosphorus discharges to support achievement of phosphorus load reductions identified in the TMDLs. To address phosphorus, all permittees with a phosphorus reduction requirement greater than 0% shall develop a Lake Phosphorus Control Plan (LPCP) designed to reduce the amount of phosphorus in stormwater discharges from its MS4 to the impaired waterbody or its tributaries in accordance with the phosphorus load reduction requirements set forth in Table F-6 below. Permittees discharging to waterbodies in Table F-6 with an associated 0% Phosphorus Required Percent Reduction are subject to Appendix F part II.2.f and are relieved of the requirements of Appendix F part II.1.i through Appendix F part II.2.e Table F-6 identifies the primary municipalities¹¹ located within the watershed of the respective lake or pond and the percent phosphorus reductions necessary from urban stormwater sources. Any permittee (traditional or non-traditional) that discharges to a lake or pond listed in Table F-6 or its tributaries is subject to the same phosphorus percent reduction requirements associated with that lake or pond.

| Primary Municipality | Waterbody Name | Required Percent Reduction |
|-------------------------|-----------------------|-------------------------------|
| | Leesville Pond | 31% |
| | Auburn Pond | 24% |
| Auburn | Eddy Pond | 0% |
| | Pondville Pond | 8% |
| | Stoneville Pond | 3% |
| | Buffumville Lake | 28% |
| | Dresser Hill Pond | 17% |
| | Gore Pond | 14% |
| Charlton | Granite Reservoir | 11% |
| | Jones Pond | 13% |
| | Pierpoint Meadow Pond | 27% |
| | Pikes Pond | 38% |
| Dudley | Gore Pond | 14% |

¹⁰ Final TMDLs for lakes and ponds in the Northern Blackstone River Watershed, Chicopee Basin, Connecticut Basin, French Basin, Millers Basin and Bare Hill Pond, Flint Pond, Indian Lake, Lake Boon, Leesville Pond, Salisbury Pond, White Island Pond, Ouaboag Pond and Ouacumquasit Pond can be found

here: http://www.mass.gov/eea/agencies/massdep/water/watersheds/total-maximum-daily-loads-tmdls.html
11 Primary municipalities indicate the municipality in which the majority of the lake or pond is located but does not necessarily indicate each municipality that has urbanized area that discharges to the lake or pond or its tributaries.

| Primary Municipality | Waterbody Name | Required Percent Reduction |
|-------------------------|------------------------------|-------------------------------|
| | Larner Pond | 55% |
| | New Pond | 56% |
| | Pierpoint Meadow Pond | 27% |
| | Shepherd Pond | 25% |
| | Tobins Pond | 62% |
| | Wallis Pond | 54% |
| | Hilchey Pond | 27% |
| C 1 | Parker Pond | 47% |
| Gardner | Bents Pond | 52% |
| | Ramsdall Pond | 49% |
| Grafton | Flint Pond/Lake Quinsigamond | 59% |
| Granby | Aldrich Lake East | 0% |
| Hadley | Lake Warner | 24% |
| Harvard | Bare Hill Pond | 2% |
| Hudson | Lake Boon | 28% |
| | Smiths Pond | 30% |
| | Southwick Pond | 64% |
| T : . | Cedar Meadow Pond | 17% |
| Leicester | Dutton Pond | 23% |
| | Greenville Pond | 14% |
| | Rochdale Pond | 8% |
| Ludlow | Minechoag Pond | 48% |
| | Brierly Pond | 14% |
| Millbury | Dorothy Pond | 1% |
| | Howe Reservoir | 48% |
| | Buffumville Lake | 28% |
| | Hudson Pond | 37% |
| Oxford | Lowes Pond | 51% |
| Oxioid | McKinstry Pond | 79% |
| | Robinson Pond | 8% |
| | Texas Pond | 21% |
| | Flint Pond/Lake Quinsigamond | 49% |
| | Jordan Pond | 60% |
| Shrewsbury | Mill Pond | 43% |
| | Newton Pond | 19% |
| | Shirley Street Pond | 30% |
| Spencer | Quaboag Pond | 29% |

| Primary Municipality | Waterbody Name | Required Percent Reduction |
|-------------------------|-------------------|-------------------------------|
| | Quacumquasit Pond | 2% |
| | Jones Pond | 13% |
| | Sugden Reservoir | 31% |
| | Loon Pond | 10% |
| Springfield | Long Pond | 56% |
| | Mona Lake | 57% |
| Stow | Lake Boon | 28% |
| | Brazell Pond | 62% |
| Т1-4 | Depot Pond | 50% |
| Templeton | Bourn-Hadley Pond | 49% |
| | Greenwood Pond 2 | 56% |
| Wilbraham | Spectacle Pond | 45% |
| | Lake Denison | 22% |
| Win shoulds :: | Stoddard Pond | 24% |
| Winchendon | Whitney Pond | 16% |
| | Whites Mill Pond | 21% |

Table F-6: Phosphorus impaired Lakes or Ponds subject to a TMDL along with primary municipality and required percent reduction of phosphorus from urban stormwater sources

- i. The LPCP shall be implemented in accordance with the following schedule and contain the following elements:
 - a. LPCP Implementation Schedule The permittee shall complete its LPCP and fully implement all of the control measures in its LPCP as soon as possible but no later than 15 years after the effective date of the permit.
 - b. The LPCP shall be implemented in accordance with the following schedule and contain the following elements:

| Number | LPCP Component and Milestones | Completion Date |
|--------|--|------------------------|
| 1 | Legal Analysis | 2 years after permit |
| | | effective date |
| 2 | Funding source assessment | 3 years after permit |
| | | effective date |
| 3 | Define LPCP scope (LPCP Area) | 4 years after permit |
| | | effective date |
| 4 | Calculate Baseline Phosphorus, Allowable | 4 years after permit |
| | Phosphorus Load and Phosphorus Reduction | effective date |
| | Requirement | |

| Sescription of planned nonstructural and structural controls 6 Description of Operation and Maintenance (O&M) Program 7 Implementation schedule 8 Cost and Funding Source Assessment 8 Cost and Funding Source Assessment 9 Complete written LPCP 10 Full implementation of nonstructural controls. 11 Performance Evaluation. 12 1. Performance Evaluation. 13 Performance Evaluation. 14 Performance Evaluation of all structural controls used to demonstrate that the total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or less than the applicable Allowable Phosphorus Load(P_{allow}) Plus the applicable Phosphorus Evaluation 14 1. Performance Evaluation 15 Performance Evaluation 16 Performance Evaluation 17 Syears after permit effective date 18 Syears after permit effective date 19 Syears after permit effective date 10 Syears after permit effective date 11 Performance Evaluation 12 Performance Evaluation 13 Performance Evaluation 14 Performance Evaluation 15 Performance Evaluation 16 Performance Evaluation 17 Syears after permit effective date 18 Syears after permit effective date 19 Syears after permit effective date 10 Syears after permit effective date 10 Syears after permit effective date 11 Performance Evaluation 12 Update LPCP 13 Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or less than the applicable Allowable Phosphorus Reduction Requirement (P_{RR}) multiplied by 0.60 $P_{exp} \leq P_{allow} + (P_{RR} \times 0.60)$ OR that the permittee has reduced their phosphorus export rate by 30kg/year (whichever is greater, unless full Phosphorus Reduction Requirement has been met) 15 Performance Evaluation 16 Performance Evaluation 17 Performance Evaluation 18 Performance Evaluation 19 Performance Evaluation 19 Performance Evaluation 10 Performance Evaluation 11 and 12 years after permit effective date 11 Syears after permit effective date 12 Perfor | 5 | Description of planted posteriotized and | 5 years often mannit |
|--|----|--|-----------------------|
| 6 Description of Operation and Maintenance (O&M) Program 7 Implementation schedule 8 Cost and Funding Source Assessment 8 Cost and Funding Source Assessment 9 Complete written LPCP 10 Full implementation of nonstructural controls. 11 Performance Evaluation. 12 1. Performance Evaluation. 2. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P _{exp}) from the LPCP Area in mass/yr is equal to or less than the applicable Allowable Phosphorus Load(P _{allow}) plus the applicable Phosphorus Reduction Requirement (P _{RR}) multiplied by 0.80 P _{exp} ≤ P _{allow} + (P _{RR} X 0.80) 13 Performance Evaluation 14 1. Performance Evaluation 15 Performance Evaluation 16 1. Performance Evaluation of all structural controls used to demonstrate that the total phosphorus export rate (P _{exp}) from the LPCP Area in mass/yr is equal to or less than the applicable Allowable Phosphorus Load(P _{allow}) plus the applicable Phosphorus Reduction Requirement (P _{RR}) multiplied by 0.60 P _{exp} ≤ P _{allow} + (P _{RR} X 0.60) OR that the permittee has reduced their phosphorus Reduction Requirement thas been met) 15 Performance Evaluation 16 1. Performance Evaluation 2. Full implementation of all structural controls used to demonstrate that the total phosphorus Reduction Requirement has been met) 15 Performance Evaluation 16 1. Performance Evaluation 2. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P _{exp}) from the LPCP Area in mass/yr is equal to or less fare permit effective date applicable Phosphorus Reduction Requirement has been met) 15 Performance Evaluation 16 1. Performance Evaluation 2. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P _{exp}) from the LPCP Area in mass/yr is equal to or less fact permit effective date less than the permit effective d | 3 | Description of planned nonstructural and | 5 years after permit |
| | 6 | | |
| To a control of the control of th | O | | |
| S Cost and Funding Source Assessment S Syears after permit effective date | 7 | | |
| Sears after permit effective date 5 years after permit effective date 10 Full implementation of nonstructural controls. 6 years after permit effective date 11 Performance Evaluation. 6 and 7 years after permit effective date 12 1. Performance Evaluation. 2. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or less than the applicable Allowable Phosphorus Load(P_{allow}) plus the applicable Phosphorus Reduction Requirement (P_{RR}) multiplied by 0.80 $P_{exp} \le P_{allow} + (P_{RR} \times 0.80)$ 9 years after permit effective date 10 years after permit effective date 11 years after permit effective date 12 years after permit effective date 13 years after permit effective date 14 1. Performance Evaluation 10 years after permit effective date 14 1. Performance Evaluation 10 years after permit effective date 15 years after permit effective date 16 years after permit effective date 17 years after permit effective date 18 years after permit effective date 19 years after permit effective date 19 years after permit effective date 10 years after permit effective date 11 years after permit effective date 12 years after permit effective date 13 years after permit effective date 14 years after permit effective date 15 years after permit effective date 16 years after permit effective date 17 years after permit effective date 18 years after permit effective date 19 years after permit effective date 10 years after permit e | , | imprementation senerate | |
| Search Section Sect | 8 | Cost and Funding Source Assessment | 5 years after permit |
| Full implementation of nonstructural controls. Full implementation of nonstructural controls. Full implementation. 6 and 7 years after permit effective date 12 | | | |
| 10 Full implementation of nonstructural controls. | 9 | Complete written LPCP | |
| Controls Performance Evaluation. Controls Performance Evaluation. Controls | | | |
| 11 Performance Evaluation. 6 and 7 years after permit effective date 1. Performance Evaluation. 2. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or less than the applicable Allowable Phosphorus Load(P_{allow}) plus the applicable Phosphorus Reduction Requirement (P_{RR}) multiplied by 0.80 $P_{exp} \leq P_{allow} + (P_{RR} \times 0.80)$ 9 years after permit effective date 14 1. Performance Evaluation 9 years after permit effective date 14 1. Performance Evaluation 15 2. Update LPCP 3. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or less than the applicable Allowable Phosphorus Load(P_{allow}) plus the applicable Phosphorus Reduction Requirement (P_{RR}) multiplied by 0.60 $P_{exp} \leq P_{allow} + (P_{RR} \times 0.60)$ OR that the permittee has reduced their phosphorus export rate by 30kg/year (whichever is greater, unless full Phosphorus Reduction Requirement has been met) 15 Performance Evaluation 11 and 12 years after permit effective date 16 1. Performance Evaluation 2. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or large after permit effective date 17 years after permit effective date 18 years after permit effective date 19 years after permit effective date 19 years after permit effective date 10 years aft | 10 | | 1 |
| 1. Performance Evaluation. 2. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P_{ewp}) from the LPCP Area in mass/yr is equal to or less than the applicable Allowable Phosphorus Load(P_{allow}) plus the applicable Phosphorus Reduction Requirement (P_{RR} X 0.80) 13 Performance Evaluation 14 1. Performance Evaluation 2. Update LPCP 3. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P_{ewp}) from the LPCP Area in mass/yr is equal to or less than the applicable Allowable Phosphorus Reduction Requirement (P_{RR} X 0.60) OR that the permittee has reduced their phosphorus export rate by 30kg/year (whichever is greater, unless full Phosphorus Reduction Requirement has been met) 15 Performance Evaluation 16 Performance Evaluation 17 Performance Evaluation 18 Performance Evaluation 19 years after permit effective date 10 years after permit effective date 10 years after permit effective date 11 and 12 years after permit effective date 12 Performance Evaluation 13 years after permit effective date 14 1 and 12 years after permit effective date 15 Performance Evaluation 16 1 Performance Evaluation 17 Performance Evaluation 18 Performance Evaluation 19 years after permit effective date 10 years after permit effective date 11 and 12 years after permit effective date 12 years after permit effective date | | | |
| 1. Performance Evaluation. 2. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P _{exp}) from the LPCP Area in mass/yr is equal to or less than the applicable Allowable Phosphorus Load(P _{allow}) plus the applicable Phosphorus Reduction Requirement (P _{RR}) multiplied by 0.80 P _{exp} ≤ P _{allow} + (P _{RR} X 0.80) 13 Performance Evaluation 2. Update LPCP 3. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P _{exp}) from the LPCP Area in mass/yr is equal to or less than the applicable Allowable Phosphorus Load(P _{allow}) plus the applicable Phosphorus Reduction Requirement (P _{exR}) multiplied by 0.60 P _{exp} ≤ P _{allow} + (P _{RR} X 0.60) OR that the permittee has reduced their phosphorus export rate by 30kg/year (whichever is greater, unless full Phosphorus Reduction Requirement has been met) 15 Performance Evaluation 16 Performance Evaluation 2. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P _{exp}) from the LPCP Area in mass/yr is equal to or less than the applicable Phosphorus Reduction Requirement has been met) 16 Performance Evaluation 17 Performance Evaluation 18 Performance Evaluation 19 Performance Evaluation 11 and 12 years after permit effective date 12 Performance Evaluation 13 Performance Evaluation 14 Performance Evaluation 15 Performance Evaluation 15 Performance Evaluation 16 Performance Evaluation 17 Performance Evaluation 18 Performance Evaluation 29 years after permit effective date 19 Performance P | 11 | Performance Evaluation. | |
| 2. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P _{exp}) from the LPCP Area in mass/yr is equal to or less than the applicable Allowable Phosphorus Load(P _{allow}) plus the applicable Phosphorus Reduction Requirement (P _{RR}) multiplied by 0.80 P _{exp} ≤ P _{allow} + (P _{RR} X 0.80) 13 Performance Evaluation 14 1. Performance Evaluation. 2. Update LPCP 3. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P _{exp}) from the LPCP Area in mass/yr is equal to or less than the applicable Allowable Phosphorus Load(P _{allow}) plus the applicable Phosphorus Reduction Requirement (P _{RR}) multiplied by 0.60 P _{exp} ≤ P _{allow} + (P _{RR} X 0.60) OR that the permittee has reduced their phosphorus export rate by 30kg/year (whichever is greater, unless full Phosphorus Reduction Requirement has been met) 15 Performance Evaluation 16 1. Performance Evaluation 17 Performance Evaluation 18 Performance Evaluation 19 years after permit effective date 10 years after permit effective date 11 and 12 years after permit effective date 12 Performance Evaluation 13 years after permit effective date 14 1. Performance Evaluation 15 Performance Evaluation 15 Performance Evaluation 16 1. Performance Evaluation 17 Performance Evaluation 18 Performance Evaluation 19 years after permit effective date | | | permit effective date |
| controls used to demonstrate that the total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or less than the applicable Allowable Phosphorus Load(P_{allow}) plus the applicable Phosphorus Reduction Requirement (P_{RR}) multiplied by 0.80 $P_{exp} \leq P_{allow} + (P_{RR} X 0.80)$ 13 Performance Evaluation 14 1. Performance Evaluation. 2. Update LPCP 3. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or less than the applicable Allowable Phosphorus Load(P_{allow}) plus the applicable Phosphorus Reduction Requirement (P_{RR}) multiplied by 0.60 $P_{exp} \leq P_{allow} + (P_{RR} X 0.60)$ OR that the permittee has reduced their phosphorus export rate by $30 \log y$ (whichever is greater, unless full Phosphorus Reduction Requirement has been met) 15 Performance Evaluation 16 1. Performance Evaluation. 2. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or | 12 | | |
| total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or less than the applicable Allowable Phosphorus Load (P_{allow}) plus the applicable Phosphorus Reduction Requirement (P_{RR}) multiplied by 0.80 $P_{exp} \leq P_{allow} + (P_{RR} \times 0.80)$ 13 Performance Evaluation 9 years after permit effective date 14 1. Performance Evaluation. 2. Update LPCP 3. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or less than the applicable Allowable Phosphorus Load (P_{allow}) plus the applicable Phosphorus Reduction Requirement (P_{RR}) multiplied by 0.60 $P_{exp} \leq P_{allow} + (P_{RR} \times 0.60)$ OR that the permittee has reduced their phosphorus export rate by 30kg/year (whichever is greater, unless full Phosphorus Reduction Requirement has been met) 15 Performance Evaluation 11 and 12 years after permit effective date 12. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or | | | effective date |
| the LPCP Area in mass/yr is equal to or less than the applicable Allowable Phosphorus Load(P_{allow}) plus the applicable Phosphorus Reduction Requirement (P_{RR}) multiplied by 0.80 $P_{exp} \leq P_{allow} + (P_{RR} \ X \ 0.80)$ 13 Performance Evaluation 9 years after permit effective date 14 1. Performance Evaluation. 2. Update LPCP 3. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or less than the applicable Allowable Phosphorus Load(P_{allow}) plus the applicable Phosphorus Reduction Requirement (P_{RR}) multiplied by 0.60 $P_{exp} \leq P_{allow} + (P_{RR} \ X \ 0.60)$ OR that the permittee has reduced their phosphorus export rate by 30kg/year (whichever is greater, unless full Phosphorus Reduction Requirement has been met) 15 Performance Evaluation 11 and 12 years after permit effective date 12. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or | | | |
| less than the applicable Allowable Phosphorus Load(P_{allow}) plus the applicable Phosphorus Reduction Requirement (P_{RR}) multiplied by 0.80 $P_{exp} \leq P_{allow} + (P_{RR} X 0.80)$ 13 Performance Evaluation 14 1. Performance Evaluation. 2. Update LPCP 3. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or less than the applicable Allowable Phosphorus Load(P_{allow}) plus the applicable Phosphorus Reduction Requirement (P_{RR}) multiplied by 0.60 $P_{exp} \leq P_{allow} + (P_{RR} X 0.60)$ OR that the permittee has reduced their phosphorus export rate by 30kg/year (whichever is greater, unless full Phosphorus Reduction Requirement has been met) 15 Performance Evaluation 16 1. Performance Evaluation. 2. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or | | | |
| Phosphorus Load(P_{allow}) plus the applicable Phosphorus Reduction Requirement (P_{RR}) multiplied by 0.80 $P_{exp} \leq P_{allow} + (P_{RR} \ X \ 0.80)$ 13 Performance Evaluation 9 years after permit effective date 14 1. Performance Evaluation. 2. Update LPCP 3. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or less than the applicable Allowable Phosphorus Reduction Requirement (P_{RR}) multiplied by 0.60 $P_{exp} \leq P_{allow} + (P_{RR} \ X \ 0.60)$ OR that the permittee has reduced their phosphorus export rate by 30kg/year (whichever is greater, unless full Phosphorus Reduction Requirement has been met) 15 Performance Evaluation 11 and 12 years after permit effective date 16 1. Performance Evaluation 2. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or | | | |
| applicable Phosphorus Reduction Requirement (P_{RR}) multiplied by 0.80 $P_{exp} \leq P_{allow} + (P_{RR} \ X \ 0.80)$ 13 Performance Evaluation 14 1. Performance Evaluation. 2. Update LPCP 3. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or less than the applicable Allowable Phosphorus Reduction Requirement (P_{RR}) multiplied by 0.60 $P_{exp} \leq P_{allow} + (P_{RR} \ X \ 0.60)$ OR that the permittee has reduced their phosphorus export rate by 30kg/year (whichever is greater, unless full Phosphorus Reduction Requirement has been met) 15 Performance Evaluation 16 1. Performance Evaluation. 2. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or | | * * | |
| Requirement (P_{RR}) multiplied by 0.80 $P_{exp} \leq P_{allow} + (P_{RR} \times 0.80)$ 13 Performance Evaluation 9 years after permit effective date 14 1. Performance Evaluation. 2. Update LPCP 3. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or less than the applicable Allowable Phosphorus Load (P_{allow}) plus the applicable Phosphorus Reduction Requirement (P_{RR}) multiplied by 0.60 $P_{exp} \leq P_{allow} + (P_{RR} \times 0.60)$ OR that the permittee has reduced their phosphorus export rate by 30kg/year (whichever is greater, unless full Phosphorus Reduction Requirement has been met) 15 Performance Evaluation 16 1. Performance Evaluation. 2. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or | | | |
| $P_{exp} \le P_{allow} + (P_{RR} X 0.80)$ 13 Performance Evaluation 9 years after permit effective date 14 1. Performance Evaluation. 10 years after permit effective date 2. Update LPCP 3. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or less than the applicable Allowable Phosphorus Load(P_{allow}) plus the applicable Phosphorus Reduction Requirement (P_{RR}) multiplied by 0.60 $P_{exp} \le P_{allow} + (P_{RR} X 0.60)$ OR that the permittee has reduced their phosphorus export rate by 30kg/year (whichever is greater, unless full Phosphorus Reduction Requirement has been met) 15 Performance Evaluation 11 and 12 years after permit effective date 16 1. Performance Evaluation. 13 years after permit effective date 16 1. Performance Evaluation. 13 years after permit effective date 16 1. Performance Evaluation. 13 years after permit effective date 16 1. Performance Evaluation. 13 years after permit effective date | | | |
| 13 Performance Evaluation 9 years after permit effective date 14 1. Performance Evaluation. 2. Update LPCP 3. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or less than the applicable Allowable Phosphorus Load (P_{allow}) plus the applicable Phosphorus Reduction Requirement (P_{RR}) multiplied by 0.60 $P_{exp} \leq P_{allow} + (P_{RR} \times 0.60)$ OR that the permittee has reduced their phosphorus export rate by $30 \log y$ year (whichever is greater, unless full Phosphorus Reduction Requirement has been met) 15 Performance Evaluation 11 and 12 years after permit effective date 16 1. Performance Evaluation. 2. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or | | | |
| 14 1. Performance Evaluation. 10 years after permit 2. Update LPCP 3. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or less than the applicable Allowable Phosphorus Load (P_{allow}) plus the applicable Phosphorus Reduction Requirement (P_{RR}) multiplied by 0.60 $P_{exp} \leq P_{allow} + (P_{RR} \times 0.60)$ OR that the permittee has reduced their phosphorus export rate by 30kg/year (whichever is greater, unless full Phosphorus Reduction Requirement has been met) 11 and 12 years after permit effective date 1. Performance Evaluation. 11 and 12 years after permit effective date 13 years after permit effective date 13 years after permit effective date 14 years after permit effective date 15 years after permit effective date 16 years after permit effective date 17 years after permit effective date 18 years after permit effective date 19 years after permit effective date 10 year | | | |
| 1. Performance Evaluation. 2. Update LPCP 3. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P _{exp}) from the LPCP Area in mass/yr is equal to or less than the applicable Allowable Phosphorus Load(P _{allow}) plus the applicable Phosphorus Reduction Requirement (P _{RR}) multiplied by 0.60 P _{exp} ≤ P _{allow} + (P _{RR} X 0.60) OR that the permittee has reduced their phosphorus export rate by 30kg/year (whichever is greater, unless full Phosphorus Reduction Requirement has been met) 15 Performance Evaluation 16 1. Performance Evaluation. 2. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P _{exp}) from the LPCP Area in mass/yr is equal to or | 13 | Performance Evaluation | |
| 2. Update LPCP 3. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P _{exp}) from the LPCP Area in mass/yr is equal to or less than the applicable Allowable Phosphorus Load(P _{allow}) plus the applicable Phosphorus Reduction Requirement (P _{RR}) multiplied by 0.60 P _{exp} ≤ P _{allow} + (P _{RR} X 0.60) OR that the permittee has reduced their phosphorus export rate by 30kg/year (whichever is greater, unless full Phosphorus Reduction Requirement has been met) 15 Performance Evaluation 16 1. Performance Evaluation. 2. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P _{exp}) from the LPCP Area in mass/yr is equal to or | | | |
| 3. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P _{exp}) from the LPCP Area in mass/yr is equal to or less than the applicable Allowable Phosphorus Load(P _{allow}) plus the applicable Phosphorus Reduction Requirement (P _{RR}) multiplied by 0.60 P _{exp} ≤ P _{allow} + (P _{RR} X 0.60) OR that the permittee has reduced their phosphorus export rate by 30kg/year (whichever is greater, unless full Phosphorus Reduction Requirement has been met) 15 Performance Evaluation 16 1. Performance Evaluation. 2. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P _{exp}) from the LPCP Area in mass/yr is equal to or | 14 | | |
| controls used to demonstrate that the total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or less than the applicable Allowable Phosphorus Load (P_{allow}) plus the applicable Phosphorus Reduction Requirement (P_{RR}) multiplied by 0.60 $P_{exp} \leq P_{allow} + (P_{RR} X 0.60)$ OR that the permittee has reduced their phosphorus export rate by 30kg/year (whichever is greater, unless full Phosphorus Reduction Requirement has been met) 15 Performance Evaluation 11 and 12 years after permit effective date 16 1. Performance Evaluation. 2. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or | | 1 | effective date |
| total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or less than the applicable Allowable Phosphorus Load (P_{allow}) plus the applicable Phosphorus Reduction Requirement (P_{RR}) multiplied by 0.60 $P_{exp} \le P_{allow} + (P_{RR} \ X \ 0.60)$ OR that the permittee has reduced their phosphorus export rate by 30kg/year (whichever is greater, unless full Phosphorus Reduction Requirement has been met) 15 Performance Evaluation 11 and 12 years after permit effective date 16 1. Performance Evaluation. 2. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or | | <u> </u> | |
| the LPCP Area in mass/yr is equal to or less than the applicable Allowable Phosphorus Load(P_{allow}) plus the applicable Phosphorus Reduction Requirement (P_{RR}) multiplied by 0.60 $P_{exp} \le P_{allow} + (P_{RR} \times 0.60)$ OR that the permittee has reduced their phosphorus export rate by 30kg/year (whichever is greater, unless full Phosphorus Reduction Requirement has been met) 15 Performance Evaluation 11 and 12 years after permit effective date 16 1. Performance Evaluation. 2. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or | | | |
| less than the applicable Allowable Phosphorus Load(P_{allow}) plus the applicable Phosphorus Reduction Requirement (P_{RR}) multiplied by 0.60 $P_{exp} \le P_{allow} + (P_{RR} \times 0.60)$ OR that the permittee has reduced their phosphorus export rate by 30kg/year (whichever is greater, unless full Phosphorus Reduction Requirement has been met) 15 Performance Evaluation 11 and 12 years after permit effective date 16 1. Performance Evaluation. 2. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or | | | |
| Phosphorus Load(P_{allow}) plus the applicable Phosphorus Reduction Requirement (P_{RR}) multiplied by 0.60 $P_{exp} \leq P_{allow} + (P_{RR} \ X \ 0.60)$ OR that the permittee has reduced their phosphorus export rate by 30kg/year (whichever is greater, unless full Phosphorus Reduction Requirement has been met) 15 Performance Evaluation 16 1. Performance Evaluation. 2. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or | | , · · · · · · · · · · · · · · · · · · · | |
| applicable Phosphorus Reduction Requirement (P_{RR}) multiplied by 0.60 $P_{exp} \le P_{allow} + (P_{RR} \ X \ 0.60)$ OR that the permittee has reduced their phosphorus export rate by 30kg/year (whichever is greater, unless full Phosphorus Reduction Requirement has been met) 15 Performance Evaluation 16 1. Performance Evaluation. 2. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or | | | |
| Requirement (P_{RR}) multiplied by 0.60 $P_{exp} \le P_{allow} + (P_{RR} \times 0.60)$ OR that the permittee has reduced their phosphorus export rate by 30kg/year (whichever is greater, unless full Phosphorus Reduction Requirement has been met) 15 Performance Evaluation 11 and 12 years after permit effective date 16 1. Performance Evaluation. 2. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or | | | |
| $P_{exp} \leq P_{allow} + (P_{RR} \times 0.60)$ OR that the permittee has reduced their phosphorus export rate by 30kg/year (whichever is greater, unless full Phosphorus Reduction Requirement has been met) 15 Performance Evaluation 11 and 12 years after permit effective date 16 1. Performance Evaluation. 2. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or | | | |
| OR that the permittee has reduced their phosphorus export rate by 30kg/year (whichever is greater, unless full Phosphorus Reduction Requirement has been met) 15 Performance Evaluation 16 1. Performance Evaluation. 2. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P _{exp}) from the LPCP Area in mass/yr is equal to or | | | |
| phosphorus export rate by 30kg/year (whichever is greater, unless full Phosphorus Reduction Requirement has been met) 15 Performance Evaluation 11 and 12 years after permit effective date 16 1. Performance Evaluation. 2. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P _{exp}) from the LPCP Area in mass/yr is equal to or | | | |
| (whichever is greater, unless full Phosphorus Reduction Requirement has been met) 15 Performance Evaluation 11 and 12 years after permit effective date 16 1. Performance Evaluation. 2. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P _{exp}) from the LPCP Area in mass/yr is equal to or | | 1 | |
| Phosphorus Reduction Requirement has been met) 15 Performance Evaluation 16 1. Performance Evaluation. 2. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P _{exp}) from the LPCP Area in mass/yr is equal to or | | | |
| been met) 15 Performance Evaluation 16 1. Performance Evaluation. 2. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P _{exp}) from the LPCP Area in mass/yr is equal to or | | | |
| Performance Evaluation 11 and 12 years after permit effective date 12. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P _{exp}) from the LPCP Area in mass/yr is equal to or | | | |
| 16 1. Performance Evaluation. 2. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P _{exp}) from the LPCP Area in mass/yr is equal to or | | , | |
| 1. Performance Evaluation. 2. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P _{exp}) from the LPCP Area in mass/yr is equal to or | 15 | Performance Evaluation | |
| 2. Full implementation of all structural controls used to demonstrate that the total phosphorus export rate (P _{exp}) from the LPCP Area in mass/yr is equal to or | | | |
| controls used to demonstrate that the total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or | 16 | | |
| total phosphorus export rate (P_{exp}) from the LPCP Area in mass/yr is equal to or | | * | effective date |
| the LPCP Area in mass/yr is equal to or | | | |
| | | | |
| less than the applicable Allowable | | | |
| | | less than the applicable Allowable | |

| | Phosphorus Load(Pallow) plus the | |
|----|---|-----------------------|
| | applicable Phosphorus Reduction | |
| | Requirement (P_{RR}) multiplied by 0.30 | |
| | $P_{exp} \le P_{allow} + (P_{RR} X 0.30)$ | |
| 17 | Performance Evaluation | 14 years after permit |
| | | effective date |
| 18 | 1. Performance Evaluation. | 15 years after permit |
| | 2. Full implementation of all structural | effective date |
| | controls used to demonstrate that the | |
| | total phosphorus export rate (P_{exp}) from | |
| | the LPCP Area in mass/yr is equal to or | |
| | less than the applicable Allowable | |
| | Phosphorus Load(P _{allow}) | |
| | $P_{exp} \le P_{allow}$ | |

Table F-7: LPCP components and milestones

c. Description of LPCP Components:

<u>Legal Analysis</u>- The permittee shall develop and implement an analysis that identifies existing regulatory mechanisms available to the MS4 such as by-laws and ordinances and describes any changes to these regulatory mechanisms that may be necessary to effectively implement the LPCP. This may include the creation or amendment of financial and regulatory authorities. The permittee shall adopt necessary regulatory changes by the end of the permit term.

Scope of the LPCP (LPCP Area) - The permittee shall indicate the area in which the permittee plans to implement the LPCP, this area is known as the "LPCP Area". The permittee must choose one of the following: 1) to implement its LPCP in the entire area within its jurisdiction discharging to the impaired waterbody (for a municipality this would be the municipal boundary) or 2) to implement its LPCP in only the urbanized area portion of its jurisdiction discharging to the impaired waterbody. If the permittee chooses to implement the LPCP in its entire jurisdiction discharging to the impaired waterbody, the permittee may demonstrate compliance with the Phosphorus Reduction Requirement and Allowable Phosphorus Load requirements applicable to it through structural and nonstructural controls on discharges that occur both inside and outside the urbanized area. If the permittee chooses to implement the LPCP in its urbanized area only discharging to the impaired waterbody, the permittee must demonstrate compliance with the Phosphorus Reduction Requirement and Allowable Phosphorus Load requirements applicable to it through structural and non-structural controls on discharges that occur within the urbanized area only.

Calculate Baseline Phosphorus Load (P_{base}), Phosphorus Reduction Requirement (P_{RR}) and Allowable Phosphorus Load (P_{allow}) —Permittees shall calculate their numerical Allowable Phosphorus Load and Phosphorus Reduction Requirement in mass/yr by first estimating their Baseline Phosphorus Load in mass/yr from its LPCP Area consistent with the methodology in Attachment 1 to Appendix F, the baseline shall only be estimated using land use phosphorus export coefficients in Attachment 1 to Appendix F and not account for phosphorus reductions resulting from implemented structural BMPs completed to date. Table F-6 contains the

percent phosphorus reduction required from urban stormwater consistent with the TMDL of each impaired waterbody. The permittee shall apply the applicable required percent reduction in Table F-6 to the calculated Baseline Phosphorus Load to obtain the permittee specific Allowable Phosphorus Load. The Allowable Phosphorus Load shall then be subtracted from the Baseline Phosphorus Load to obtain the permittee specific Phosphorus Reduction Requirement in mass/yr.

Description of planned non-structural controls – The permittee shall describe the non-structural stormwater control measures to be implemented to support the achievement of the milestones in Table F-7. The description of non-structural controls shall include the planned measures, the areas where the measures will be implemented, and the annual phosphorus reductions that are expected to result from their implementation. Annual phosphorus reduction from non-structural BMPs shall be calculated consistent with Attachment 2 to Appendix F. The permittee shall update the description of planned non-structural controls as needed to support the achievement of the milestones in Table F-7, including an update in the updated written LPCP 10 years after the permit effective date.

Description of planned structural controls – The permittee shall develop a priority ranking of areas and infrastructure within the municipality for potential implementation of phosphorus control practices. The ranking shall be developed through the use of available screening and monitoring results collected during the permit term either by the permittee or another entity and the mapping required pursuant to part 2.3.4.6 of the Permit. The permittee shall also include in this prioritization a detailed assessment of site suitability for potential phosphorus control measures based on soil types and other factors. The permittee shall coordinate this activity with the requirements of part 2.3.6.8.b of the Permit. A description and the result of this priority ranking shall be included in the LPCP. The permittee shall describe the structural stormwater control measures necessary to support achievement of the milestones in Table F-7. The description of structural controls shall include the planned measures, the areas where the measures will be implemented, and the annual phosphorus reductions in units of mass/yr that are expected to result from their implementation. Structural measures to be implemented by a third party may be included in the LPCP. Annual phosphorus reduction from structural BMPs shall be calculated consistent with Attachment 3 to Appendix F. The permittee shall update the description of planned structural controls as needed to support the achievement of the milestones in Table F-7, including an update in the updated written LPCP 10 years after the permit effective date.

Description of Operation and Maintenance (O&M) Program for all planned and existing structural BMPs — The permittee shall establish an Operation and Maintenance Program for all structural BMPs being claimed for phosphorus reduction credit as part of Phase 1 and 2 of the PCP. This includes BMPs implemented to date as well as BMPs to be implemented during Phase 2 of the PCP. The Operation and Maintenance Program shall become part of the PCP and include: (1) inspection and maintenance schedule for each BMP according to BMP design or manufacturer specification and (2) program or department responsible for BMP maintenance.

Implementation Schedule – An initial schedule for implementing the BMPs, including, as appropriate: funding, training, purchasing, construction, inspections, monitoring, O&M and other assessment and evaluation components of implementation. Implementation of planned BMPs must begin upon completion of the LPCP, and all non-structural BMPs shall be fully implemented within six years of the permit effective date. Where planned structural BMP retrofits or major drainage infrastructure projects are expected to take additional time to construct, the permittee shall within four years of the effective date of the permit have a schedule for completion of construction consistent with the reduction requirements in Table F-7. The permittee shall complete the implementation of its LPCP as soon as possible or at a minimum in accordance with the milestones set forth in Table F-7. The implementation schedule shall be updated as needed to support the achievement of the milestones in Table F-7, including an update in the updated written LPCP 10 years after the permit effective date.

<u>Cost and funding source assessment</u> – The permittee shall estimate the cost for implementing its LPCP and describe known and anticipated funding mechanisms. The permittee shall describe the steps it will take to implement its funding plan. This may include but is not limited to conceptual development, outreach to affected parties, and development of legal authorities.

Complete written LPCP – The permittee must complete the written LPCP 5 years after permit effective date. The complete LPCP shall include item numbers 1-8 in Table F-7. The permittee shall make the LPCP available to the public for public comment during the LPCP development. EPA encourages the permittee to post the LPCP online to facilitate public involvement. The LPCP shall be updated as needed with an update 10 years after the permit effective date at a minimum to reflect changes in BMP implementation to support achievement of the phosphorus export milestones in Table F-7. The updated LPCP shall build upon the original LPCP and include additional or new BMPs the permittee will use to support the achievement of the milestones in Table F-7.

<u>Performance Evaluation</u> – The permittee shall evaluate the effectiveness of the LPCP by tracking the phosphorus reductions achieved through implementation of structural and non-structural BMPs¹² and tracking increases in phosphorus loading from the LPCP Area beginning six years after the effective date of the permit. Phosphorus reductions shall be calculated consistent with Attachment 2 (non-structural BMP performance), Attachment 3 (structural BMP performance) and Attachment 1 (reductions through land use change), to Appendix F for all BMPs implemented to date¹³. Phosphorus load increases resulting from development shall be calculated consistent with Attachment 1 to Appendix F. Phosphorus

¹² In meeting its phosphorus reduction requirements a permittee may quantify phosphorus reductions by actions undertaken by another entity, except where those actions are credited to MassDOT or another permittee identified in Appendix F Table F-7

¹³ Annual phosphorus reductions from structural BMPs installed in the LPCP Area prior to the effective date of this permit shall be calculated consistent with Attachment 3 to Appendix F. Phosphorus Reduction Credit for previously installed BMPs will only be given if the Permittee demonstrates that the BMP is performing up to design specifications and certifies that the BMP is properly maintained and inspected according to manufacturer design or specifications. This certification shall be part of the annual performance evaluation during the year credit is claimed for the previously installed BMP.

loading increases and reductions in units of mass/yr shall be added or subtracted from the calculated Baseline Phosphorus Load to estimate the yearly phosphorous export rate from the LPCP Area in mass/yr. The permittee shall also include all information required in part II.2 of this Appendix in each performance evaluation.

2. Reporting

Beginning 1 year after the permit effective date, the permittee shall include a progress report in each annual report on the planning and implementation of the LPCP.

Beginning five (5) years after the permit effective date, the permittee shall include the following in each annual report submitted pursuant to part 4.4 of the Permit:

- a. All non-structural control measures implemented during the reporting year along with the phosphorus reduction in mass/yr (P_{NSred}) calculated consistent with Attachment 2 to Appendix F
- b. Structural controls implemented during the reporting year and all previous years including:
 - a. Location information of structural BMPs (GPS coordinates or street address)
 - b. Phosphorus reduction from all structural BMPs implemented to date in mass/yr (P_{Sred}) calculated consistent with Attachment 3 to Appendix F
 - c. Date of last completed maintenance for each Structural control
- c. Phosphorus load increases due to development over the previous reporting period and incurred to date (P_{DEVinc}) calculated consistent with Attachment 1 to Appendix F.
- d. Estimated yearly phosphorus export rate (P_{exp}) from the LPCP Area calculated using Equation 2. Equation 2 calculates the yearly phosphorus export rate by subtracting yearly phosphorus reductions through implemented nonstructural controls and structural controls to date from the Baseline Phosphorus Load and adding loading increases incurred through development to date. This equation shall be used to demonstrate compliance with the phosphorus reduction milestones required as part of each phase of the LPCP.

$$P_{exp}\left(\frac{mass}{yr}\right) = P_{base}\left(\frac{mass}{yr}\right) - \left(P_{Sred}\left(\frac{mass}{yr}\right) + P_{NSred}\left(\frac{mass}{yr}\right)\right) + P_{DEVinc}\left(\frac{mass}{yr}\right)$$

Equation 2. Equation used to calculate yearly phosphorus export rate from the chosen LPCP Area. P_{exp} =Current phosphorus export rate from the LPCP Area in mass/year. P_{base} =baseline phosphorus export rate from LPCP Area in mass/year. P_{Sred} = yearly phosphorus reduction from implemented structural controls in the LPCP Area in mass/year. P_{NSred} = yearly phosphorus reduction from implemented non-structural controls in the LPCP Area in mass/year. Area in mass/year. P_{DEVinc} = yearly phosphorus increase resulting from development since the year baseline loading was calculated in the LPCP Area in mass/year.

e. Certification that all structural BMPs are being inspected and maintained according to the O&M program specified as part of the PCP. The certification statement shall be:

I certify under penalty of law that all source control and treatment Best Management Practices being claimed for phosphorus reduction credit have been inspected, maintained and repaired in accordance with manufacturer or design specification. I certify that, to the best of my knowledge, all Best Management

Practices being claimed for a phosphorus reduction credit are performing as originally designed.

- f. Certification that all municipally owned and maintained turf grass areas are being managed in accordance with Massachusetts Regulation 331 CMR 31 pertaining to proper use of fertilizers on turf grasses (see http://www.mass.gov/courts/docs/lawlib/300-399cmr/330cmr31.pdf).
- 3. At any time during the permit term the permittee may be relieved of additional requirements in Appendix F part A.II.1. as follows:
 - a. The permittee is relieved of its additional requirements as of the date when the following conditions are met:
 - i. The applicable TMDL has been modified, revised or withdrawn and EPA has approved a new TMDL applicable for the receiving water that indicates that no additional stormwater controls for the control of phosphorus are necessary for the permittee's discharge based on wasteload allocations in the newly approved TMDL
 - b. In such a case, the permittee shall document the date of the approved TMDL in its SWMP and is relieved of any additional remaining requirements of Appendix F part A.II.1 as of that date and the permittee shall comply with the following:
 - i. The permittee shall identify in its SWMP all activities implemented in accordance with the requirements of Appendix F part A.II.1 to date to reduce phosphorus in their discharges including implementation schedules for non-structural BMPs and any maintenance requirements for structural BMPs
 - ii. The permittee shall continue to implement all requirements of Appendix F part A.I.1 required to be implemented prior to the date of the newly approved TMDL, including ongoing implementation of identified non-structural BMPs and routine maintenance and replacement of all structural BMPs in accordance with manufacturer or design specifications, and the reporting requirements of Appendix F part A.II.2. remain in place.

B. Requirements for Discharges to Impaired Waters with an Approved Out of State TMDL

I. Nitrogen TMDL Requirements

Discharges from MS4s in Massachusetts to waters that are tributaries to the Long Island Sound, which has an approved TMDL for nitrogen¹⁷, are subject to the requirements of this part.

1. The operators of traditional and non-traditional MS4s located in municipalities listed in Table F-11 shall comply with the following BMPs in addition to the requirements of part 2.3 of the Permit, as described below:

a. Enhanced BMPs

- i. Enhancement of BMPs required by part 2.3 of the permit that shall be implemented during this permit term:
 - 1. part 2.3.2, Public education and outreach: The permittee shall supplement its Residential and Business/Commercial/Institution program with annual timed messages on specific topics. The permittee shall distribute an annual message in the spring (April/May) timeframe that encourages the proper use and disposal of grass clippings and encourages the proper use of slow-release fertilizers. The permittee shall distribute an annual message in the summer (June/July) timeframe encouraging the proper management of pet waste, including noting any existing ordinances where appropriate. The permittee shall distribute an annual message in the Fall (August/September/October) timeframe encouraging the proper disposal of leaf litter. The permittee shall deliver an annual message on each of these topics, unless the permittee determines that one or more of these issues is not a significant contributor of nitrogen to discharges from the MS4 and the permittee retains documentation of this finding in the SWMP. All public education messages can be combined with requirements of Appendix H part I, II and III as well as Appendix F part A.III, A.IV, A.V, B.II and B.III where appropriate.
 - 2. part 2.3.6, Stormwater Management in New Development and Redevelopment: the requirement for adoption/amendment of the permittee's ordinance or other regulatory mechanism shall include a requirement that new development and redevelopment stormwater management BMPs be optimized for nitrogen removal; retrofit inventory and priority ranking under 2.3.6.1.b shall include consideration of BMPs to reduce nitrogen discharges.
 - 3. part 2.3.7, Good House Keeping and Pollution Prevention for Permittee Owned Operations: establish requirements for use of

¹⁷ Connecticut Department of Environmental Protection. 2000. A Total Maximum Daily Load Analysis to Achieve Water Quality Standards for Dissolved Oxygen in Long Island Sound

slow release fertilizers on permittee owned property currently using fertilizer, in addition to reducing and managing fertilizer use as provided in in part 2.3.7.1; establish procedures to properly manage grass cuttings and leaf litter on permittee property, including prohibiting blowing organic waste materials onto adjacent impervious surfaces; increased street sweeping frequency of all municipal owned streets and parking lots subject to Permit part 2.3.7.a.iii.(c) to a minimum of two (2) times per year, once in the spring (following winter activities such as sanding) and at least once in the fall (Sept 1 – Dec 1; following leaf fall).

b. Nitrogen Source Identification Report

- i. Within four years of the permit effective date the permittee shall complete a Nitrogen Source Identification Report. The report shall include the following elements:
 - Calculation of total urbanized area within the permittee's jurisdiction that is within the Connecticut River Watershed, the Housatonic River Watershed, or the Thames River Watershed, incorporating updated mapping of the MS4 and catchment delineations produced pursuant to part 2.3.4.6,
 - 2. All screening and monitoring results pursuant to part 2.3.4.7.d., targeting the receiving water segment(s)
 - 3. Impervious area and DCIA for the target catchment
 - 4. Identification, delineation and prioritization of potential catchments with high nitrogen loading
 - 5. Identification of potential retrofit opportunities or opportunities for the installation of structural BMPs during re-development
- ii. The final Nitrogen Source Identification Report shall be submitted to EPA as part of the year 4 annual report.

c. Structural BMPs

- i. Within five years of the permit effective date, the permittee shall evaluate all properties identified as presenting retrofit opportunities or areas for structural BMP installation under permit part 2.3.6.d.ii. or identified in the Nitrogen Source Identification Report. The evaluation shall include:
 - 1. The next planned infrastructure, resurfacing or redevelopment activity planned for the property (if applicable) OR planned retrofit date;
 - 2. The estimated cost of redevelopment or retrofit BMPs; and
 - 3. The engineering and regulatory feasibility of redevelopment or retrofit BMPs.
- ii. The permittee shall provide a listing of planned structural BMPs and a plan and schedule for implementation in the year 5 annual

report. The permittee shall plan and install a minimum of one structural BMP as a demonstration project within six years of the permit effective date. The demonstration project shall be installed targeting a catchment with high nitrogen load potential. The permittee shall install the remainder of the structural BMPs in accordance with the plan and schedule provided in the year 5 annual report.

iii. Any structural BMPs listed in Table 4-3 of Attachment 1 to Appendix H installed in the urbanized area by the permittee or its agents shall be tracked and the permittee shall estimate the nitrogen removal by the BMP consistent with Attachment 1 to Appendix H. The permittee shall document the BMP type, total area treated by the BMP, the design storage volume of the BMP and the estimated nitrogen removed in mass per year by the BMP in each annual report.

| Adams | North Adams |
|-----------------|------------------|
| Agawam | Northampton |
| Amherst | Oxford |
| Ashburnham | Palmer |
| Ashby | Paxton |
| Auburn | Pelham |
| Belchertown | Pittsfield |
| Charlton | Richmond |
| Cheshire | Russell |
| Chicopee | Rutland |
| Dalton | South Hadley |
| Douglas | Southampton |
| Dudley | Southbridge |
| East Longmeadow | Southwick |
| Easthampton | Spencer |
| Gardner | Springfield |
| Granby | Sturbridge |
| Hadley | Sutton |
| Hampden | Templeton |
| Hatfield | Ware |
| Hinsdale | Webster |
| Holyoke | West Springfield |
| Lanesborough | Westfield |
| Leicester | Westhampton |
| Lenox | Westminster |
| Longmeadow | Wilbraham |
| Ludlow | Williamsburg |
| Millbury | Winchendon |

Monson

Table F-11: Massachusetts municipalities in which MS4 discharges are within the Connecticut River Watershed, the Housatonic River Watershed. or the Thames River Watershed.

2. At any time during the permit term the permittee may be relieved of additional requirements in Appendix F part B.I.1. as follows:

- a. The permittee is relieved of its additional requirements as of the date when the following conditions are met:
 - i. The applicable TMDL has been modified, revised or withdrawn and EPA has approved a new TMDL applicable for the receiving water that indicates that no additional stormwater controls for the control of nitrogen are necessary for the permittee's discharge based on wasteload allocations in the newly approved TMDL
- b. In such a case, the permittee shall document the date of the approved TMDL in its SWMP and is relieved of any remaining requirements of Appendix F part B.I.1 as of that date and the permittee shall comply with the following:
 - i. The permittee shall identify in its SWMP all activities implemented in accordance with the requirements of Appendix F part B.I.1 to date to reduce nitrogen in their discharges including implementation schedules for non-structural BMPs and any maintenance requirements for structural BMPs
 - ii. The permittee shall continue to implement all requirements of Appendix F part B.I.1 required to be implemented prior to the date of the newly approved TMDL, including ongoing implementation of identified non-structural BMPs and routine maintenance and replacement of all structural BMPs in accordance with manufacturer or design specifications.

APPENDIX H

Requirements Related to Discharges to Certain Water Quality Limited Waterbodies

| | | | • | \sim | 4 | 4 |
|----|-----|---|-----|--------|-----|-----|
| 10 | nı | Δ | Λt | Co | nto | ntc |
| 14 | .,, | | 171 | \ \U | ш | |

| I. | Discharges to water quality limited waterbodies and their tributaries where nitrogen is the cause of the impairment |
|------|---|
| II. | Discharges to water quality limited waterbodies and their tributaries where phosphorus is the cause of the impairment |
| III. | Discharges to water quality limited waterbodies where bacteria or pathogens is the cause of the impairment |
| IV. | Discharges to water quality limited waterbodies where chloride is the cause of the impairment |
| V. | Discharges to water quality limited waterbodies and their tributaries where solids, oil and grease (hydrocarbons), or metals is the cause of the impairment |
| | |

Attachment 1- Nitrogen Reduction Credits For Selected Structural BMPs

I. <u>Discharges to water quality limited waterbodies and their tributaries where nitrogen is the cause of the impairment</u>

1. Part 2.2.2.a.i. of the permit identifies the permittees subject to additional requirements to address nitrogen in their stormwater discharges because they discharge to waterbodies that are water quality limited due to nitrogen, or their tributaries, without an EPA approved TMDL. Permittees identified in part 2.2.2.a.i of the permit must identify and implement BMPs designed to reduce nitrogen discharges in the impaired catchment(s). To address nitrogen discharges each permittee shall comply with the following requirements:

a. Additional or Enhanced BMPs

- i. The permittee remains subject to all the requirements of part 2.3. of the permit and shall include the following enhancements to the BMPs required by part 2.3 of the permit:
 - 1. Part 2.3.2, Public education and outreach: The permittee shall supplement its Residential and Business/Commercial/Institution program with annual timed messages on specific topics. The permittee shall distribute an annual message in the spring (April/May) timeframe that encourages the proper use and disposal of grass clippings and encourages the proper use of slow-release fertilizers. The permittee shall distribute an annual message in the summer (June/July) timeframe encouraging the proper management of pet waste, including noting any existing ordinances where appropriate. The permittee shall distribute an annual message in the Fall (August/September/October) timeframe encouraging the proper disposal of leaf litter. The permittee shall deliver an annual

III. <u>Discharges to water quality limited waterbodies where bacteria or pathogens is the cause of</u> the impairment

1. Consistent with part 2.2.2.c.i. of the permit, permittees that discharge to waterbodies that are water quality limited due to bacteria or pathogens, without an EPA approved TMDL, are subject to the following additional requirements to address bacteria or pathogens in their stormwater discharges.

2. Additional or Enhanced BMPs

- a. The permittee remains subject to the requirements of part 2.3. of the permit and shall include the following enhancements to the BMPs required by part 2.3 of the permit:
 - i. Part 2.3.2. Public Education and outreach: The permittee shall supplement its Residential program with an annual message encouraging the proper management of pet waste, including noting any existing ordinances where appropriate. The permittee or its agents shall disseminate educational materials to dog owners at the time of issuance or renewal of a dog license, or other appropriate time. Education materials shall describe the detrimental impacts of improper management of pet waste, requirements for waste collection and disposal, and penalties for non-compliance. The permittee shall also provide information to owners of septic systems about proper maintenance in any catchment that discharges to a water body impaired for bacteria or pathogens. All public education messages can be combined with requirements of Appendix H part I and II as well as Appendix F part A.III, A.IV, A.V, B.I, B.II and B.III where appropriate.
 - ii. Part 2.3.4 Illicit Discharge: The permittee shall implement the illicit discharge program required by this permit. Catchments draining to any waterbody impaired for bacteria or pathogens shall be designated either Problem Catchments or HIGH priority in implementation of the IDDE program.
- 3. At any time during the permit term the permittee may be relieved of additional requirements in Appendix H part III.2. applicable to it when in compliance with this part.
 - a. The permittee is relieved of its additional requirements as of the date when one of the following criteria are met:
 - i. The receiving water is determined to be no longer impaired due to bacteria or pathogens by MassDEP and EPA concurs with such a determination.
 - ii. An EPA approved TMDL for the receiving water indicates that no additional stormwater controls are necessary for the control of bacteria or pathogens from the permittee's discharge based on wasteload allocations as part of the approved TMDL.
 - iii. The permittee's discharge is determined to be below applicable water quality criteria¹ and EPA agrees with such a determination. The permittee shall submit data to EPA that accurately characterizes the concentration of bacteria or pathogens in their discharge. The characterization shall include water quality

¹ Applicable water quality criteria are the state standards that have been federally approved as of the effective date of this permit and are compiled by EPA at http://www.epa.gov/waterscience/standards/wqslibrary/

Page 8 of 14

MA MS4 General Permit Appendix H

- and flow data sufficient to accurately assess the concentration of bacteria or pathogens in all seasons during storm events of multiple sizes and for the duration of the storm events including the first flush, peak storm flow and return to baseflow.
- b. In such a case, the permittee shall document the date of the determination, date of approved TMDL or date of EPA concurrence that the discharge meets water quality criteria in its SWMP and is relieved of any additional requirements of Appendix H part III.2. as of that date and the permittee shall comply with the following:
 - The permittee shall identify in its SWMP all activities implemented in accordance with the requirements of Appendix H part III.2. to date to reduce bacteria or pathogens in its discharges, including implementation schedules for non-structural BMPs and any maintenance requirements for structural BMPs
 - ii. The permittee shall continue to implement all requirements of Appendix H part III.3. required to be done prior to the date of determination date, date of approved TMDL, or date of EPA concurrence that the discharge meets water quality criteria, including ongoing implementation of identified non-structural BMPs and routine maintenance and replacement of all structural BMPs in accordance with manufacturer or design specifications

ATTACHMENT 1 TO APPENDIX H

The estimates of nitrogen load reductions resulting from BMP installation are intended for informational purposes only and there is no associated permittee-specific required nitrogen load reduction in the Draft Permit. Nitrogen load reduction estimates calculated consistent with the methodologies below may be used by the permittee to comply with future permit requirements providing the EPA determines the calculated reductions are appropriate for demonstrating compliance with future permit requirements. This attachment provides the method and an example to calculate the BMP nitrogen load as well as methods to calculate nitrogen load reductions for structural BMPs in an impaired watershed.

BMP N Load:

The **BMP** N Load is the annual nitrogen load from the drainage area to each proposed or existing BMP used by permittee. This measure is used to estimate the amount of annual nitrogen load that the BMP will receive or treat (BMP N Load).

To calculate the BMP N Load for a given BMP:

- 1) Determine the total drainage area to the BMP and sort the total drainage area into two categories: total impervious area (IA) and total pervious area (PA);
- 2) Calculate the nitrogen load associated with impervious area (N Load _{IA}) and the pervious area (N Load _{PA}) by multiplying the IA and PA by the appropriate land use-based nitrogen load export rate provided in Table 1; and
- 3) Determine the total nitrogen load to the BMP by summing the calculated impervious and pervious subarea nitrogen loads.

Table 1: Annual nitrogen load export rates

| Nitrogen Source Category by | Land Surface | Nitrogen Load Export Rate, | Nitrogen Load Export Rate, |
|-----------------------------|--------------|-------------------------------|-------------------------------|
| Land Use | Cover | lbs/ac/yr | kg/ha/yr |
| All Impervious Cover | Impervious | 14.1 | 15.8 |
| *Developed Land Pervious | | | |
| (DevPERV)- HSG A | Pervious | 0.3 | 0.3 |
| *Developed Land Pervious | | | |
| (DevPERV)- HSG B | Pervious | 1.2 | 1.3 |
| *Developed Land Pervious | | | |
| (DevPERV) – HSG C | Pervious | 2.4 | 2.7 |
| *Developed Land Pervious | | | |
| (DevPERV) - HSG C/D | Pervious | 3.0 | 3.4 |
| *Developed Land Pervious | | | |
| (DevPERV) - HSG D | Pervious | 3.7 | 4.1 |

Notes: For pervious areas, if the hydrologic soil group (HSG) is known, use the appropriate value from this table. If the HSG is not known, assume HSG C/D conditions for the nitrogen load export rate.

Example 1 to determine nitrogen load to a proposed BMP when the contributing drainage area is 100% impervious: A permittee is proposing a storm water infiltration system that will treat runoff from 1.49 acres of impervious area.

| Table 1-1: Design | parameters for | · Bio-filtration w | y/ ISR s | vstems for Exampl | le 1 |
|-------------------|----------------|--------------------|----------|-------------------|------|
| | | | | | |

| Components of representation | Parameters | Value |
|-----------------------------------|------------------------|--------------------------------------|
| Donding | Maximum depth | 0.33 ft |
| Ponding | Surface area | 645 ft ² |
| | Depth | 2.0 ft |
| Soil mix | Porosity | 0.24 |
| | Hydraulic conductivity | 2.5 inches/hour |
| | Depth | 2.50 ft |
| Stone Reservoir (ISR) | Porosity | 0.42 |
| | Hydraulic conductivity | 500 inches/hour |
| ISR Volume: System Storage Volume | Ratio | 0.56 |
| | | 12 in |
| Orifices | Diameter | Installed 2.5 above impermeable soil |
| | | layer |

Determine:

- **A)** Percent nitrogen load reduction (BMP Reduction %-N) for the specified bio-filtration w/ISR system and contributing impervious drainage area; and
- **B)** Nitrogen reduction in pounds that would be accomplished by the bio-filtration w/ISR system (BMP-Reduction _{lbs-N})

Solution:

- 1) The BMP is a bio-filtration w/ISR system that will treat runoff from 1.49 acres of impervious area (IA = 1.49 acre);
- 2) The available storage volume capacity (ft³) of the bio-filtration w/ISR system (BMP-Volume BMP-ft³) is determined using the surface area of the system, depth of ponding, the porosity of the filter media and the porosity of the stone reservoir:

BMP-Volume
$$_{BMP-ft}^3$$
 =Surface area x (pond maximum depth + (soil mix depth x soil mix porosity) + stone reservoir depth x gravel layer porosity)) = 520 ft² x (0.33 ft + (2.0ft x 0.24) + (2.5 ft x 0.42)) = 1,200 ft³

3) The available storage volume capacity of the bio-filtration w/ISR system in inches of runoff from the contributing impervious area (BMP-Volume IA-in) is calculated using equation 1:

BMP-Volume $_{\text{IA-in}} = (BMP\text{-Volume }_{\text{ft}}^3/\text{ IA (acre)} \times 12 \text{ in/ft } \times 1 \text{ acre/43560 ft}^2 \text{ (Equation 1)}$

Example 1 Continued:

BMP-Volume _{IA-in} =
$$(1,200 \text{ ft}^3/1.49 \text{ acre}) \times 12 \text{ in/ft} \times 1 \text{ acre/}43560 \text{ ft}^2$$

= **0.22 in**

- **4)** Using the Regional Performance Curve shown in Figure 1 for a bio-filtration w/ ISR system, a **61%** nitrogen load reduction (BMP Reduction %-N) is determined for a bio-filtration w/ ISR systems sized for 0.22 in of runoff from 1.49 acres of impervious area; and
- 5) Calculate the nitrogen load reduction in pounds of nitrogen for the bio-filtration w/ISR system (BMP Reduction _{lbs-N}) using the BMP Load calculation method shown above in Example 1 and the BMP Reduction _{%-N} determined in step 4 by using equation 2.

First, the BMP Load is determined as specified in Example 1:

```
BMP Load = IA (acre) x 14.1 lb/ac/yr

= 1.49 acres x 14.1 lbs/acre/yr


= 21.0 lbs/yr

BMP Reduction _{lbs-N} = BMP Load x (BMP Reduction _{\%-N}/100) (Equation 2)

BMP Reduction _{lbs-N} = 21 lbs/yr x (61/100)

= 12.8 lbs/yr
```

Method to determine the nitrogen load reduction for a structural BMP with a known storage volume when the contributing drainage area has impervious and pervious surfaces



Flow Chart 2 (previous page). Method to determine the nitrogen load reduction for a BMP with known storage volume when both pervious and impervious drainage areas are present.

1) Identify the type of structural BMP and characterize the contributing drainage area to the structural BMP by identifying the following information for the impervious and pervious surfaces:

Impervious area (IA) – Area (acre) and export rate (Table 1)

Pervious area (**PA**) – Area (acre) and runoff depth based on hydrologic soil group (HSG) and size of rainfall event. Table 2 provides values of runoff depth for various rainfall depths and HSGs. Soils are assigned to an HSG based on their permeability. HSG categories for pervious areas in the Watershed shall be estimated by consulting local soil surveys prepared by the National Resource Conservation Service (NRCS) or by a storm water professional evaluating soil testing results from the Watershed. If the HSG condition is not known, a HSG D soil condition should be assumed.

Table 2: Developed Land Pervious Area Runoff Depths based on Precipitation depth and Hydrological Soil Groups (HSGs)

| | Runoff Depth, inches | | |
|-----------------|----------------------|--------------|--------------|
| Rainfall Depth, | Pervious HSG | Pervious HSG | Pervious HSG |
| Inches | A/B | C | D |
| 0.10 | 0.00 | 0.00 | 0.00 |
| 0.20 | 0.00 | 0.01 | 0.02 |
| 0.40 | 0.00 | 0.03 | 0.06 |
| 0.50 | 0.00 | 0.05 | 0.09 |
| 0.60 | 0.01 | 0.06 | 0.11 |
| 0.80 | 0.02 | 0.09 | 0.16 |
| 1.00 | 0.03 | 0.12 | 0.21 |
| 1.20 | 0.04 | 0.14 | 0.39 |
| 1.50 | 0.11 | 0.39 | 0.72 |
| 2.00 | 0.24 | 0.69 | 1.08 |

Notes: Runoff depths derived from combination of volumetric runoff coefficients from Table 5 of *Small Storm Hydrology and Why it is Important for the Design of Stormwater Control Practices*, Pitt, 1999 and using the Stormwater Management Model (SWMM) in continuous model mode for hourly precipitation data for Boston, MA, 1998-2002.

2) Determine the available storage volume (ft³) of the structural BMP (BMP-Volume ft³) using the BMP dimensions and design specifications (e.g., maximum storage depth, filter media porosity);

3) To estimate the nitrogen load reduction of a BMP with a known storage volume capacity, it is first necessary to determine the portion of available BMP storage capacity (BMP-Volume ft³) that would treat the runoff volume generated from the contributing impervious area (IA) for a rainfall event with a depth of *i* inches (in). This will require knowing the corresponding amount of runoff volume that would be generated from the contributing pervious area (PA) for the same rainfall event (depth of *i* inches). Using equation 3 below, solve for the BMP capacity that would be available to treat runoff from the contributing imperious area for the unknown rainfall depth of *i* inches (see equation 4):

BMP-Volume $_{fi}^3$ = BMP-Volume $_{(IA-fi}^3)_i$ + BMP-Volume $_{(PA-fi}^3)_i$ (Equation 3)

Where:

BMP-Volume $_{\rm ft}^3$ = the available storage volume of the BMP

BMP-Volume $_{(IA-fl^3)i}$ = the available storage volume of the BMP that would fully

treat runoff generated from the contributing impervious

area for a rainfall event of size *i* inches

BMP-Volume $_{(PA-ft^3)i}$ = the available storage volume of the BMP that would fully

treat runoff generated from the contributing pervious area

for a rainfall event of size *i* inches

Solving for BMP-Volume (IA-ft³)i:

BMP-Volume $_{(IA-ft^3)i}$ = BMP-Volume $_{ft^3}$ - BMP-Volume $_{(PA-ft^3)i}$ (**Equation 4**)

To determine BMP-Volume (IA-ft³)i, requires performing an iterative process of refining estimates of the rainfall depth used to calculate runoff volumes until the rainfall depth used results in the sum of runoff volumes from the contributing IA and PA equaling the available BMP storage capacity (BMP-Volume ft³). For the purpose of estimating BMP performance, it will be considered adequate when the IA runoff depth (in) is within 5% IA runoff depth used in the previous iteration.

For the first iteration (1), convert the BMP-Volume ft³ determined in step 2 into inches of runoff from the contributing impervious area (BMP Volume (IA-in)1) using equation 5.

BMP-Volume $_{(IA-in)l} = (BMP-Volume_{ft}^3/IA (acre)) \times (12 in/ft/43,560 ft^2/acre)$ (**Equation 5**);

For iterations 2 through n (2...n), convert the BMP Volume (IA-ft³)2...n, determined in step 5a below, into inches of runoff from the contributing impervious area (BMP Volume (IA-in)2...n) using equation 6.

BMP-Volume $_{(IA-in)2...n}$ = (BMP-Volume $_{(IA-ft^3)2...n}$ / IA (acre)) x (12 in/ft /43,560 ft²/acre) (**Equation 6**);

4) For 1 to n iterations, use the pervious runoff depth information from Table 2 and equation 7 to determine the total volume of runoff (ft³) from the contributing PA (BMP Volume

PA-ft³) for a rainfall size equal to the sum of BMP-Volume (IA-in)1, determined in step 3. The runoff volume for each distinct pervious area must be determined.

BMP Volume
$$_{(PA-ft^3)_{1...n}} = \sum ((PA \times (runoff depth)_{(PA1, PA2..PAn)} \times (3,630 \text{ ft}^3/acre-in))$$
 (**Equation 7**)

5) For iteration 1, estimate the portion of BMP Volume that is available to treat runoff from only the IA by subtracting BMP-Volume PA-ft³, determined in step 4, from BMP-Volume ft³, determined in step 2, and convert to inches of runoff from IA (see equations 8 and 9):

BMP-Volume
$$(IA-ft^3)2 = ((BMP-Volume_{ft}^3 - BMP Volume_{(PA-ft^3)1})$$
 (**Equation 8**)

BMP-Volume
$$_{(IA-in)2} = (BMP-Volume_{(IA-ft}^3)_2/IA_{(acre)}) \times (12_{in}/ft \times 1_{acre}/43,560_{ft}^2)$$
 (**Equation 9**)

If additional iterations (i.e., 2 through n) are needed, estimate the portion of BMP volume that is available to treat runoff from only the IA (BMP-Volume (IA-in)3..n+1) by subtracting BMP Volume (PA-ft³)2..n, determined in step 4, from BMP Volume (IA-ft³)3..n+1, determined in step 5, and by converting to inches of runoff from IA using equation 9):

- 6) For iteration A (an iteration between 1 and n+1), compare BMP Volume (IA-in)a to BMP Volume (IA-in)a-1 determined from the previous iteration (a-1). If the difference in these values is greater than 5% of BMP Volume (IA-in)a then repeat steps 4 and 5, using BMP Volume (IA-in)a as the new starting value for the next iteration (a+1). If the difference is less than or equal to 5 % of BMP Volume (IA-in)a then the permittee may proceed to step 7.
- 7) Determine the % nitrogen load reduction for the structural BMP (BMP Reduction %-N) using the appropriate BMP curve on Figure 1 or 2 and the BMP-Volume (IA-in)n calculated in the final iteration of step 5; and
- 8) Calculate the nitrogen load reduction in pounds of nitrogen for the structural BMP (BMP Reduction _{lbs-N}) using the BMP Load as calculated above in Example 1 and the percent nitrogen load reduction (BMP Reduction _{%-N}) determined in step 7 by using equation 10:

BMP Reduction $_{lbs-N}$ = BMP Load x (BMP Reduction $_{hbs-N}/100$) (**Equation 10**)

Example 2: Determine the nitrogen load reduction for a structural BMP with a known design volume when the contributing drainage area has impervious and pervious surfaces

A permittee is considering an infiltration basin to capture and treat runoff from a portion of the Watershed draining to the impaired waterbody. The contributing drainage area is 16.55 acres and is 71% impervious. The pervious drainage area (PA) is 80% HSG D and 20% HSG C. An infiltration basin with the following specifications can be placed at the down-gradient end of the contributing drainage area where soil testing results indicates an infiltration rate (IR) of 0.28 in/hr:

Example continued:

| | Bottom | Top | Maximum | Design | Infiltration |
|--------------------|--------|-------------|------------|--------------|--------------|
| Structure | area | surface | pond depth | storage | Rate |
| | (acre) | area (acre) | (ft) | volume (ft³) | (in/hr) |
| Infiltration basin | 0.65 | 0.69 | 1.65 | 48,155 | 0.28 |

Determine the:

- **A)** Percent nitrogen load reduction (BMP Reduction %-N) for the specified infiltration basin and the contributing impervious and pervious drainage area; and
- **B**) Nitrogen reduction in pounds that would be accomplished by the BMP (BMP-Reduction _{lbs-N})

Solution:

1) A surface infiltration basin is being considered. Information for the contributing impervious (IA) and pervious (PA) areas are summarized in below.

Impervious area characteristics

| imper vious area characteristics | | |
|----------------------------------|--------------|-------------|
| ID | % Impervious | Area (acre) |
| IA1 | 100 | 11.75 |

Pervious area characteristics

| ID | Area (acre) | Hydrologic Soil Group (HSG) |
|-----|-------------|--------------------------------|
| PA1 | 3.84 | D |
| PA2 | 0.96 | C |

- 2) The available storage volume (ft^3) of the infiltration basin (BMP-Volume ft^3) is determined from the design details and basin dimensions; BMP-Volume $ft^3 = 48,155$ ft³.
- 3) To determine what the BMP design storage volume is in terms of runoff depth (in) from IA, an iterative process is undertaken:

Solution Iteration 1

For the first iteration (1), the BMP-Volume_{ft}³ is converted into inches of runoff from the contributing impervious area (BMP Volume (IA-in)1) using equation 5.

BMP Volume
$$_{(IA-in)1}$$
 = (48,155 ft²/ 11.75 acre) x (12 in/ft /43,560 ft²/acre) = 1.13 in

Solution Continued:

4-1) The total volume of runoff (ft³) from the contributing PA (BMP Volume PA-ft³) for a rainfall size equal to the sum of BMP Volume (IA-in)1 determined in step 3 is determined

for each distinct pervious area using the information from Table 2 and equation 7. Interpolation was used to determine runoff depths.

BMP Volume
$$_{(PA-ft^3)1}$$
 = ((3.84 acre x (0.33 in) + (0.96 acre x (0.13 in)) x 3,630 ft³/acre-in = 5052 ft³

5-1) For iteration 1, the portion of BMP Volume that is available to treat runoff from only the IA is estimated by subtracting the BMP Volume (PA-ft³)1, determined in step 4-1, from BMP Volume_{ft}³, determined in step 2, and converted to inches of runoff from IA:

BMP Volume
$$_{(IA-ft^3)}{}_2 = 48,155 \text{ ft}^3 - 5052 \text{ ft}^3$$

= 43,103 ft³
BMP Volume $_{(IA-in)}{}_2 = (43,103 \text{ ft}^3/11.75 \text{ acre}) \text{ x } (12 \text{ in/ft x } 1 \text{ acre/43,560 ft}^2)$
= 1.01 in

6-1) The % difference between BMP Volume (IA-in) 2, 1.01 in, and BMP Volume (IA-in)1, 1.13 in is determined and found to be significantly greater than 5%:

% Difference =
$$((1.13 \text{ in} - 1.01 \text{ in})/1.01 \text{ in}) \times 100$$

= 12%

Therefore, steps 4 through 6 are repeated starting with BMP Volume (IA-in) 2 = 1.01 in.

Solution Iteration 2

- **4-2**) BMP-Volume $_{(PA-ft^3)2}$ = ((3.84 acre x 0.21 in) + (0.96 acre x 0.12 in)) x 3,630 ft³/acre-in = 3,358 ft³
- **5-2)** BMP-Volume $_{(IA-ft^3)}$ 3 = 48,155 ft³ 3,358 ft³ = 44,797 ft³

BMP-Volume
$$_{(IA-in) 3} = (44,797 \text{ ft}^3/11.75 \text{ acre}) \text{ x } (12 \text{ in/ft x } 1 \text{ acre}/43,560 \text{ ft}^2)$$

= 1.05 in

6-2) % Difference =
$$((1.05 \text{ in} - 1.01 \text{ in})/1.05 \text{ in}) \times 100$$

= 4%

The difference of 4% is acceptable.

Solution Continued:

- 7) The % nitrogen load reduction for the infiltration basin (BMP Reduction %-N) is determined by using the RR treatment curve in Figure 2 and the treatment volume (BMP-Volume Net IA-in = 1.05 in) calculated in step 5-2 and is **BMP Reduction** %-N = 56%.
- 9) The nitrogen load reduction in pounds of nitrogen (BMP-Reduction _{lbs-N}) for the proposed infiltration basin is calculated by using equation 11 with the BMP Load (as determined by the procedure in Example 4-1) and the N _{target} of 56%.

```
BMP-Reduction <sub>lbs-N</sub> = BMP N Load x (N <sub>target</sub> /100) (Equation 11)
```

Following example 1, the BMP load is calculated:

```
BMP N Load = (IA x impervious cover nitrogen export loading rate)
```

+ (PA_{HSG D} x pervious cover nitrogen export loading rate, HSG D

+ (PA_{HSG C} x pervious cover nitrogen export loading rate, HSG C)

= (16.55 acre x 15.4 lbs/acre/yr) + (3.84 acre x 3.7 lbs/acre/yr) +


(0.96 acre x 2.4 lbs/acre/yr)

= 271.4 lbs/yr

BMP-Reduction $_{lbs-N} = 275.13 lbs/yr \times 56/100 = 152.0 lbs/yr$

Figure 1: Regional BMP Performance Curve for Annual Nitrogen Load Removal: System Design by the University of New Hampshire Stormwater Center (UNHSWC)

Regional BMP Performance Curve: Bio-filtration with Internal storage Reservoir (ISR) ISR Volume = 56% Total System Storage



→TN

Table 3. Classification of BMP to Determine Nitrogen Reduction¹

| Structural BMP | Classification |
|--|---------------------------|
| Infiltration Trench | Runoff Reduction (RR) |
| Infiltration Basin or other surface infiltration | Runoff Reduction (RR) |
| practice | |
| Bioretention Practice | Runoff Reduction (RR) |
| Gravel Wetland System | Stormwater Treatment (ST) |
| Porous Pavement | Runoff Reduction (RR) |
| Wet Pond or wet detention basin | Stormwater Treatment (ST) |
| Dry Pond or detention basin | Runoff Reduction (RR) |
| Water Quality Swale | Runoff Reduction (RR) |

¹Recommendations of the Expert Panel to Define Removal Rates for New State Stormwater Performance Standards http://chesapeakestormwater.net/wp-content/plugins/download-monitor/download.php?id=25, Retrieved 12/14/2012

100% 95% 90% 85% 80% 75% Total Nitrogen Removal (%) 70% 65% 60% RR 55% 50% 40% ST35% 30% 25% 20% 15% 10% 5% 0% 0.1 0.2 0.3 0.4 0.5 0.6 0.7 0.8 0.9 1 1.1 1.2 1.3 1.4 1.5 1.6 1.7 1.8 1.9 Runoff Depth Captured per Impervious Acre (inches)

Figure 2: Total Nitrogen Removal for RR and ST Practices

Adopted from: Final CBP Approved Expert Panel Report on Stormwater Retrofits http://chesapeakestormwater.net/wp-content/plugins/download-monitor/download.php?id=25, Retrieved 12/14/2012

Town of Wilbraham IDDE Program Appendix H

Tracking Implementation Goals

Town of Wilbraham IDDE Program Appendix I IDDE Training Program Log

EMPLOYEE TRAINING LOG

| Training date: | | | | |
|---|--|--|--|--|
| Title of Training: | | | | |
| Training Duration (minutes): | Training Duration (minutes): | | | |
| Subject(s) covered during Training: (Atta | ach copy of training materials, if applicable) | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| Employee(s) Trained: | Signature: | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

